LUSIKISIKI GROUNDWATER FEASIBILITY STUDY PHASE 2

Investigating the Potential to Supplement the Lusikisiki Rural Water Supply Scheme (LRWSS)

TABLE OF CONTENTS

		Storage Scheme-Zalu Dam (Fig 4, Appendix 2)			
		Dam, Xura River Rollcrete Dam (Fig 5 & 6 Appendix 2)			
		Dam, Xura River, Embankment Dam			
Option 2A: Zalu Dam, Xura River, Rockfill Dam (Fig 9 & 10, Appendix 2)					
		u Dam, Xura River, Earthfill Dam (Fig 12, 13 & 14, Appendix 2)			
		se of Surface and Groundwater Resources			
		kisiki Weir in conjunction with groundwater (98% assurance of supply)	VII		
accura	uiale Aug	gmentation Measures: Lusikisiki Weir in conjunction with Groundwater (95%	vii		
assurance of supply) Development Options/Schemes					
Water Source					
Bulk Supply System.					
Recommendations					
1. INTRODUCTION					
2.		RAL AND BASIC INFORMATION			
	2.5.1	Natal Group Sandstone	4		
	2.5.2	Dwyka Formation	e		
	2.5.3	Ecca Group	7		
3.	REVIE	W AND UPDATE OF EXISTING POPULATION INFORMATION	9		
3.1	Update	Population Based on 2001 Census	9		
	3.1.1	Eastern Cape's demographic development indicators	و		
	3.1.2	The Eastern Cape's labour and employment profile	10		
	3.1.3	EC economy compared to other provinces	12		
	3.1.4	Census 2001 for the Project Area	12		
	3.1.5	Population	13		
	3.1.6	Population Projections for Different Phases of Development	14		
4.	WATER	REQUIREMENTS	16		
4.1	Metho	dology	16		
	Water	requirements methodology (DWAF 2001)	16		
4.2	Population data		18		
	4.2.1	Urban and rural population division	18		
	Final o	calculation of water requirements	18		
4.3	Domestic and Industrial Water Requirements				
4.4	Agricu	Itural, Stock Watering and Afforestation Requirements	24		
	4.4.1	Agricultural Requirements	24		
	4.4.2	Stock Watering Requirements	25		
	4.4.3	Afforestation Requirements	26		
	4.4.4	Summary of Consumptive Water Requirements	26		
5.	LUSIKI	SIKI REGIONAL WATER SUPPLY SCHEME (LRWS)	28		
5.1		cal overview and proposed development			

5.2 5.3 5.4 5.5 6.	Water Source Bulk Water Supply Infrastructure Current Status of the Scheme Sources for Augmentation of LRWS groundwater 6.4.1 Background.		
	6.4.2	Yield of existing boreholes	34
	6.4.3	Springs	34
	6.4.4	Location of the villages that formed part of the hydrocensus	35
	6.4.5	Correlation between NGDB, Desk Study and Hydrocensus	36
	6.6.1		
	6.6.2	Dwyka Formation	41
	6.6.3	Ecca	43
6.8 7.	Groundwater targets for further drillingZalu Dam		
	7.1.1	Introduction and Catchment Characteristics.	49
	7.1.2	Catchment rainfall	49
	7.1.3	Catchment Mean Annual Precipitation	49
	7.1.4	Point Rainfall at Zalu Dam site	49
	7.1.5	Evaporation	50
	7.1.6	Afforestation	50
	7.1.7	Irrigation	50
	7.1.8	WRSM2000 model setup	50
	7.1.9	Model Calibration / Model parameters	50
	7.1.10) Results	51
	7.2.1	Monthly Inflow Record	51
	7.2.2	Point Rainfall	51
	7.2.3	Evaporation	52
	7.2.4	Stage / area / capacity relationship	52
	7.2.5	Environmental Flow requirements	52
	7.2.6	Silt Volume	52
	7.2.7	Historical firm yield analysis	52
	Catch	ment characteristics	55
	Rainfa	all	55
	Histori	ical floods	56
	Previous calculations		
	Revised flood peak determination		
	Zalu Dam Hydraulic Assessment		
		n floods for Zalu Dam spillway	
	Hydra	ulics of Zalu Dam spillway	64
	7.7.1	Methodology	71
	7.7.2	Results and discussion	72
	Surfac	ce water users	72

	Surface water quality	72
8.	RECONCILIATION OF WATER REQUIREMENTS AND AVAILABILITY	
9.	SUMMARY OF FINDINGS	
10.	CONCLUSIONS	. 80
11.	RECOMMENDATIONS	
11.1	Springs	. 81
11.2	Areas or aspects that should be considered for further investigation	
12. 12.1	DESCRIPTION OF THE REGIONAL DEVELOPMENT OPTIONS	
12.1	12.1.1 Option 1: Zalu Dam, Xura River Rollcrete Dam (Fig 5 & 6 Appendix 2)	. 04 84
	12.1.2 Option 2: Zalu Dam, Xura River, Embankment Dam	
	12.1.3 Option 2A: Zalu Dam, Xura River, Rockfill Dam (Fig 9 & 10, Appendix 2)	
	12.1.4 Option 2B: Zalu Dam, Xura River, Earthfill Dam (Fig 12, 13 & 14, Appendix 2)	
12.2	Conjunctive Use of Surface and Groundwater Resources	. 85
	12.2.2 Imidiate Augmentation Measures: Lusikisiki Weir in conjunction with Groundwater (
	assurance of supply)	
13.	FACTORS AFFECTING DEVELOPMENT	. 87
13.1	GEOLOGY AND MATERIALS	. 87
	13.1.1 Zalu Dam Site	87
13.2	Environmental Impact Assessment of Zalu Dam Site	. 88
13.3	Social Impact Assessment	. 89
Table 3	33: Summary of Negative Social Impacts for Zalu dam site	. 90
13.4	Water Quality Issues	. 91
Table 3	34: Site sources of urban runoff and sewerage treatment works	. 91
13.5	Institutional Arrangements for O&M	
14.	RECONNAISSANCE SIZING AND COSTING	
14.1	General Sizing Criteria: Design Capacities and Flows	
	35: Design capacities and flow rates for sizing of infrastructure components	
14.2	Zalu Dam	
	36: Design and Extreme Floods for Sizing of Dam Spillways	
	37: Sizing Parameters for Dam	
14.3	Groundwater Development	
14.4	Primary Distribution System	
14.5	Summary of Capital Costs	
15.	38: Capital Cost Reconnaissance Phase March 2006	
15. 15.1	Topographical Surveys	
15.1	Geological and Materials Investigations	. 30
15.2	Stochastic Yield Analysis	
16.	PRE-FEASIBILITY CONCEPTUAL DESIGN AND COSTING	
16.1	Zalu Dam	
16.2	Primary Distribution System	
16.3	Summary of Capital Costs.	
	40: Capital Cost Pre-Feasibility Phase (R million)	100
17.	EVALUATION OF DEVELOPMENT OPTIONS	101
17.1	Economic Analysis Model	101
Table 4	41: O&M costs as a percentage of the capital costs	101
Table 4	42: Results of the Economic Analysis (for reconnaissance phase)	102
17.2	Evaluation of Development Options	102
	17.2.1 Surface Water Storage Scheme Zalu Dam Options	102
	17.2.2 Conjunctive run of river plus groundwater option	. 103

SRK Consulting xiv Final Report – May 2009

Report No P WMA 12/000/00/1507

17.3 Summary of Preferred Options	103	
Table 44: Summary of recommended schemes per source category		
18. CONCLUSIONS	104	
18.1 Development Options/Schemes	104	
18.2 Water Source	105	
18.3 Bulk Supply System	105	
19. RECOMMENDATIONS	106	
Appendices		
Appendix 1: Rainfall Data		
Appendix 2: Layouts and Typical Details	109	
Appendix 3: Surface Sampling Protocol	119	
Appendix 4: Certificate of Water Analysis		
Appendix 5: Cost Estimates	128	
Appendix 6: Economic Analysis	149	

SRK Consulting xv Final Report – May 2009