





# **BULK WATER SUPPLY** INFRASTRUCTURE **AUGMENTATION SCHEMES** IMPLEMENTATION

Crocodile West Reconciliation Strategy Steering Committee

25 July 2012

### **Presentation Contents**

- MW Guiding Principles (S3)
- Background to Bulk Infrastructure Backlogs (S4)
- New Bulk Water Supply Capital Expenditure Projects (S5)
- Alignment of MW's Response to the 12 Government Outcomes (S6-S9)
- Current Situation Vaalkop Area of Supply (\$10-\$15)
- Current Situation Roodeplaat Development Area (\$16 \$18)
- Current Situation Cullinan & Klipdrift Areas of Supply (619-524)
- MW Total Water Demand Projections (S25-S26)
- Raw Water Applicartions (S27)
- Major Capex Programme & Estimated Backlog Eradication (528-529)
- Joint Macro Planning & Prompt Conditions (S30-S31)
- Contribution to Community Development CSI Programme (S32)
- Way forward (S33)
- Klipvoor Scheme Implementation Task Team (S34)



### Magalies Water Guiding Principles

- Government committed all spheres to five priority areas;
  - Education, health, rural development and land reform, creating decent jobs and fighting crime
- Government's current key focus of work until 2014
  - Job creation
  - Infrastructure development
  - Infrastructure Operations and Maintenance
- CoGTA strategy and state of Local Government in South Africa
  - Backlogs
- Magalies Water as strategic partner will contribute significantly to national infrastructure expansion programmes as well as to strengthen O&M in terms of efficient service delivery and is geared to implement on Government's delivery agenda



### Background to Bulk Infrastructure Backlogs


#### All Development Areas:

- Unavailability of sufficient bulk water (& infrastructure) to supply in demand
  - Delayed / restricted development over past more than 10 years
- Limitations on macro area planning (IDP, SDF, WSDP, etc.)
- Limitations on Capital Funds (both MW & WSA's)
  - adversely effect bulk infrastructure development & implementation
- Increased capital funding requirements must be defined & sourced in time
- Development needs & -dynamics require SDF's & IDP's to be reviewed timeously
- SDF's, IDP's & WSDP's to be <u>updated</u> & availed to DWA & WB's on approval
- New development scenarios affects current demand projections (to be reviewed & included in infrastr. planning models & WSDP's)



#### New Bulk Water Supply Capital Expenditure Projects - Response to challenges

Magalies Water Magali



# Alignment of Magalies Water Response to the 12 Government Outcomes


MW aligned its Business strategy to the strategic outcomes of Government



#### **Outcomes and Deliverables**

#### **Outcome 6**

Infrastructure



#### **Magalies Water's deliverables**

Currently implementing a R1.3 billion Bulk
Water Supply Infrastructure Investment
(Pilanesberg Water Scheme) to augment and
address sustainability of bulk water supply
(support water for growth, development and
job creation)

#### Madibeng LM (DWA - RBIG Project):

- Emergency intervention in terms of water quantity and quality improvement
- Feasibility Study & Master Planning
- Conclude Implementation Ready Study/ies
- First 20 Ml Water Treatment Works Expansion
- Confirmation of further bulk infrastructure augmentation requirements

Kgetleng Rivier LM (O&M Support – 5 year contr)

+ Intervention on water & bulk sanitation (RBIG)



### Status Quo in the Bojanala District

Local	Total number of	Backlog -Water supply ((Number of Households)					
municipality	households	Below RDP	On RDP (200m)	Above RDP			
Madibeng LM	100165	17662	17007	65496			
Moretele LM	65196	22244	40151	2801			
Moses Kotane	02226	11000	40025	22702			
LM	83236	11828	48625	22783			
Kgetleng Rivier	40702	2042		7004			
LM	10703	2812	0	7891			
Rustenburg LM	103149	5781	9724	87644			
TOTAL	362449	60327	115507	186615			

Source: Bojanala Water & Sanitation Backlog study, 2008



### **Status Quo Continue:**

Local municipality	Total number	Backlog – Sanitation (Number of Households)				
	of households	Below RDP	RDP VIP Toilets	Above RDP		
Madibeng LM	100165	40428	9572	50000		
Moretele LM	65196	56815	7948	433		
Moses Kotane LM	83236	74237	3012	5987		
Kgetleng Rivier LM	10703	2037	0	8666		
Rustenburg LM	103149	52960	5630	44559		
TOTAL	362449	226477	26162	109645		

Source: Bojanala Water & Sanitation Backlog study, 2008

Similar Backlog Statuses exist in LM's within the Waterberg and other Districts





### **CURRENT SITUATION**




(Focus on Vaalkop System only)

- Magalies Water's started to implement the Pilanesberg Scheme from its Vaalkop WTW to supply bulk water for domestic and industrial use to urban, rural and industrial (mainly mining) consumers in Moses Kotane, Thabazimbi & Rustenburg LM's jointly with 4 new mines.
  - ♦ Section B of Pilanesberg North Scheme (R190 million) completed & operational
- Delayed implementation (global economic downturn & pending statutory approvals) resulted in <u>further growth in demand</u> for <u>industrial and domestic</u> use - to be supplied through an <u>increased</u> <u>Pilanesberg bulk Water supply Scheme</u> with <u>additional phases</u> of bulk infrastructure requirements, and further <u>benefit of scale</u> advantages.
- ♦ Increased Scheme capacity >120 Mℓ/d required for implementation.
- Magalies Water is now <u>proceeding</u> with implementation of upgrades at Vaalkop WTW - <u>Own Capital</u>
- Mines will proceed with implementation of further phases of bulk infrastructure requirements
- Magalies Water is sourcing balance of funding requirements on behalf of LM's (domestic component) - RBIG, Borrowings, etc.

#### **Current Situation**

#### Vaalkop Area of Supply:


- Vaalkop WTW capacity: 210 ML/d
- Current demand / consumption = supply capacity (in peak demand periods)
- Pilanesberg Bulk Water Scheme will add 60 MI/d (NOW >120 MI/d) treatment capacity and will increase distribution capacity with 70 MI/d (NOW 140 MI/d)
- Total scheme cost R1.3 billion (NOW R1.8 b)
  - (52% Industrial consumers & 48% Domestic component) (26% Industrial consumers & 74% Domestic component)
- Joint implementation / funding of Scheme by MW (for 3 LM's) and 4 mines
- One of the mines completed a new 30 km pipeline (750mm) and 35 Ml reservoir at Tuschenkomst to the value of R190M (balance of scheme implementation delayed mainly due to global economic down turn and funding & institutional arrangements)
- This scheme will support mining development as well as mining related domestic development and stabilise <u>and</u> support backlog domestic supply to the region (mainly rural)





#### **FUTURE PILANESBERG REGIONAL BULK WATER SUPPLY**







# Magalies Water Economies of Scale Benefits Magalies Water




	2007/8	2012			
Design Capacity	70 Me/day	100 M€/day	120 M€/day	150 M€/day	
Capital Cost	R1 309 Million (escalated)	R1 495 Million (estimated)	R1 630 Million (estimated)	R1 800 Million (estimated)	
Unit Capital Cost	R18-61/kℓ	R14-95/ke	R13-59/kℓ	R12-00/ke	
Current O&M Cost	R3-20/ke (excl. capital)	R3-20/k& (excl. capital)	R3-20/ke (excl. capital)	R3-20/ke (excl. capital)	

- MW as DWA's licensed bulk water service provider must implement WDM & conservation measures and regulating actions accordingly and is consistently encouraging all consumers to this effect
- Magalies Water will ensure most economic product to end consumer!

### **Demand Projections**

#### **Vaalkop Water Demand Projections**






### **Current Situation**

#### Roodeplaat Development Area:


- Wallmannstal WTW capacity: 12 ML/d
- Current demand / consumption > supply capacity
- Add 10 MI/d from CoT's Roodeplaat WTW to increase supply capacity to 22 MI/d
- Short to medium term demand > 85 Ml/d
- MW completed the completed first phases of bulk infrastructure upgrades
- Former Nokeng Tsa Taemane area now incorporated in City of Tshwane
- Magalies Water confirmed its position of Bulk Supplier with CoT
- Magalies Water will now continue with next phases of bulk infrastructure upgrades





### **Demand Projections**

#### **Wallmannsthal Water Demand Projections**



Note: Above projections not based on new SDF (CTMM) requirements!



### **Current Situation**

#### **Cullinan Area of Supply:**

- Cullinan WTW capacity: 16 MI/d
- Current demand / consumption < supply capacity</li>
- MW will upgrade the Rayton / Zonderwater pumpstation


#### Klipdrift Area of Supply:

- Klipdrift WTW capacity: 18 Ml/d
- Current demand / consumption > supply capacity
- MW currently upgrading Klipdrift to 36 Ml/d
- CoT requested MW to supply Moretele LM directly from Klipdrift WTW
- MW confirmed with Crocodile West Team and DWA that current supply to Moretele plus <u>augmentation</u> to Moretele, Bela Bela, Modimolle & Mookgophong should be combination of Klipdrift and new Klipvoor Scheme
- It was also confirmed that there would be no negative effect to previous supply scenarios as same demands were modelled from Temba & Klipdrift




### **Demand Projections**

#### **Cullinan Water Demand Projections**










### **Demand Projections**


#### **Klipdrift Water Demand Projections**





### Magalies Water Total Demand Projections

### Magalies Water Total Water Demand Projections



Note: These figures <u>excludes</u> the New Klipvoor Scheme <u>and</u> Bulk water supply to Marikana-Mooinooi area





# **Capacity Utilization**

Name	% Utilization	Design Capacity (MI/day)
Vaalkop	90	210
Klipdrift	>122	18
Wallmannsthal	100	12
• Cullinan	82	14





### Raw Water Applications



#### Additional raw water licenses applied for with DWA:

Plant	Current Capacity (Current License)	License applied for	Total Capacity (if approved)
Vaalkop	210 MI/d	70 MI/d	270 MI/d
	(180 MI/d)	APPROVED	APPROVED
Wallmannsthal	12 MI/d + 10 MI/d	> 30 Ml/d	> 42 Ml/d
	(12 MI/d)		+ 10 Ml/d
Klipdrift	18 MI/d	16 MI/d	36 MI/d
	(20 MI/d)		
Cullinan	16 MI/d	7.7 MI/d	22.4 MI/d
	(14.7 MI/d)		
New	NEW	45 MI/d	45 MI/d
Klipvoor Scheme			

WSDP's, IDP's & SDF's only recently obtained from WSA's.

Detailed application reports are currently prepared & to be submitted to DWA upon completion

#### **MAJOR CAPEX PROGRAM**



Department / Plant	Description	GRAND TOTAL	GRAND TOTAL FUNDING SOURCE				Expexted Starting		
			MINES	DPW	MW Funds	Financing & Borrowings	Grant Funding (RBIG)	Date	Completion Date
HEAD OFFICE	Strategic Asset Assessment and Planning	-			-				
	Capital Project Implementation Programme	17 502 000			17 502 000			July 2012	Ongoing
/AALKOP	Pipeline refurb section and repair.	2 314 000			2 314 000			January 2013	July 2014
	Upgrade Kortbegrip/Bethanie Pipeline	28 050 000				28 050 000		June 2013	July 2016
	Air Valve Replacement & Chamber Sheltering	1 010 000			1 010 000			January 2013	June 2014
	Pilansberg Northern System:	982 460 000	336 360 000	-	114 100 000	532 000 000	?	July 2012	July 2015
	- Bulk Power Supply Upgrade from Eskom	131 000 000			10 000 000	121 000 000		October 2012	December 2015
	Power Supply for Increased Capacity at Pump St.	14 000 000			14 000 000			January 2013	July 2014
	- Existing Infrastructure Capacity Improvement	1 100 000			1 100 000			February 2013	January 2014
	Increased Capacity at WTW (30 Mt/d Plant 3 ext)	58 000 000	34 000 000		24 000 000			July 2012	December 2013
	Increased Capacity at WTW (30 Mt/d Plant 4 new)	139 000 000				139 000 000		July 2012	October 2015
	Increased Capacity at Pumpstation	80 000 000			65 000 000	15 000 000		July 2012	Dec2013 & Jul'15
	Rising Main from Vaalkop to Evergreen	85 000 000				85 000 000		September 2012	December 2013
	Rising Main from Evergreen to La Patrie	110 000 000				110 000 000		September 2012	April 2014
	Reservoir at La Patrie	30 000 000				30 000 000		October 2012	June 2014
	Gravity Main from La Patrie to Padda	122 000 000	122 000 000					September 2012	April 2014
	Project Management & Professional Fees	149 000 000	149 000 000					July 2012	June 2015
	- Acquisition of Servitudes	18 360 000	18 360 000					2013/2014	June 2015
	Gravity Main from Padda to Tuschenkomst	Completed	Completed					Completed	Commissioned
	- 35 Mt Terminal Reservoir at Tuschenkomst	Completed	Completed					Completed	Commissioned
	- Supply Lines from Reservoir To Metering Points	13 000 000	13 000 000					2013/2014	June 2014
	Incremental Capacity Increase of New Pipelines	32 000 000				32 000 000		September 2012	June 2014
	Pilansberg Southern System:	541 840 000	210 840 000	-	0	331 000 000	?	July 2012	July 2015
	- Existing Pipeline Capacity Improvement	1 590 000	1 590 000					February 2013	June 2014
	- Gravity Main from Evergreen to Sun City Station	296 000 000				296 000 000		2013/2014	July 2015
	- Gravity Main from Sun City Station to Mafenya	141 000 000	141 000 000					July 2012	December 2013
	Reservoir at Mafenya	70 000 000	35 000 000			35 000 000		July 2012	October 2015
	- Acquisition of Servitudes	9 000 000	9 000 000					2013/2014	June 2015
	Incremental Capacity Increase of New Pipelines	24 250 000	24 250 000					2013/2014	June 2015
WALLMANNSTHAL	Wallmannsthal System Upgrade	36 350 050				36 350 050		June 2013	May 2015
	25ML Reservoir	37 500 050			37 500 050			November 2012	April 2015
	Baviaanspoort Pumping System:								
	- Wallmannsthal-Baviaanspoort P/S & Rising Main	27 130 051			27 130 051			November 2012	August 2014
	- Existing Pipeline Capacity Improvement	920 000			920 000			January 2013	June 2013
	Zeekoegat Pipeline Upgrade (SAPS-Dog School)	15 320 000		15 320 000				July 2012	April 2014
	Office Building Upgrade	3 000 000				3 000 000		2014/2015	June 2015
KLIPDRIFT	Klipdrift Upgrade	12 000 000			12 000 000			August 2012	June 2014
	10ML Reservoir	14 650 000			14 650 000			August 2012	May 2014
	Steve Bikoville Pumping System (To Reservoir)	12 550 000			12 550 000			August 2012	February 2014
	Extenstion of plant	41 450 050			41 450 050			August 2012	April 2015
	Pipeline Capacity Improvement	990 000			990 000			October 2012	May 2013
CULLINAN	Upgrading of Zonderwater Pumpstation	1 685 000			1 685 000			October 2012	June 2013
	Pipeline Capacity Improvement	600 000			600 000			October 2012	April 2013
AND TOTAL		1 777 321 201	547 200 000	15 320 000	284 401 151	930 400 050	?		
	Magalies Water Funds	021201	J.: 200 000		284 401 151				
	Public Works Funds			15 320 000					
	Mala a Francia		F 47 000 000	13 320 000					

Required Financing / Borrowings

# **Estimated Backlog Eradication**

			Estimated Backlog Eradication  Demand [M&/d]			
		New / Existing				
DEPARTMENT/PLANT	Description	CAPACITY	Additional	Backlog	% Backlog	
VAALKOP	Pipeline refurb section and repair.	Sustain Existing				
	Upgrade Kortbegrip/Bethanie Pipeline	New Capacity	?		>80%	
	Air Valve Replacement & Chamber Sheltering	Sustain Existing				
	Infrastructure Condition & Capacity Assessment	Sustain Existing				
	La Patrie Reservoir	New Capacity	00 0 D	00 D	000/ Damastia	
	Pilansberg Northern Scheme	New Capacity	33.8 Domestic 36.2 Industrial	>20 Domestic 36.2 Industrial > 56 Total	>60% Domestic	
	Pilansberg Southern Scheme	New Capacity	70 total		80% Total Bulk	
	Incremental increase in Capacity of Pipelines	Future Additional				
WALLMANNSTHAL	Wallmannsthal System Upgrade	New Capacity		<10 Domestic	<30% Domestic	
	25ML Reservoir	New Capacity	>30 Domestic	>50 Total Bulk	>200% Total Bulk	
	Baviaanspoort Pumping System	New Capacity		700 Total Baix	220070 Total Ball	
	Zeekoegat Pipeline Upgrade (SAPS-Dog School	New Capacity	2	New facility	small	
	Office Building Upgrade					
	Infrastructure Condition & Capacity Assessment	Sustain Existing				
KLIPDRIFT	Klipdrift Upgrade	New Capacity				
	10ML Reservoir	New Capacity	0 D	>12 Domestic 6 Sustainablty	0000/	
	Steve Bikoville Reservoir	New Capacity	6 Domestic		200%	
	Extension of Plant	New Capacity				
	Infrastructure Condition & Capacity Assessment	Sustain Existing				
	L				<b>500</b> /	
CULLINAN	Upgrading of Zonderwater Pumpstation	New Capacity	2	1	50%	



### Joint Macro Planning

- Development dynamics urged & resulted in joint macro planning & strategic coordination with WSA's, DM's & DWA
- New demand projections & infrastructure development requirements must be reflected in the respective WSDP's
  - MW currently coordinates these requirements with Thabazimbi LM Moses Kotane LM, Rustenburg LM and RBA, Modimolle & Bela Bela and Moretele LM's
  - MW also negotiates funding approvals and grants (RBIG) with DWA & National Treasury (domestic & social components of the schemes)
- More focused water resources planning required
  - especially for the Roodeplaat & Klipdrift areas
  - MW currently coordinates with DWA Regional & National (limited local resources should be optimally resourced before more costly raw water augmentation schemes are considered)
- Optimal utilisation of existing bulk infrastructure is essential before new infrastructure is implemented

### **Prompt Conditions**

- Prompt license approval is crucial, in order to supply in the growing demand of the area
- Capital funding requirements to be resourced timeously to implement supporting infrastructure in time
- Water Boards should apply for Grant Funding (e.g. RBIG) on behalf of WSA's to implement bulk water infrastructure projects

#### (DWA's current approach)

- EIA processes should be accelerated and not allowed to unnecessarily delay infrastructure project implementation
- Joint macro planning between MW & WSA's must continue
- Magalies Water will continue to partake in DWA's water resources planning and water resource management activities



# Contribution to Community Development Corporate Social Investment

- Magalies Water is proud of the fact that it has been a responsible corporate citizen in the District for more than 40 years. Since 1969, Magalies Water's corporate head office, operational divisions and employees have steadily committed their innovative spirit, resources and time to charitable causes and community efforts.
- Magalies Water is dedicated to being even more responsive to community needs, primarily in areas where it has facilities, by fostering partnerships with social and community based institutions, funding special programmes, and encouraging further employee involvement in these cases



### **Way Forward**

- MW ready to support on Water Conservation and Demand Management interventions
- MW will confirm optimum bulk water infrastructure requirements to ensure most economical bulk water supply to all
- DWA, Bojanala, <u>Waterberg</u> and WSA's to support MW in pursuit of the optimum regional bulk water supply initiatives:
  - Pilanesberg Water Scheme
  - New Klipvoor Bulk Water Supply Scheme
    - Implementation Task Team to be established
- MW will continue with Regional Macro-Planning on key projects and water services provision
- All to forge ahead on backlog eradication (bulk and retail)
- Joint Services coordination and cooperation on water and sanitation provision in the area of operation



# Klipvoor Bulk Water Supply Scheme Implementation Task Team

- Proposed Task Team:
  - Magalies Water
  - DWA North West
  - DWA Limpopo
  - DWA Planning
  - Waterberg DM
  - Bojanala DM
  - Relevant LM's

