



**water affairs**

Department:  
Water Affairs  
REPUBLIC OF SOUTH AFRICA



REPORT NO: P WMA 11/U10/00/3312/3/1/2

# The uMkhomazi Water Project Phase 1: Module 1: Technical Feasibility Study: Raw Water


**ENGINEERING FEASIBILITY DESIGN REPORT**

**SUPPORTING DOCUMENT 2:**

**DAM POSITION REPORT**

**FINAL**

**FEBRUARY 2014**



The uMkomazi Water Project Phase 1: Module 1: Technical Feasibility Study Raw Water

---

**Project name:** *The uMkhomazi Water Project Phase 1: Module 1: Technical Feasibility Study Raw Water*

**Report Title:** *Engineering Feasibility Design Report*

**Sub-report title:** *Supporting Document 2: Dam Position Report*

**Compiled by:** *D van der Merwe D B Badenhorst*

**PSP project reference no.:** *J01763*

**DWA Report no.:** *P WMA 11/U10/00/3312/3/1/2*

**Status of report:** *Final*


**First issue:** *2012/07/18*


**Final issue:** *2014/02/12*

---

**CONSULTANTS:** *AECOM (BKS\*) in association with AGES, MM&A and Urban-Econ.*

**Approved for Consultants:**


  
-----  
**Dvd Merwe**  
Sub-Task Leader


  
-----  
**DB Badenhorst**  
Task Leader

---

**DEPARTMENT OF WATER AFFAIRS (DWA): Directorate: Options Analysis**

**Approved for DWA:**

  
-----  
**K Bester**  
Chief Engineer: Options Analysis (East)

  
-----  
**LS Mabuda**  
Chief Director: Integrated Water Resource Planning

---

\* BKS (Pty) Ltd was acquired by AECOM Technology Corporation on 1 November 2012

Prepared by:

**AECOM**  
AECOM (Pty) Ltd  
PO Box 3173  
Pretoria  
0001

In association with:

**Africa Geo-Environmental Services**

**Mogoba Maphuthi and Associates**

**Urban-Econ**




## PREAMBLE

---

In June 2014, two years after the commencement of the uMkhomazi Water Project Phase 1 Feasibility Study, a new Department of Water and Sanitation was formed by Cabinet, including the formerly known Department of Water Affairs.

In order to maintain consistent reporting, all reports emanating from Module 1 of the study will be published under the Department of Water Affairs name.

## The uMkhomazi Water Project Phase 1 LIST OF REPORTS



# TABLE OF CONTENTS

	<b>Page</b>
<b>1 INTRODUCTION .....</b>	<b>1-1</b>
<b>2 DAM SITE OPTIONS.....</b>	<b>2-1</b>
2.1 SMITHFIELD DAM.....	2-1
2.2 BALANCING DAM .....	2-1
<b>3 SIZING OF DAMS.....</b>	<b>3-1</b>
3.1 SMITHFIELD DAM.....	3-1
3.2 BALANCING DAM .....	3-1
<b>4 FLOOD AND FLOOD ATTENUATION .....</b>	<b>4-1</b>
4.1 SMITHFIELD DAM.....	4-1
4.2 BALANCING DAM .....	4-3
<b>5 SPILLWAY AND CHUTE SIZES.....</b>	<b>5-1</b>
5.1 SMITHFIELD .....	5-1
5.2 NEW BAYNESFIELD BALANCING DAM.....	5-1
<b>6 RIVER DIVERSION AND PERMANENT OUTLETS.....</b>	<b>6-1</b>
6.1 SMITHFIELD DAM.....	6-1
6.2 NEW BAYNESFIELD BALANCING DAM .....	6-1
<b>7 DAM CONFIGURATION ARRANGEMENTS OPTIONS .....</b>	<b>7-1</b>
7.1 SMITHFIELD DAM.....	7-1
7.2 BALANCING DAM .....	7-3
<b>8 DAM CROSS SECTION LAYOUTS.....</b>	<b>8-1</b>
8.1 SMITHFIELD DAM.....	8-1
8.2 BALANCING DAM .....	8-1
<b>9 FOUNDATION CONSIDERATIONS .....</b>	<b>9-1</b>
9.1 SMITHFIELD DAM SITE B .....	9-1

---

9.2	SMITHFIELD DAM SITE A .....	9-1
9.3	SMITHFIELD DAM SITE C .....	9-1
9.4	NEW BAYNESFIELD BALANCING DAM SITE .....	9-2
<b>10</b>	<b>COST ESTIMATION .....</b>	<b>10-1</b>
10.1	SMITHFIELD DAM.....	10-1
10.2	BALANCING DAM .....	10-2
<b>11</b>	<b>CONCLUSIONS.....</b>	<b>11-1</b>
11.1	COMPARISON OF DAMS.....	11-1
<b>12</b>	<b>RECOMMENDATION FOR MATERIALS BORROW AREAS AND QUARRIES FOR AND LAYOUT OF PREFERRED DAMS.....</b>	<b>12-1</b>
<b>13</b>	<b>REFERENCES .....</b>	<b>13-1</b>

# LIST OF FIGURES

	<b>Page</b>
Figure 2.1: Smithfield Dam: Location of Alternative Sites .....	2-3
Figure 2.2: Location of Option 1, Balancing Dams .....	2-4
Figure 2.3: Location of Option 2, Balancing.....	2-5
Figure 2.4: Longitudinal section through conveyance system.....	2-6
Figure 7.1: Smithfield Dam Site A, Option 1 .....	7-4
Figure 7.2: Smithfield Dam Site A, Option 2 - Dam Layout.....	7-5
Figure 7.3: Smithfield Dam Site B, Option 1- Dam .....	7-6
Figure 7.4: Smithfield Dam Site B, Option 2 .....	7-7
Figure 7.5: Smithfield Dam Site B, Option 3 .....	7-8
Figure 7.6: Smithfield Dam Site C, Option 1 .....	7-9
Figure 7.7: Smithfield Dam Site C, Option 2.....	7-10
Figure 7.8: New Baynesfield Balancing Dam, Option 2 .....	7-11
Figure 7.9: Intake tower through RCC structure .....	7-12
Figure 7.10: Intake tower for tunnel option.....	7-13
Figure 7.11: Intake tower for pump option .....	7-14
Figure 8.1: Typical cross sections of embankments .....	8-2

# LIST OF TABLES

	<b>Page</b>
Table 1.1: Tasks of the Engineering Investigation Task .....	1-1
Table 3.1: Full supply levels for 137 million m <sup>3</sup> storage volume .....	3-1
Table 3.2: Storage volumes per Balancing Dam .....	3-2
Table 4.1: Pre-feasibility and feasibility flood peaks .....	4-1
Table 4.2: Spillway Discharges .....	4-2
Table 4.3: Peak flood (m <sup>3</sup> /s).....	4-3
Table 4.4: Recommended flood peaks (m <sup>3</sup> /s).....	4-4
Table 4.5: Flood attenuation results .....	4-4
Table 5.1: Unit discharges for chute spillways.....	5-1
Table 5.2: Selected chute widths .....	5-1
Table 7.1: Dam Site and Type options .....	7-1
Table 7.2: Dam options and special arrangements .....	7-2
Table 9.1: Depths (m) of excavation for Site B .....	9-1
Table 9.2: Depths (m) of excavation for Site A .....	9-1
Table 9.3: Depths (m) of excavation for Site C .....	9-2
Table 10.1: Summary of Comparable Cost Estimates of the Dams .....	10-1
Table 10.2: Summary of new Balancing Dam Options.....	10-2



# APPENDICES

- APPENDIX A: PHOTOGRAPHS OF SMITHFIELD DAM**
- APPENDIX B: BALANCING DAM: PHOTOGRAPHS OF SITES**
- APPENDIX C: SMITHFIELD DAM-STAGE/AREA, VOLUME CURVES**
- APPENDIX D: BALANCING DAMS- STAGE/AREA, VOLUME CURVES**
- APPENDIX E: CATCHMENT AND LONGEST WATERCOURSE, OPTION 2 NEW BAYNESFIELD DAM**
- APPENDIX F: SMITHFIELD DAM SITE, FLOOD ATTENUATION**
- APPENDIX G: NEW BAYNESFIELD DAM, FLOOD ATTENUATION**
- APPENDIX H: SMITHFIELD DAM SITE A, OPTION 1 BOQ**
- APPENDIX I: SMITHFIELD DAM SITE A, OPTION 2 BOQ**
- APPENDIX J: SMITHFIELD DAM SITE B, OPTION 1 BOQ**
- APPENDIX K: SMITHFIELD DAM SITE B, OPTION 2, BOQ**
- APPENDIX L: SMITHFIELD DAM SITE B, OPTION 3, BOQ**
- APPENDIX M: SMITHFIELD DAM SITE C, OPTION 1, BOQ**
- APPENDIX N: SMITHFIELD DAM SITE C, OPTION 2, BOQ**
- APPENDIX O: BAYNESFIELD BALANCING DAM, OPTION 2, BOQ**

## LIST OF ABBREVIATIONS

BOR	Bottom of River
TOR	Terms of Reference
MAR	Mean annual runoff
MOL	Minimum operating level
FSL	Full supply level
DWA	Department of Water Affairs
ECRD	Earth Care Rockfill Dam
EED	Earthfill Embankment Dam
RCCG	Roller Compacted Concrete Gravity Dam

## LIST OF UNITS

Mm <sup>3</sup>	Million cubic metres
Mm <sup>3</sup> /a	Million cubic metres per annum
m <sup>3</sup> /s	Cubic metres per second
Mℓ/d	Mega litres per day
masl	Metres above sea level
T <sub>c</sub>	Time of Concentration

# 1 INTRODUCTION

This report forms part of the feasibility study on the Water Project Phase 1: Module 1: Technical Feasibility Study Raw Water. More specifically it covers the *Dam Position Task 5.2* as part of the *Engineering Investigations Task 5*. The Engineering Investigation main task consists of the following tasks shown in **Table 1.1**.

**Table 1.1: Tasks of the Engineering Investigation Task**

Task number	Task description
5.1	Optimization of Conveyance System
5.2	Dam Position
5.3	Materials Investigation
5.4	Geomorphologic and Seismic Investigation
5.5	Geotechnical Investigation
5.6	Survey
5.7	Dam Type Selection
5.8	Establish required Capacity of Dam
5.9	Flood and Backwater calculations for the Final Dam
5.10	Climatological Data for the Construction Site
5.11	Water Quality and Limnological Review
5.12	Sediment Yield
5.13	Land requirements and associated costs
5.14	Optimize Scheme Configuration
5.15	Assessment of the Potential for Hydropower
5.16	Feasibility Design of the Selected Scheme
5.17	Creating a Cost Model for the Project

The purpose of this report is, in conjunction with *Task 5.1: Optimization of the conveyance system*, to:

- ◆ Consider alternative dam sites for the Smithfield Dam;
- ◆ Finally determine the Smithfield Dam site matching the recommended conveyance layout; and to
- ◆ Identify the position of the balancing dam site downstream of the conveyance structure.

The pre-feasibility study concluded that the dam located at Site B, see **Figure 2.1**, in the uMkhomazi River and pumping from the Smithfield Dam reservoir at position of Site A, **Figure 2.1**, to the intake of a free-flow tunnel was the preferred transfer option.

This option was included in the comparison of options as described in the report of *Task 5.1*.

A layout of the proposed conveyance scheme is included in this report, see **Figure 2.4**.

This report will be attached in an Appendix to the Feasibility Study Report.

## 2 DAM SITE OPTIONS

---

### 2.1 SMITHFIELD DAM

The identified possible Smithfield Dam sites are indicated on **Figure 2.1** and are from upstream to downstream in the river the following:

- ◆ Site A, a site selected, during this feasibility study, upstream of the entrance to the conveyance structure which was selected during the pre-feasibility study. This position will enable releases to the conveyance structure from the outlet structure of the dam;
- ◆ Site B, the pre-feasibility study site, which has a saddle dam on the left side close to the main dam;
- ◆ Site C, a site downstream of the pre-feasibility site (Site B) identified during the pre-feasibility study. This site has an area on the left bank which can be used for a spillway and was not evaluated in detail during the feasibility study.

Photographs of the sites are shown in **Appendix A**.

### 2.2 BALANCING DAM

#### 2.2.1 Dams required for balancing

The transfer scheme is positioned to transfer water in gravitation from the Site A position towards Umlaas Road via a water treatment plant – that is without a second pumpstation on route. This layout has the lowest present value cost and is recommended for implementation in the report *Task 5.1: Optimisation of Conveyance system report* and is shown in **Figure 2.4**. The lowest draw down level for balancing dams is level 872 masl - the full supply level of the existing Baynesfield Dam. The full supply level for the balancing is 897,2m – refer to *Task 5.1 Optimization of Conveyance System report*.

Operational requirements for inspection and maintenance of long transfer tunnels, like the Lesotho Highlands Transfer scheme, include the provision of balancing dams on the downstream side. These dams store water for the supply during down time periods required for inspection and maintenance periods of the tunnels, also if they

are concrete lined. The proposed uMkhomazi scheme allows for the transfer of water through a 32km long tunnel under gravity into the Umgeni Water's '57 pipeline which supplies eThekweni Municipality Western Aqueduct. It is therefore necessary that storage is provided for three weeks average supply associated with the yield of the scheme. The required balancing storage volumes for the two phases are as follows:

- ◆ Phase 1: Smithfield Dam: 7,2 million m<sup>3</sup>;
- ◆ Phase 2: Smithfield and Impendle Dam: 14.4 million m<sup>3</sup>.

Two layout options for the Balancing Dams were investigated in more detail:

- ◆ Option 1, a new Baynesfield Balancing Dam with storage volume 14,4 million m<sup>3</sup>, about 1 km downstream of the existing Baynesfield Dam, of which the reservoir is located to miss the electricity power lines on the left bank and a new Mbangweni Balancing Dam with storage capacity 7,2 million m<sup>3</sup>, about 1km downstream of the existing Mbangweni Dam. This existing dam will also be inundated by the new dam.
- ◆ Option 2, one Baynesfield Balancing Dam with storage volume 21,6 million m<sup>3</sup> located about 2 km downstream of the existing Baynesfield Dam.

Photographs of the existing Baynesfield Dam are included in **Appendix B**. This dam cannot be raised due to the spillway concrete A frame situated on soil and associated settlement problems.

Photographs of the Mbangweni Dam are included in **Appendix B**.

Comparison of the valleys and required dam embankments indicated that Option 2, with the one balancing dam at Baynesfield Dam, has the lowest embankment volumes by far. Option 2 was therefore considered in detail in this report. Option 1 can be considered in further optimization exercises when necessary.

The layout of the two options of balancing dams is shown on **Figure 2.2** and **Figure 2.3**.

Depending on the acceptance of the recommendations made in the report of *Task 5.1* the balancing volume requirement could change. If the twin tunnel option is accepted a balancing storage of only 13,4 million m<sup>3</sup> (7,4 m<sup>3</sup>/s) will be required, based on the ultimate yield of the scheme. However, as an initial process a required balancing volume of 21,6 million m<sup>3</sup> was used to position the balancing dam.




Figure 2.1: Smithfield Dam: Location of Alternative Sites




Figure 2.2: Location of Option 1, Balancing Dams






Figure 2.3: Location of Option 2, Balancing Dams




Figure 2.4: Longitudinal section through conveyance system

## 3 SIZING OF DAMS

### 3.1 SMITHFIELD DAM

The pre-feasibility study full supply storage volume of 137 million m<sup>3</sup> was taken as norm for sizing the reservoirs of all options. It was assumed that this capacity would result in the same yield from the dams. This assumption should be re-considered during detail yield analyses. The storage volumes characteristics of the new sites have been determined from the detail contour surveys obtained from DWA for sites A and B. For site C, 1:50 000 topographical maps were used.

The full supply levels for the dams are indicated in **Table 3.1**:

**Table 3.1: Full supply levels for 137 million m<sup>3</sup> storage volume**

Smithfield Dam Option	FSL (masl)
Site A	921
Site B	915
Site C	909

The pre-feasibility study indicates that for a capacity of 137 million m<sup>3</sup> the full supply level is at 915 masl. A re-calculated curve for Site B Smithfield Dam is included in **Appendix C**. From this curve it can be concluded that the capacity of 137 million m<sup>3</sup> at a level of 915 masl is accurate.

### 3.2 BALANCING DAM

Stage / storage volume curves for the two considered options are included in **Appendix D**. The required storage volumes between the levels 879,2 and 872 masl for the two options can be obtained as shown in **Table 3.2**:

**Table 3.2: Storage volumes per Balancing Dam**

<b>Balancing Dam Option</b>	<b>Storage Volume above 872 masl (Million m<sup>3</sup>)</b>
New Baynesfield Balancing Dam and new Mbangweni Balancing Dam – Option 1	11+10,6
New Baynesfield Balancing Dam – Option 2	21,6

## 4 FLOOD AND FLOOD ATTENUATION

### 4.1 SMITHFIELD DAM

#### 4.1.1 Philosophy

In accordance with SANCOLD's *Guidelines on Safety in Relation to Floods*, the spillway at Smithfield Dam (Category III dam – large size and high hazard rating) should be capable of discharging a recommended design flood (RDF) equal to the 200-year flood with adequate “dry” freeboard and without any damage to the dam. It is furthermore required that the spillway and the dam must be able to discharge and accommodate the safety evaluation flood (SEF) with zero “dry” freeboard and accepting damage to the dam, but not with a catastrophic failure. The SEF is determined as the regional maximum flood (RMF) for the adjacent region with a numerically one step higher factor ( $RMF_{+\Delta}$ ).

The flood peaks recommended by the DWA Directorate Hydrological Service as included in the Pre-feasibility study report are shown and compared with the Feasibility (this study) determined flood peaks in **Table 4.1**:

**Table 4.1: Pre-feasibility and feasibility flood peaks**

Flood peak description	Pre-feasibility Flood Peaks (m <sup>3</sup> /s)	Feasibility Flood Peaks (m <sup>3</sup> /s)
100 year	1 750	1 750
200 year	2 540	2 540
RMF	4 500 (k=5)	5 200 (k=5.2)
RMF <sub>+\Delta</sub>	5 200 (k=5,2)	6 960 (k = 5,4)

The safety evaluation flood peak for this dam is taken as 6 960 m<sup>3</sup>/s.

#### 4.1.2 Spillway Discharge

Various spillway discharges associated with various spillway widths for ogee weir spillways were considered. Discharges for 130m wide and 160m wide spillway widths are shown in **Table 4.2**:

**Table 4.2: Spillway Discharges**

Stage (masl)	Flood (m <sup>3</sup> /s)	
	130m wide spillway	160m wide Spillway
915 (FSL)	0	0
916	278	342
917	787	968
918	1 446	1 779
919	2 226	2 739
920	3 110	3 828
921	4089	5132
922	5152	6341
923	6295	7748

Discharges from these two spillway widths were used to assess flood attenuation.

#### 4.1.3 Flood hydrograph

The SEF hydrograph was derived from the 1:200 year hydrograph proposed by the DWA as shown in report by Ninham Shand. The hydrograph with a peak of 6 960 m<sup>3</sup>/s is shown on the figure included in **Appendix F**.

#### 4.1.4 Stage area storage volume

The stage storage volume relationship is shown on the figure included in **Appendix C**. This graph was determined from the 1 m contour interval surveys done by the DWA.

#### 4.1.5 Flood attenuation results

Flood attenuation calculations have been determined using the Flood 2 computer programme and the results are shown in the figure included in **Appendix F**.

From the table it is clear that the attenuation is insignificant – in the order of 3%.

It has therefore been assumed for all dam site positions that:

- ◆ Flood attenuation for the safety evaluation flood is insignificant for all the dam positions;
- ◆ That the spillway crest must be 160 m wide; and that
- ◆ A calculated freeboard of 8 m is allowed.

## 4.2 BALANCING DAM

### 4.2.1 Philosophy

The existing Baynesfield Dam is classified as a Category II dam and has a storage volume of 1,8 million m<sup>3</sup>. The proposed new Baynesfield Balancing dam wall will be 44 m high and therefore classify as a large dam. As the dam wall is more than 30 m high and the potential loss of life is more than 10 people the hazard potential is high and thus the proposed dam will be classified as a Category III dam. The design was based on this category.

### 4.2.2 Flood hydrology

The catchment area of the new Baynesfield Balancing Dam (103 km<sup>2</sup>) is attached as **Appendix E** and the time of concentration determined with the longest flow path and 10-85% slope is 2,8 h.

It is required that for a Category III Dam the recommended design flood be the 1:200 year and the SEF should be the RMF<sub>+Δ</sub>. The 1:20 year flood is required to be accommodated for river diversion purposes for rockfill embankments. These floods were determined with the methods and results indicated in **Table 4.3**.

**Table 4.3: Peak flood (m<sup>3</sup>/s)**

Method	Recurring Interval/method				
	1:20	1:50	1:100	1:200	RMF+delta
Rational	529	707	890		
Alternative	685	906	1099	1244	
Unit Hydrograph	284	412	546		
SDF	366	554	713	883	
Empirical	247	342	432	841	
TR137		513	666	841	1769

In relation to the values in **Table 4.3**, the recommended flood peaks are indicated in **Table 4.4**.

**Table 4.4: Recommended flood peaks (m<sup>3</sup>/s)**

Flood peaks for recurring interval/method		
1:20	1:200 (RDF)	SEF
422	999	1769

#### 4.2.3 Flood Hydrograph

With the calculated time of concentration ( $T_c$ ), a triangular flood hydrograph was utilised to simulate the inflow flood to the new Baynesfield Balancing Dam. The total storm duration was approximated as  $3 \times T_c$ .

#### 4.2.4 Flood attenuation

The stage-area-capacity curve was determined from 1:50 000 topographical maps (20 m intervals) and is attached in **Appendix D**. With the Muskingum routing method the flood attenuation was determined for the RDF and SEF peak floods. The results of the calculations are indicated in **Table 4.5** and attached as **Appendix G**:

**Table 4.5: Flood attenuation results**

	Peak Flood (m <sup>3</sup> /s)	Routed flow discharge (m <sup>3</sup> /s)	Raising of water level (m)
RDF	999	587	2,79
SEF	1 769	1 146	4,19

#### 4.2.5 Freeboard

Freeboard was determined according to the Interim Guidelines on Freeboards for Dams (1990). The following assumptions were made in order to calculate the freeboard:

- ◆ Design wind direction perpendicular to the dam wall;
- ◆ Upstream embankment slope as 1:1,75;
- ◆ Rockfill embankment;
- ◆ Surges and seiches as 0,5 m.

The combination of RDF, the 25 year event, wind setup and flood surges and seiches had the highest freeboard requirement of 4,4 m.



#### 4.2.6 Embankment Level

The attenuated SEF level provides for a 4,2 m freeboard. The freeboard calculated from the methodology described previously provides a larger freeboard requirement as the SEF level. The freeboard of 4,4 m is therefore adopted. This freeboard added to the FSL of 879,2 masl gives 883,6 masl. The NOC (non-overspill crest) of the embankment should be placed at 883,6 masl. As the river bed level is at 840 masl the embankment height equals 43,6 m. With a 1 % settlement allowance the Non Overspill Crest (NOC) calculates to a level of 884 masl.

## 5 SPILLWAY AND CHUTE SIZES

### 5.1 SMITHFIELD

Research indicate that for effective energy absorption the unit discharges for the chutes sized from an ogee weir or side channel spillway should conform to the unit discharges indicated in **Table 5.1**.

**Table 5.1: Unit discharges for chute spillways**

Type of chute	Maximum unit discharge selected (m <sup>3</sup> /s/m)
Stepped spillway (RCC gravity structure)*	40
Chute Spillway	100

\*The stepped spillway methodology has been developed for the de Hoop Dam with the aid of small triangular blocks.

For large spillways with air entrainment the higher value is used as a maximum. Chute sizes have therefore been sized as shown in **Table 5.2**.

**Table 5.2: Selected chute widths**

Type of chute	Chute width (m)
Stepped spillway for gravity structures	160
Chute Spillway	68

The invert levels of the side channel spillways were calculated with the method as described in the *Design of Small Dams* and with the selected chute width as indicated in **Table 5.2** the wall heights of the chutes were determined for the SEF.

### 5.2 NEW BAYNESFIELD BALANCING DAM

A spillway length of 60 m and a chute width of 20 m were adopted within the limits of 40 and 100 m<sup>3</sup>/s/m. The required chute wall heights were calculated with the Bernoulli equation for the SEF flood.

## 6 RIVER DIVERSION AND PERMANENT OUTLETS

---

### 6.1 SMITHFIELD DAM

The river diversion flood sizes were selected as follows:

- ◆ For embankment dams, the 1:20 year flood which is 1 310 m<sup>3</sup>/s as shown in the hydro report included in Ninham Shand (1999). No flood attenuation was taken into consideration.
- ◆ For concrete gravity dams, the 1:10 year flood which is 1000 m<sup>3</sup>/s.

To accommodate these floods 5 x 6m diameter tunnels with capacity 262 m<sup>3</sup>/s each with 16m high cofferdams were selected for embankment dams and a diversion method through slots or culverts for the concrete gravity dam structures.

The permanent, Environmental Water Requirement (EWR) outlets for the two types of dams considered in this study were assumed as follows:

- ◆ Embankment dams: Two 2m diameter pipes in one tunnel originating from a multiple draw off intake structure on the upstream side of the tunnel – and access from the one tunnel.
- ◆ RCC gravity dams: Similar to the layout of Spring Grove Dam but upgraded to suit the higher head.

### 6.2 NEW BAYNESFIELD BALANCING DAM

The 1:20 year peak flood was calculated as 422 m<sup>3</sup>/s as indicated in **Table 4.4**. In order to accommodate this flood 2 x 6m diameter tunnels with a 12 m high cofferdam were selected.

For the irrigation requirement and the EWR, 2 x 1m diameter pipes constructed in one of the diversion tunnels were estimated. The cost of a 6m x 6m intake tower with multiple draw off upstream of the tunnel was considered.

# 7 DAM CONFIGURATION ARRANGEMENTS OPTIONS

## 7.1 SMITHFIELD DAM

### 7.1.1 General Layouts

The layouts described in **Table 7.1** have been identified. The layouts are shown on figures as indicated.

**Table 7.1: Dam Site and Type options**

Dam option	Figure number
Site A: Option 1: ECRD with side channel spillway on right bank and tunnel/cofferdam diversion arrangement. Permanent Outlet through intake structure and one of the tunnels.	5
Site A: Option 2: Combined RCC gravity spillway with EED right bank.	6
Site B: Option 1: ECRD with side channel spillway and tunnel/cofferdam diversion structure on right bank and Saddle embankment. Permanent Outlet through intake structure and one of the tunnels.	7
Site B: Option 2: Central RCC spillway structure with EED flanks and Saddle embankment.	8
Site B: Option 3: ECRD with tunnel/cofferdam diversion structure, Saddle embankment and chute spillway at left side of saddle embankment. Permanent Outlet through intake structure and one of the tunnels.	9
Site C: Option 1: ECRD with side channel spillway on left bank and tunnel/cofferdam diversion structure. Permanent Outlet through intake structure and one of the tunnels.	10
Site C: Option 2: RCC Gravity Dam with central spillway	11

### 7.1.2 Specific arrangements

For each option two layouts associated with outlets have been considered, namely an outlet for pumping and an outlet (intake structures) to the tunnels. The layouts of the intake structures for the pumping and tunnel options are shown in **Figure 7.9**, **Figure 7.10** and **Figure 7.11**. A larger intake structure is required for the pumping option which is associated with a pumphouse. No structures for the releases of instream flow requirements have been included in the analysis as these costs are common to all considered options. Furthermore, the relocation of power lines around

the reservoir is a common cost and has not been taken into consideration in the comparisons.

The deviation of the road for Site A and the longer transfer tunnel for Site C is included in the determination of the cost.

A summary of the options and specific arrangements/infrastructure are described in **Table 7.2**.

**Table 7.2: Dam options and special arrangements**

Dam option	Specific arrangement/infrastructure
Site A: Option 1: <b>ECRD with side channel spillway</b> on right bank and tunnel/cofferdam diversion arrangement. Permanent Outlet through intake structure and one of the tunnels	For water supply: Intake Tower upstream of one diversion tunnel, pipeline through diversion tunnel to Pump Station or tunnel. Pump Station downstream of the dam for pumping option. No pumping station for tunnel option.
Site A: Option 2: <b>Combined RCC gravity spillway</b> with EED right bank.	For water supply: Intake Tower upstream of dam, pipeline to Pump Station or tunnel. Pump station downstream of the dam for pumping option. Schematically depicted in <b>Figure 7.9</b> . No pumping station for tunnel option.
Site B: Option 1: <b>ECRD with side channel spillway</b> and tunnel/cofferdam diversion structure on right bank and Saddle embankment. Permanent Outlet through intake structure and one of the tunnels	For water supply: Intake tower to tunnel and larger intake tower with Pump Station house at site A. See <b>Figure 7.10</b> and <b>Figure 7.11</b> .
Site B: Option 2: <b>Central RCC spillway structure</b> with EED flanks and Saddle embankment.	For water supply: Intake Tower upstream of dam, pipeline to Pump Station or tunnel. Schematically depicted in <b>Figure 7.9</b> , <b>Figure 7.10</b> and <b>Figure 7.11</b> . No pumping station for tunnel option.
Site B: Option 3: <b>ECRD with tunnel/cofferdam diversion structure, Saddle embankment and side channel spillway</b> at left side of saddle embankment. Permanent Outlet through intake structure and one of the tunnels	For water supply: Intake tower to tunnel and larger intake tower with Pump Station house at site A. See <b>Figure 7.10</b> and <b>Figure 7.11</b> .
Site C: Option 1: <b>ECRD with side channel spillway</b> on left bank and tunnel/cofferdam diversion structure. Permanent Outlet through intake structure and one of the tunnels	For water supply: Intake tower to tunnel and larger intake tower with Pump Station house upstream of the embankment See <b>Figure 7.10</b> and <b>Figure 7.11</b> .
Site C: Option 2: RCC Gravity Dam with central spillway	For water supply: Intake Tower upstream of dam, pipeline to Pump Station or tunnel. Pump station downstream of the dam for pumping option. Schematically depicted in <b>Figure 7.9</b> . No pumping station for tunnel option.

## 7.2 BALANCING DAM

An Earth Core Rockfill Dam (ECRD) with the Outlet works and ogee shaped, side channel spillway on the left flank was considered. The diversion tunnels were also placed on the left flank. The transfer structure was placed on the right flank in order to facilitate the transfer to the water treatment works. The layout of the considered balancing dam is shown in **Figure 7.8**.





Figure 7.1: Smithfield Dam Site A, Option 1



**Figure 7.2: Smithfield Dam Site A, Option 2 - Dam Layout**






Figure 7.3: Smithfield Dam Site B, Option 1- Dam





Figure 7.4: Smithfield Dam Site B, Option 2



**Figure 7.5: Smithfield Dam Site B, Option 3**





Figure 7.6: Smithfield Dam Site C, Option 1



**Figure 7.7: Smithfield Dam Site C, Option 2**




Figure 7.8: New Baynesfield Balancing Dam, Option 2




Figure 7.9: Intake tower through RCC structure




Figure 7.10: Intake tower for tunnel option






Figure 7.11: Intake tower for pump option

## 8 DAM CROSS SECTION LAYOUTS

---

### 8.1 SMITHFIELD DAM

Cross sections for the ECRD and the RCC gravity structures are shown in **Figure 8.1**.

### 8.2 BALANCING DAM

The New Baynesfield Balancing Dam was estimated with the same cross section layout as shown in **Figure 8.1**.




Figure 8.1: Typical cross sections of embankments

## 9 FOUNDATION CONSIDERATIONS

### 9.1 SMITHFIELD DAM SITE B

Based on Site B investigations the layout and the depths of excavation on the areas indicated are shown in **Table 9.1**.

**Table 9.1: Depths (m) of excavation for Site B**

Left Bank		River Section		Right Flank		Spillway
Siltstone Dolerite Siltstone		Siltstone		Alluvium Siltstone Dolerite Siltstone		Alluvium Siltstone Dolerite
Core	Concrete	Core	Concrete	Core	Concrete	Concrete
3 - 5	7 - 10	1 - 3	7,5	5 - 11	>13	>13

### 9.2 SMITHFIELD DAM SITE A

**Table 9.2** shows the excavation depths assumed for Site A.

**Table 9.2: Depths (m) of excavation for Site A**

Left Bank		River Section		Right Flank		Spillway
Siltstone Dolerite		Siltstone		Alluvium Siltstone		Alluvium Siltstone Dolerite
Core	Concrete	Core	Concrete	Core	Concrete	Concrete
3 - 5	7 - 10	1 - 3	7,5	5 - 11	>13	>13

### 9.3 SMITHFIELD DAM SITE C

The excavation depths shown in **Table 9.3** have been assumed for Site C.

**Table 9.3: Depths (m) of excavation for Site C**

Left Bank		River Section		Right Flank		Spillway
Siltstone Dolerite Siltstone		Siltstone		Alluvium Siltstone Dolerite Siltstone		Alluvium Siltstone Dolerite
Core	Concrete	Core	Concrete	Core	Concrete	Concrete
2 - 4	5 - 10	2 - 3	7,5	5 - 11	>10	4 - 8

#### 9.4 NEW BAYNESFIELD BALANCING DAM SITE

The VAPS model was utilised to determine the excavation depths. VAPS proposes that for a CFRD the footprint of the embankment should be excavated 2 m deep. The core should be excavated by a factor in relation to the height of the embankment. Therefore the core invert level was excavated a further 2 m deep, 22 m wide and with V1:H1 side slopes.

# 10 COST ESTIMATION

## 10.1 SMITHFIELD DAM

### 10.1.1 Dam Cost

The Schedules of Quantities (SOQ's) of the cost estimates are included in Appendices as shown in **Table 10.1**. Latest tender rates e.g. for Springs Grove Dam contract were used for cost estimate. A summary of the capital costs for layout for the outlet for pumping option and for supply to pressure tunnel are also shown in **Table 10.1**.

**Table 10.1: Summary of Comparable Cost Estimates of the Dams**

Dam option	Appendix where SOQ is included	Capital cost (R million excluding VAT)	
		Outlet for pumping option	Outlet for supply to pressure tunnel
Site A: Option 1: ECRD with side channel spillway on right bank and tunnel/cofferdam diversion structure.	Appendix H	1 334	1 328
Site A: Option 2: Combined RCC gravity spillway with EED right bank.	Appendix I	1 856	1 844
Site B: Option 1: ECRD with side channel spillway and tunnel/cofferdam diversion structure on right bank and Saddle embankment.	Appendix J	1 117	935
Site B: Option 2: Central RCC spillway structure with EED flanks and Saddle embankment.	Appendix K	1 575	1 384
Site B: Option 3: ECRD with tunnel/cofferdam diversion structure, Saddle embankment and chute spillway at left side of saddle embankment.	Appendix L	999	817
Site C: Option 1: ECRD with side channel spillway on left bank and tunnel/cofferdam diversion structure.	Appendix M	1 414	1 229
Site C: Option 2: RCC Gravity Dam with central spillway.	Appendix N	1 650	1 469

## 10.2 BALANCING DAM

Cost estimates of the Balancing Dams are included in **Appendix O** and a summary is shown in **Table 10.2**.

**Table 10.2: Summary of new Balancing Dam Options**

Dam option	Capital cost (R excluding VAT)
Option 2: One dam	R 887,1 million

# 11 CONCLUSIONS

---

## 11.1 COMPARISON OF DAMS

### 11.1.1 Smithfield Dam

From **Table 10.1** the following is clear:

- ◆ Site C Dams are higher in cost in relation to other options. These dams should not be considered further.
- ◆ Site B: Option 3 Dam has the lowest cost with site B: Option 1 second lowest (Sensitivity analysis on rockfill haulage for Site B: Option 3 dams concludes this same assumption).
- ◆ Site A dam options all have higher costs than site B dams.

Site A: Option 1 and Site B: Option 3 costs have been used in the *5.1 Optimization of Conveyance System Report*. The outcome of the complete conveyance system showed that Site B: Option 3 dam with a pressure tunnel is the preferred option.

### 11.1.2 Baynesfield Dam

Due to the proposed position of the balancing dam and the overall scheme configuration water can only be abstracted between levels 872 masl and 879,2 masl as described in the Report 5.1 Optimization of Conveyance System. In order to obtain the required 21 day balancing and deliverable height (872 masl) a very high embankment needs to be constructed. This dam has a large “dead” storage volume below 872 masl.

The following options are available and should be investigated:

- ◆ The construction of the proposed new Baynesfield Balancing Dam;
- ◆ The construction of a balancing dam at the proposed position with a FSL at 872 masl. The required abstraction could be obtained by pumping to the nearby water treatment works. However, the cost of a pump station to transfer 15 m<sup>3</sup>/s is significant and the very irregular period of operation of the pump station will be unpractical;
- ◆ The construction of a balancing dam at Umlaas road (and water treatment plant);



- The utilization of the existing water resources and water supply infrastructure to supplement the uMkhomazi system when maintenance of the tunnel is required.

## 12 RECOMMENDATION FOR MATERIALS, BORROW AREAS AND QUARRIES FOR AND LAYOUT OF PREFERRED DAMS

---

The following are recommended:

- ◆ Smithfield Dam Site B: Option 3 be investigated for foundation and material conditions;
- ◆ The balancing dam position is re-considered, after appointment of the Umgeni Water consultant for the pipeline section of the conveyance structure to Umlaas Road reservoir;
- ◆ Phasing of the balancing dam in accordance with the size of the tunnel (one large tunnel as opposed to twin tunnels – one tunnel constructed later when required).

## 13 REFERENCES

---

Ninham Shand (1999): *Mkomazi/Mooi-Mgeni Transfer Scheme Pre-feasibility Study. Report number: PB1 Ui00-00-1399*. Department of Water Affairs and Forestry in association with Umgeni Water Corporate Services Division. Supporting Report no 6: Engineering Design and Costing. Report number 27871/7856. May 1999.

SANCOLD (1991): *Guidelines on Safety in Relation to Floods*. SANCOLD. P.O. Box 3404, Pretoria, South Africa.

SANCOLD (1990). *Interim Guidelines on the Freeboard of Dams, Report No.3*. The South African National Committee on Large Dams, PO Box 3404, Pretoria 0001, RSA.

United States Department of the Interior Bureau of Reclamation. *Design of small dams* (1987) US Government printing Office

Van der Walt, D, Dunbar, R.M,(1990): *Baynesfield Dam, Dam Safety Inspection Report* (1990), Bradford Conning and Partners, 217 Burger str. Pietermaritzburg, 3201.

Robertson, RM, Sellick, ECH, (1999), *Baynesfield Dam, Second Dam Safety Report*, 1999, MBB Consulting Engineers, P.O. Box 2821, Pietermaritzburg, 3200

Rennie AG: *Report on Mbangweni Dam Safety Inspection*, 2011, MBB Consulting Engineers, P.O. Box 12051, Dorpspruit, 3206.

BKS 2012: Task 5.1: *Optimization of conveyance System Report*. BKS report number J01763 of May 2012. Client: The Department of Water Affairs.

Department of Water Affairs and Forestry, Directorate Project Planning (1996), *Guidelines for the Preliminary Siting, Costing and Engineering Economic Evaluation of Planning Operations*. Vaal Augmentation Planning Study (VAPS).

# **Appendix A**

## **Photographs of Smithfield Dam**



**Figure 1: Site B: View from left bank towards downstream**



**Figure 2: Site C: Area on left bank for spillway viewing upstream**

---

# **Appendix B**

## **Photographs of balancing dam sites**



**Figure 1: Baynesfield Dam: Dam viewed from the left bank**



**Figure 2: Baynesfield Dam: Concrete A-frame spillway with splitters**



**Figure 3: Baynesfield Dam: Spalled concrete on slipway due to movement**



**Figure 4: Baynesfield Dam: Spalled concrete on spillway due to movement of concrete structure on embankment.**








**Figure 5: Mbangweni Embankment left bank**




**Figure 6: Mbangweni Embankment: Right Bank. Pump Station downstream of the dam**

# **Appendix C**




## **Smithfield Dam stage/area, volume curves**






# **Appendix D**

## **Balancing dam stage/area, volume curves**



# **Appendix E**

## **Catchment and longest watercourse, Option 2 New Baynesfield dam**






# **Appendix F**

## **Smithfield dam site, flood attenuation**


Smithfield Dam  
Safety evaluation Hydrograph

Time (h)	Inflow 1:200 m3/s	Inflow RMF+delta m3/s
0	0	0
0.9	63.9	175
1.8	133.4	366
2.7	143.4	393
3.6	175.4	481
4.5	272.1	746
5.4	447.6	1,227
6.3	695.6	1,906
7.2	997.2	2,733
8.1	1326	3,634
9	1654	4,533
9.9	1954.3	5,356
10.8	2204.8	6,042
11.7	2389.9	6,550
12.6	2501.5	6,855
13.5	2540	6,961
14.4	2513.4	6,888
15.3	2437	6,679
16.2	2331.7	6,390
17.1	2222.1	6,090
18	2134.2	5,849
18.9	2014.1	5,520
19.8	1853.1	5,079
20.7	1704.9	4,672
21.6	1568.6	4,299
22.5	1443.2	3,955
23.4	1327.8	3,639
24.3	1221.6	3,348
25.2	1124	3,080
26.1	1034.1	2,834
27	951.4	2,607
27.9	875	2,398



uMkhomazi Feasibility Study  
 Flood Attenuation Results  
 Spillway ogee weir width 160m

Time (h)	Inflow: RMF + Delta (m <sup>3</sup> /s)	Outflow (m <sup>3</sup> /s)
0	0	0
0.9	175	7.5
1.8	366	30.2
2.7	393	66.8
3.6	481	11.5
4.5	746	152.6
5.4	1,227	194
6.3	1,906	239
7.2	2,733	300
8.1	3,634	417
9	4,533	610
9.9	5,356	854
10.8	6,042	1,196
11.7	6,550	1,495
12.6	6,855	1,753
13.5	6,961	2,108
14.4	6,888	2,506
15.3	6,679	2,957
16.2	6,390	3,446
17.1	6,090	3,983
18	5,849	4,655
18.9	5,520	5,229
19.8	5,079	5,717
20.7	4,672	6,099
21.6	4,299	6,382
22.5	3,955	6,587
23.4	3,639	6,702
24.3	3,348	6,737
25.2	3,080	6,709
26.1	2,834	6,628
27	2,607	6,511
27.9	2,398	6,369





# **Appendix G**

## **New Baynesfield dam flood attenuation**







# **Appendix H**

## **Smithfield dam site A, Option 1**

### **BOQ**



SITE A, OPTION 1  
with  
OUTLET WORKS TO PUMPSTATION

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>PART 2: RIVER DIVERSION</b>						
<b>STAGE 1</b>						
1	<b>SANS 1200 C</b>	<b>SITE CLEARANCE</b>				
	1.1	Clear and grub				
		(a) Portal footprints	ha	1.2	26 546.00	31 855
	1.2	Remove and grub large trees and tree stumps of girth				
		(a) over 1 m and up to and including 2m	No	2	1 700.00	3 400
	1.3	Remove topsoil to nominal depth of 150 mm and stockpile	m <sup>3</sup>	1800	20.00	36 000
2	<b>P10</b>	<b>EXCAVATION AND BACKFILL FOR DAMS AND WATERWAYS</b>				
		Bulk Excavation				
	2.1	<b>Inlet portal</b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	122 615	21.00	2 574 915
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	30 654	3.30	101 157
		(ii) Hard Rock	m <sup>3</sup>	30 654	34.00	1 042 228
		(iii) Boulder, Class A	m <sup>3</sup>	12 262	78.00	956 397
		(iv) Boulder, Class B	m <sup>3</sup>	6 131	61.00	373 976
	2.2	<b>Outlet Portal</b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	86 651	21.00	1 819 671
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	21 663	3.30	71 487
		(ii) Hard Rock	m <sup>3</sup>	21 663	34.00	736 534
		(iii) Boulder, Class A	m <sup>3</sup>	12 998	78.00	1 013 817
		(iv) Boulder, Class B	m <sup>3</sup>	4 333	61.00	264 286
	2.3	Dewatering	Sum	1	100 000.00	100 000
<b>STAGE 2</b>						
3	<b>SANS 1200 C</b>	<b>SITE CLEARANCE</b>				
	3.1	Clear and grub				
		(a) Embankment footprint	ha	1.3	26 546.00	34 510
	3.2	Remove and grub large trees and tree stumps of girth				
		(a) over 1 m and up to and including 2 m	No	2	1 700.00	3 400
4	<b>P10</b>	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>				
	4.1	(a) Excavate all materials				
		(i) Excavate and dispose footprint of Upstream & Downstream cofferdam	m <sup>3</sup>	4 757	21.00	99 897
<b>TOTAL CARRIED FORWARD</b>						<b>9 263 528</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>9 263 528</b>
5	P21	<b>EMBANKMENT CONSTRUCTION</b> Earthfill Upstream & Downstream Cofferdam Construction. Forming Embankment Using material from designated borrow areas or commercial sources				
	5.1	(4) Homogeneous Material	m <sup>3</sup>	65853	50	3 292 650
6		<b>TUNNEL CONSTRUCTION</b>				
	6.1	<b>TUNNEL EXCAVATION</b> (a) Tunnel (Rock class II)	m <sup>3</sup>	40186	2 051	82 402 471
	6.2	<b>ROCK SUPPORT</b> (a) Rockbolts (b) Shotcrete (c) Reinforcing mesh	m m <sup>3</sup> m <sup>2</sup>	17040 814 5297	37 2 500 26	623 886 2 035 929 137 715
	6.3	Dewatering	Sum	1	550 000	550 000
<b>STAGE 3</b>						
7		<b>MEDIUM PRESSURE PIPELINES</b>				
	7.1	Supply, lay, and bed pipes complete with couplings (a) 500 mm diameter concrete pipe (class 75D) in concrete (b) Water control in tunnel	m Prov Sum	299 1	80 100 000	23 920 100 000 .
8		<b>PLUG OF TUNNEL</b>				
	8.1	<u>Scheduled Formwork items</u> Class F1 (a) Vertical formwork	m <sup>2</sup>	310	550	170 500
	8.2	<u>Scheduled Concrete items</u>				
	8.3	<u>Strength and Mass concrete</u> (a) Sealing of bulkheads shaft with mass concrete 25 Mpa/19 mm (c) Plug 25 MPa/19 mm	m <sup>3</sup> m <sup>3</sup>	1 050 708	1 100 1 100	1 155 000 778 250
	8.4	<u>Joints</u>				
	8.5	(e) Swellable water stops	m	30	500	15 000
	8.6	<u>Miscellaneous and Sundry items</u> (a) Bulkheads incl reinforcement at 120 kg/m <sup>3</sup>	No	240	3 000	720 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>101 268 848</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
9	SANS 1200 C	<b>SITE CLEARANCE</b>					
		9.1	<u>Clear and grub</u>				
			(a) Embankment footprint	ha	13.40	26 546	355 716
			(b) Spillway	ha	19.70	13 635	268 610
		9.2	<u>Remove and grub large trees and tree stumps of girth</u>				
			(a) over 1 m and up to and including 2 m				
			(i) Embankment footprint	No	5	1 700	8 500
			(ii) Spillway	No	2	1 700	3 400
		9.3	<u>Remove topsoil to nominal depth of 300 mm and stockpile</u>				
			(a) Embankment footprint	m <sup>3</sup>	40 332	21	846 972
	(b) Spillway	m <sup>3</sup>	59 643	16	954 288		
10	P10	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>					
		10.1	<u>Bulk Excavation</u>				
			(a) Excavate in all materials (to stockpile or dispose)				
			(i) Stockpile				
			(1) Embankment footprint (Use in rockfill)	m <sup>3</sup>	0	35	0
			(2) Spillway (Use in Rockfill)	m <sup>3</sup>	0	31	0
			(3) Portals (Use in Rockfill)	m <sup>3</sup>	0	35	0
			(b) Extra over for:				
			(i) Intermediate excavation	m <sup>3</sup>	0	3	0
			(ii) Hard rock excavation	m <sup>3</sup>	0	34	0
			(iii) Boulder excavation, Class A	m <sup>3</sup>	0	79	0
			(iv) Boulder excavation, Class B	m <sup>3</sup>	0	61	0
		10.2	<u>Foundation Treatment</u>				
			(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	7 326	664	4 864 464
	(b) Treatment of Faults, Dykes, Shear Zones and Zones of Poor Rock	m <sup>3</sup>	7 326	660	4 835 160		
<b>TOTAL CARRIED FORWARD</b>						<b>12 137 110</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
11	P21	<b>EMBANKMENT CONSTRUCTION</b>				
	11.1	<u>Forming Embankment</u> Using material from designated borrow areas				
		(1) Rockfill	m <sup>3</sup>	2 826 165	71	200 657 715
		(2) Clay Core	m <sup>3</sup>	584 300	50	29 215 000
		(3) Filter	m <sup>3</sup>	172 215	450	77 496 750
	11.2	Overhaul (Clay for 10 km)	m <sup>3</sup> .km	141 308	3	423 925
12		<b>SECTION : DRILLING &amp; GROUTING</b>				
		(a) Curtain grouting	m	850	13 457	11 438 450
		(b) Consolidation grouting	m	850	2 820	2 397 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>321 628 840</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
13	P20	<b>CONVENTIONAL CONCRETE FOR DAMS</b>					
		13.1 <u>Scheduled Formwork items</u>					
		Class F4					
		(a) Vertical					
		(1) Spillway	m <sup>2</sup>	2 412	550	1 326 600	
		(2) Transfer structure	m <sup>2</sup>	8 859	550	4 872 450	
		(b) Sloped					
		(1) Ogee of spillway - Drawing (05/02)	m <sup>2</sup>	1 364	550	750 200	
		(c) Sloping					
		(1) Stilling basin blocks	m <sup>2</sup>	33	550	18 150	
		(e) Horizontal	m <sup>2</sup>	64	550	35 200	
		Keyways on contraction joints					
		(a) Bridges dimensions to be given in detail design	m	20	100	2 000	
		13.2 <u>Scheduled Reinforcement items</u>	t	4 408	8 400	37 023 840	
		13.3 <u>Anchors</u>					
		Anchor bars (Y32 @ 2.5 m x 2 m)	t	77	8 500	654 883	
		13.4 <u>Scheduled Concrete items</u>					
		Strength & Mass Concrete					
		(a) Grade 25 MPa/19 mm					
		(1) Spillway, bridges and retaining wall	m <sup>3</sup>	31 338	1 500	47 007 000	
		(2) Transfer intake	m <sup>3</sup>	36 251	1 500	54 376 500	
		Secondary Concrete					
		(a) Grade 25 MPa/19 mm	m <sup>3</sup>	100	1 800	180 000	
13.5 <u>Unformed Surface Finishes</u>							
Class U2 (Wood-floated) finish							
(a) Top of chute	m <sup>2</sup>	333	23	7 659			
(b) Top of bridges	m <sup>2</sup>	197	23	4 531			
(c) Chute and Stilling basin floor	m <sup>2</sup>	24 420	23	561 660			
(d) Transfer intake	m <sup>2</sup>	714	25.00	17 840			
14		<b>MECHANICAL ITEMS</b>					
		(a) Valves and gates	Sum			6 840 000	
		(b) Cranes & Hoists	Sum			2 330 000	
		(c) Structural steelwork	Sum			1 712 971	
		(d) Pipe (2 x 2diam steel pipe)	m	600	20 000	12 000 000	
		(e) Pipes from pumpstation to tunnel inlet	m	600	18 000	10 800 000	
<b>TOTAL CARRIED FORWARD</b>						<b>180 521 484</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>180 521 484</b>
<b>15</b>		<b>WATERSTOPS, JOINTING AND BEARINGS</b>				
		<u>Scheduled items</u>				
	15.1	Waterstops				
		(a) 250 mm Centre bulb PVC waterstop	m	1 280	630	806 526
	15.2	Joint sealants				
		(a) Chute wall - 12mm expanding cork	m	1 280	10	12 802
		(b) Chute wall - 12m Impregnated Bitumen Fibre board	m	1 280	10	12 802
		(c) Chute wall - 12 x 12 mm Polysulphide sealant	m	1 280	10	12 802
<b>16</b>		<b>SUB-SOIL DRAINAGE</b>				
		<u>Scheduled items</u>				
	16.1	Excavation for sub-soil drainage system				
		(a) Excavating soft material situated within the following depth ranges below the surface level:				
		(i) 0 m to 1,5 m	m <sup>3</sup>	305	21	6 410
		(b) Extra over sub-item (a), irrespective of depth, for:				
		(ii) Excavation in hard material	m <sup>3</sup>	153	4	611
	16.2	Natural permeable material in sub-soil drainage systems				
		(b) Sand as specified on detail drawings	m <sup>3</sup>	293	550	161 172
	16.3	Pipes in sub-soil drainage system				
		(c) 110 NB, Class 6, HDPE pressure pipe, non perforated, complying with SANS 533, Part II	m	1 221	400	488 400
		(d) 75 NB, flexible slotted drainage pipes with smooth bore, "Drainex" or equivalent by Kaytech	m	370	330	122 100
	16.4	Caps to higher ends of sub-surface drain pipes				
		(a) High end of pipes of Drainex pipes	No	19	50	925
	16.5	Concrete outlet structures for sub-soil drainage systems complete as per drawings				
		(a) Concrete 1500 mm dia	No	8	600	4 800
	16.6	Overhaul for material hauled in excess of 1.0 km freehaul				
		(a) Sand for filter material (10 km)	m <sup>3</sup> .km	2 930	3	8 791
<b>17</b>		<b>ROAD DEVIATION TO ACCOMMODATE DAM LEVEL</b>				
		(a) Road (1 300 m long x 11,4 m wide)	m <sup>2</sup>	14 820	770	11 411 400
		(b) Bridges ( 230 m long bridges x 11.4 m wide)	m <sup>2</sup>	2 622	15 000	39 330 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>232 901 025</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
18	18.1	<b>SITE CLEARANCE</b>				
		<u>Clear and grub</u>				
		(a) Footprint	ha	0.05	26 546	1 327
18.2	18.2	<u>Remove and grub large trees and tree</u>				
		(a) over 1 m and up to and including 2 m (i) Embankment footprint	No	1	1 700	1 700
18.3	18.3	<u>Remove topsoil to nominal depth of 300</u>				
		(a) Footprint	m <sup>3</sup>	150	21	3 150
19	19.1	<b>EXCAVATIONS AND BACKFILL FOR</b>				
		<u>Bulk Excavation</u>				
		(a) Excavate in all materials (to stockpile or dispose)				
		(i) Stockpile				
		(1) Embankment footprint (Use in rockfill)	m <sup>3</sup>	3570	35	124 950
		(b) Extra over for:				
		(i) Intermediate excavation	m <sup>3</sup>	1 071	3	3 427
		(ii Hard rock excavation )	m <sup>3</sup>	714	34	24 276
		(iii Boulder excavation, Class A )	m <sup>3</sup>	179	79	14 012
		(i Boulder excavation, Class B )	m <sup>3</sup>	179	61	10 889
19.2	19.2	<u>Foundation Treatment</u>				
		(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	510	664	338 640
		(b) Treatment of Faults, Dykes, Shear Zones and Zones of Poor Rock	m <sup>3</sup>	510	660	336 600



ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL CARRIED FORWARD</b>						<b>858 971</b>
20		<u>Scheduled Reinforcement items</u> Steel				
		(a) High tensile steel 16 mm diameter and over	t	169	8 400	1 417 080
21		<u>Scheduled Concrete items</u> Blinding layer and Dental Concrete				
		(b) Dental concrete (Class 15/38)	m <sup>3</sup>	474	1 869	886 467
		Strength and Mass Concrete				
		(a) Strength Concrete (Class 30/38)	m <sup>3</sup>	1 687	1 500	2 530 500
		Secondary concrete (Class 30/19)	m <sup>3</sup>	100	1 870	187 000
22		<u>Unformed Surface Finishes</u> Class U2 finish				
			m <sup>2</sup>	2 489	29	72 181
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>5 093 228</b>

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE RAND	AMOUNT
23		<b>Landscaping</b> (% of 1-9)	%	673 029 051	5	33 651 453
24		<b>Miscellaneous</b> (% of 1-9)	%	673 029 051	15	101 627 387
		<b>SUB TOTAL A</b>				808 307 890
25		<b>Preliminary &amp; General</b> (% of sub-total A)	%	808 307 890	30	242 492 367
26		<b>Preliminary works</b>				
	26.1	(a) Access road	km	4.6	400 000	1 840 000
	26.2	(b) Electrical supply to site	Sum			1 000 000
	26.3	(c) Construction water to site	Sum			300 000
	26.4	(d) Railhead & materials handling	Sum			
	23.5	Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				1 054 240 257
27		<b>Contingencies</b> (% of sub total B)	%	1 054 240 257	10	105 424 026
		<b>SUB TOTAL C</b>				1 159 664 283
28		<b>Planning design &amp; supervision</b> (% of sub total C)	%	1 159 664 283	15	173 949 642
		<b>SUB TOTAL D</b>				1 333 613 926
29		<b>VAT</b> (% of sub total D)	%	1 333 613 926	0	0
		<b>NETT PROJECT COST</b>				1 333 613 926
30		<b>Cost of relocations</b>	Sum			
31		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				1 333 613 926

SITE A, OPTION 1  
with  
OUTLET WORKS TO TUNNEL INLET

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE RAND	AMOUNT
15		<b>Landscaping</b> (% of 1-9)	%	670 935 823	5	33 546 791
16		<b>Miscellaneous</b> (% of 1-9)	%	670 935 823	15	100 640 374
		<b>SUB TOTAL A</b>				805 122 988
17		<b>Preliminary &amp; General</b> (% of sub-total A)	%	805 122 988	30	241 536 896
18		<b>Preliminary works</b>				
	18.1	(a) Access road	km	4.6	400 000	1 840 000
	18.2	(b) Electrical supply to site	Sum			1 000 000
	18.3	(c) Construction water to site	Sum			300 000
	18.4	(d) Railhead & materials handling	Sum			
	18.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				1 050 099 885
19		<b>Contingencies</b> (% of sub total B)	%	1 050 099 885	10	105 009 988
		<b>SUB TOTAL C</b>				1 155 109 873
20		<b>Planning design &amp; supervision</b> (% of sub total C)	%	1 155 109 873	15	173 266 481
		<b>SUB TOTAL D</b>				1 328 376 354
21		<b>VAT</b> (% of sub total D)	%	1 328 376 354	0	0
		<b>NETT PROJECT COST</b>				1 328 376 354
22		<b>Cost of relocations</b>	Sum			
23		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				1 328 376 354

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>STAGE 1</b>						
1		<b>SITE CLEARANCE</b> Clear and grub				
		(a) Portal footprints	ha	1.2	26 546.00	31 855
		Remove and grub large trees and tree stumps of girth				
		(a) over 1 m and up to and including 2m	No	2	1 700.00	3 400
2		Remove topsoil to nominal depth of 150 mm and stockpile	m <sup>3</sup>	1800	20.00	36 000
<b>EXCAVATION AND BACKFILL FOR DAMS AND WATERWAYS</b>						
	2.1	<b>Bulk Excavation</b> <b>Inlet portal</b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	122 615	21.00	2 574 915
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	30 654	3.30	101 157
		(ii) Hard Rock	m <sup>3</sup>	30 654	34.00	1 042 228
		(iii) Boulder, Class A	m <sup>3</sup>	12 262	78.00	956 397
		(iv) Boulder, Class B	m <sup>3</sup>	6 131	61.00	373 976
	2.2	<b>Outlet Portal</b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	86 651	21.00	1 819 671
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	21 663	3.30	71 487
		(ii) Hard Rock	m <sup>3</sup>	21 663	34.00	736 534
		(iii) Boulder, Class A	m <sup>3</sup>	12 998	78.00	1 013 817
		(iv) Boulder, Class B	m <sup>3</sup>	4 333	61.00	264 286
3		<b>EMBANKMENT CONSTRUCTION</b> Dewatering	Sum	1	100 000.00	100 000
<b>STAGE 2</b>						
4		<b>SITE CLEARANCE</b>				
	4.1	Clear and grub				
		(a) Embankment footprint	ha	1.3	26 546.00	34 510
		Remove and grub large trees and tree stumps of girth				
	4.2	(a) over 1 m and up to and including 2 m	No	2	1 700.00	3 400
5		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>				
		(a) Excavate all materials				
		(i) Excavate and dispose footprint of Upstream & Downstream cofferdam	m <sup>3</sup>	4 757	21.00	99 897
<b>TOTAL CARRIED FORWARD</b>						<b>9 263 528</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>9 263 528</b>
6		<b>EMBANKMENT CONSTRUCTION</b> Earthfill Upstream & Downstream Cofferdam Construction. Forming Embankment Using material from designated borrow areas or commercial sources				
		(4) Homogeneous Material	m <sup>3</sup>	65853	50	3 292 650
7		<b>TUNNEL CONSTRUCTION</b>				
	7.1	<b>Tunnel excavation</b>				
		(a) Tunnel (Rock class II)	m <sup>3</sup>	40186	2 051	82 402 471
	7.2	<b>Rock support</b>				
		(a) Rockbolts	m	17040	37	623 886
		(b) Shotcrete	m <sup>3</sup>	814	2 500	2 035 929
		(c) Reinforcing mesh	m <sup>2</sup>	5297	26	137 715
	7.3	Dewatering	Sum	1	550 000	550 000
		<b>STAGE 3</b>				
8		<b>MEDIUM PRESSURE PIPELINES</b> Supply, lay, and bed pipes complete with couplings				
		(a) 500 mm diameter concrete pipe (class 75D) in concrete	m	299	80	23 920
		(b) Water control in tunnel	Prov Sum	1	100 000	100 000
9		<b>Plug of Tunnel (Stage 3)</b>				
	9.1	<u>Scheduled Formwork items</u> Class F1				
		(a) Vertical formwork	m <sup>2</sup>	310	550	170 500
	9.2	<u>Scheduled Concrete items</u> Strength and Mass concrete				
		(a) Sealing of bulkheads shaft with mass concrete 25 Mpa/19 mm	m <sup>3</sup>	1 050	1 100	1 155 000
		(c) Plug 25 MPa/19 mm	m <sup>3</sup>	708	1 100	778 250
	9.3	<u>Joints</u>				
		(e) Swellable water stops	m	30	500	15 000
	9.4	<u>Miscellaneous and Sundry items</u>				
		(a) Bulkheads incl reinforcement at 120 kg/m <sup>3</sup>	No	240	3 000	720 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>101 268 848</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
6	6.1	<b>SITE CLEARANCE</b>					
		<u>Clear and grub</u>					
		(a)	Embankment footprint	ha	13.40	26 546	355 716
		(b)	Spillway	ha	19.70	13 635	268 610
	6.2		<u>Remove and grub large trees and tree stumps of girth</u>				
			(a) over 1 m and up to and including 2 m				
			(i) Embankment footprint	No	5	1 700	8 500
		(ii) Spillway	No	2	1 700	3 400	
	6.3		<u>Remove topsoil to nominal depth of 300 mm and stockpile</u>				
			(a) Embankment footprint	m <sup>3</sup>	40 332	21	846 972
	(b) Spillway	m <sup>3</sup>	59 643	16	954 288		
7		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>					
	7.1		<u>Bulk Excavation</u>				
			(a) Excavate in all materials (to stockpile or dispose)				
			(i) Stockpile				
			(1) Embankment footprint (Use in rockfill)	m <sup>3</sup>	0	35	0
			(2) Spillway (Use in Rockfill)	m <sup>3</sup>	0	31	0
		(3) Portals (Use in Rockfill)	m <sup>3</sup>	0	35	0	
	7.2		(b) Extra over for:				
			(i) Intermediate excavation	m <sup>3</sup>	0	3	0
			(ii) Hard rock excavation	m <sup>3</sup>	0	34	0
			(iii) Boulder excavation, Class A	m <sup>3</sup>	0	79	0
		(iv) Boulder excavation, Class B	m <sup>3</sup>	0	61	0	
	7.3		<u>Foundation Treatment</u>				
		(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	7 326	664	4 864 464	
	(b) Treatment of Faults, Dykes, Shear Zones and Zones of Poor Rock	m <sup>3</sup>	7 326	660	4 835 160		
<b>TOTAL CARRIED FORWARD</b>						<b>12 137 110</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
8		<b>EMBANKMENT CONSTRUCTION</b>				
	8.1	<u>Forming Embankment</u> Using material from designated borrow areas				
		(1) Rockfill	m³	2 826 165	71	200 657 715
		(2) Clay Core	m³	584 300	50	29 215 000
		(3) Filter	m³	172 215	450	77 496 750
		Overhaul (Clay for 10 km)	m³.km	141 308	3	423 925
9		<b>SECTION : DRILLING &amp; GROUTING</b>				
		(a) Curtain grouting	m	850	13 457	11 438 450
		(b) Consolidation grouting	m	850	2 820	2 397 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>321 628 840</b>



ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
10	10.1	<b>CONVENTIONAL CONCRETE FOR DAMS</b>					
		<u>Scheduled Formwork items</u>					
		Class F4					
		(a) Vertical					
		(1) Spillway	m <sup>2</sup>	2 412	550	1 326 600	
		(2) Transfer structure	m <sup>2</sup>	8 859	550	4 872 450	
		(b) Sloped					
		(1) Ogee of spillway - Drawing (05/02)	m <sup>2</sup>	1 364	550	750 200	
		(c) Sloping					
		(1) Stilling basin blocks	m <sup>2</sup>	33	550	18 150	
		(e) Horizontal	m <sup>2</sup>	64	550	35 200	
		Keyways on contraction joints					
		(a) Bridges dimensions to be given in detail design	m	20	100	2 000	
		10.2	<u>Scheduled Reinforcement items</u>	t	4 408	8 400	37 023 840
		10.3	<u>Anchors</u>				
			Anchor bars (Y32 @ 2.5 m x 2 m)	t	77	8 500	654 883
		10.4	<u>Scheduled Concrete items</u>				
			Strength & Mass Concrete				
		(a) Grade 25 MPa/19 mm					
	(1) Spillway, bridges and retaining wall	m <sup>3</sup>	31 338	1 500	47 007 000		
(2) Transfer intake	m <sup>3</sup>	36 251	1 500	54 376 500			
	Secondary Concrete						
(a) Grade 25 MPa/19 mm	m <sup>3</sup>	100	1 800	180 000			
10.5	<u>Unformed Surface Finishes</u>						
	Class U2 (Wood-floated) finish						
(a) Top of chute	m <sup>2</sup>	333	23	7 659			
(b) Top of bridges	m <sup>2</sup>	197	23	4 531			
(c) Chute and Stilling basin floor	m <sup>2</sup>	24 420	23	561 660			
(d) Transfer intake	m <sup>2</sup>	714	25	17 840			
11		<b>MECHANICAL ITEMS</b>					
	(a) Valves and gates	Sum			6 840 000		
	(b) Cranes & Hoists	Sum			2 330 000		
	(c) Structural steelwork	Sum			1 712 971		
	(d) Pipe (2 x 2diam steel pipe)	m	1 290	20 000	25 800 000		
<b>TOTAL CARRIED FORWARD</b>						<b>183 521 484</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>183 521 484.35</b>
12		<b>WATERSTOPS, JOINTING AND BEARINGS</b>				
		<u>Scheduled items</u>				
		Waterstops				
		(a) 250 mm Centre bulb PVC waterstop	m	1 280	630	806 526
		Joint sealants				
		(a) Chute wall - 12mm expanding cork	m	1 280	10	12 802
		(b) Chute wall - 12m Impregnated Bitumen Fibre board	m	1 280	10	12 802
		(c) Chute wall - 12 x 12 mm Polysulphide sealant	m	1 280	10	12 802
13		<b>SUB-SOIL DRAINAGE</b>				
		<u>Scheduled items</u>				
	13.1	Excavation for sub-soil drainage system				
		(a) Excavating soft material situated within the following depth ranges below the surface level:				
		(i) 0 m to 1,5 m	m <sup>3</sup>	305	21	6 410
		(b) Extra over sub-item (a), irrespective of depth, for:				
		(ii) Excavation in hard material	m <sup>3</sup>	153	4	611
	13.2	Natural permeable material in sub-soil drainage systems				
		(b) Sand as specified on detail drawings	m <sup>3</sup>	293	550	161 172
	13.3	Pipes in sub-soil drainage system				
		(c) 110 NB, Class 6, HDPE pressure pipe, non perforated, complying with SANS 533, Part II	m	1 221	400	488 400
		(d) 75 NB, flexible slotted drainage pipes with smooth bore, "Drainex" or equivalent by Kaytech	m	370	330	122 100
	13.4	Caps to higher ends of sub-surface drain pipes				
		(a) High end of pipes of Drainex pipes	No	19	50	925
	13.5	Concrete outlet structures for sub-soil drainage systems complete as per drawings				
		(a) Concrete 1500 mm dia	No	8	600	4 800
		Overhaul for material hauled in excess of 1.0 km freehaul				
		(a) Sand for filter material (10 km)	m <sup>3</sup> .km	2 930	3	8 791
14		<b>ROAD DEVIATION TO ACCOMMODATE DAM LEVEL</b>				
		(a) Road (1 300 m long x 11,4 m wide)	m <sup>2</sup>	14 820	770	11 411 400
		(b) Bridges ( 230 m long bridges x 11.4 m wide)	m <sup>2</sup>	2 622	15 000	39 330 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>235 901 025</b>

# **Appendix I**

## **Smithfield Dam site A, Option 2**

### **BOQ**

SITE A, OPTION 2  
WITH  
OUTLET TO PUMPSTATION

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE RAND	AMOUNT
19	1-12	<b>Landscaping</b> (% of 1-9)	%	938 152 519	5	46 907 626
20	1-12	<b>Miscellaneous</b> (% of 1-9)	%	938 152 519	15	140 722 878
		<b>SUB TOTAL A</b>				1 125 783 023
21		<b>Preliminary &amp; General</b> (% of sub-total A)	%	1 125 783 023	30	337 734 907
22		<b>Preliminary works</b>				
	22.1	(a) Access road	km	5	400 000	1 840 000.00
	22.2	(b) Electrical supply to site	Sum			1 000 000
	22.3	(c) Construction water to site	Sum			300 000
	22.4	(d) Railhead & materials handling	Sum			
	22.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				1 466 957 929
23		<b>Contingencies</b> (% of sub total B)	%	1 466 957 929	10	146 695 793
		<b>SUB TOTAL C</b>				1 613 653 722
24		<b>Planning design &amp; supervision</b> (% of sub total C)	%	1 613 653 722	15	242 048 058
		<b>SUB TOTAL D</b>				1 855 701 781
25		<b>VAT</b> (% of sub total D)	%	1 855 701 781	0	0
		<b>NETT PROJECT COST</b>				1 855 701 781
26		<b>Cost of relocations</b>	Sum			
27		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				1 855 701 781

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
1	1	<b>SITE CLEARANCE</b>				
	1.2	<u>Clear and grub</u>				
		(a) Right flank footprint	ha	12.60	26 600	335 160
		(b) RCC footprint	ha	1.80	26 601	47 882
	1.3	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2 m				
		(i) Whole footprint area	No	5	1 700	8 500
	1.4	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>				
		(a) Right flank embankment	m <sup>3</sup>	38 113	21	800 373
		(b) RCC	m <sup>3</sup>	5 481	21	115 101
2	2.0	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>				
	2.1	<u>Bulk Excavation</u>				
		(a) Excavate in all materials (to stockpile or dispose)				
		(i) Stockpile				
		(1) Right flank core	m <sup>3</sup>	19071	30	572 130
		(2) RCC excavation	m <sup>3</sup>	98485	30	2 954 550
		(b) Extra over for:				
		(i) Intermediate excavation	m <sup>3</sup>	35 267	4	141 067
		(ii) Hard rock excavation	m <sup>3</sup>	23 511	34	799 381
		(iii) Boulder excavation, Class A	m <sup>3</sup>	5 878	79	464 346
	(iv) Boulder excavation, Class B	m <sup>3</sup>	954	61	58 167	
2.2	<u>Foundation Treatment</u>					
	(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	5 400	665	3 591 000	
	(b) Treatment of Faults, Dykes, Shear Zones and Zones of	m <sup>3</sup>	5 400	658	3 553 200	
<b>TOTAL CARRIED FORWARD</b>						<b>13 440 857</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
3		<b>PART 2 : RIVER DIVERSION</b>	Sum	1		15 000 000
4		<b>EMBANKMENT</b>				
		<b>SECTION: EARTHFILL DAM CONSTRUCTION</b>				
		Embankment				
4.1		(a) Trial Embankment	No			146 619
4.2		(b) Forming right flank embankment				
		(1) Earth fill	m <sup>3</sup>	1824788	46	83 940 248
		(2) Filters	m <sup>3</sup>	80232	431	34 579 992
		(3) Riprap	m <sup>3</sup>	374	351	131 274
		(4) Clay core	m <sup>3</sup>	446072	50	22 303 600
5		<b>CONCRETE STRUCTURE</b>				
		<b>SECTION: CONVENTIONAL CONCRETE FOR DAMS</b>				
		SCHEDULED FORMWORK ITEMS				
		Class F2				
5.1		(a) Vertical				
		(1) Wall (downstream and upstream)	m <sup>2</sup>	44 456	610	27 118 160
		(2) Outletworks	m <sup>2</sup>	6 210	610	3 788 100
5.2		(c) Forming of Gallery				
		(1) Horizontal	m	411	6 500	2 671 500
		(2) Sloping	m	200	8 000	1 600 000
6		SCHEDULED REINFORCEMENT ITEMS	t	1 321	8 400	11 097 240
7		SCHEDULED CONCRETE ITEMS				
7.1		Strength & Mass Concrete				
		(a) Grade 25 MPa/19 mm				
		(1) Apron (160m x 1m x 23m)	m <sup>3</sup>	3 680	1 768	6 506 240
		(2) Outlet works	m <sup>3</sup>	9 531	1 768	16 850 808
		(3) River diversion slot	m <sup>3</sup>	30 654	1 768	54 196 272
7.2		UNFORMED SURFACE FINISH				
8	8.1	Class U2 (Wood-floated) finish				
		(a) Concrete wall structure	m <sup>2</sup>	17 496	50	874 800
		(b) Apron (downstream)	m <sup>2</sup>	3 680	50	184 000
		(c) Gallery floor	m <sup>2</sup>	411	50	20 550
		(d) Outlet works	m <sup>2</sup>	324	50	16 200
9		<b>ROAD DEVIATION TO ACCOMMODATE DAM LEVEL</b>				
		(a) Road (1 300 m long x 11,4 m wide)	m <sup>2</sup>	14 820	770	11 411 400
		(b) Bridges ( 230 m long bridges x 11.4 m wide)	m <sup>2</sup>	2 622	15 000	39 330 000
<b>TOTAL CARRIED FORWARD</b>						<b>331 767 003</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
<b>TOTAL BROUGHT FORWARD</b>						<b>331 767 003</b>
10		<b>SECTION: ROLLER COMPACTED CONCRETE FOR DAMS</b>				
	10.1	Roller Compacted Concrete				
	(a)	Grade 15 MPa concrete				
	(1)	Wall	m <sup>3</sup>	477 498	950	453 623 323
	(2)	Additional for two separate wall sections	m <sup>3</sup>	477 498	100	47 749 823
	10.2	(b) Immersion Vibrated Roller Compacted Concrete (IVRCC)				
	(1)	600 mm thick, upstream	m <sup>3</sup>	13 337	1 100	14 670 401
	(2)	600 mm thick, downstream	m <sup>2</sup>	16 410	1 100	18 051 040
	10.3	RCC Bedding Mortar				
	(a)	Grade 15 MPa concrete	m <sup>2</sup>	17 496	500	8 748 000
	9.4	Test Section	No.	1	840 000	840 000
11		<b>SECTION : DRILLING &amp; GROUTING</b>				
	11.1	<b>RCC WALL</b>				
	(a)	Curtain grouting	m	18 504	850	15 728 400
	(b)	Consolidation grouting	m	4 006	850	3 405 100
	11.2	<b>EARTH EMABANKMENT</b>				
	(a)	Curtain grouting	m	10 352	850	8 799 200
	(b)	Consolidation grouting	m	1 714	850	1 456 900
12		<b>SECTION: WATERSTOPS, JOINTING AND BEARINGS</b>				
		SCHEDULED ITEMS				
	12.1	Waterstops	m	1 482	700	1 037 301
13		<b>SECTION: MECHANICAL ITEMS</b>				
	(a)	Valves and gates	Sum			6 840 000
	(b)	Cranes and hoists	Sum			2 330 000
	(c)	Structural steel screens and guides	Sum			1 712 971
	(d)	Pipe (2 x 2m steel pipe)	m	100	20 000	2 000 000
<b>TOTAL CARRIED FORWARD</b>						<b>918 759 463</b>



ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
14		<b>SITE CLEARANCE</b>				
	14.1	<u>Clear and grub</u> (a) Footprint	ha	0.05	26 546	1 327
	14.2	<u>Remove and grub large trees and tree</u> (a) over 1 m and up to and including 2 m (i) Embankment footprint	No	1	1 700	1 700
	14.3	<u>Remove topsoil to nominal depth of 300 mm</u> (a) Footprint	m <sup>3</sup>	150	21	3 150
15		<b>EXCAVATIONS AND BACKFILL FOR</b>				
	15.1	<u>Bulk Excavation</u> (a) Excavate in all materials (to stockpile or (i) Stockpile  (1) Embankment footprint (Use in rockfill)	m <sup>3</sup>	3570	35	124 950
		(b) Extra over for:				
		(i) Intermediate excavation	m <sup>3</sup>	1 071	3	3 427
		(ii) Hard rock excavation	m <sup>3</sup>	714	34	24 276
		(iii) Boulder excavation, Class A	m <sup>3</sup>	179	79	14 012
		(iv) Boulder excavation, Class B	m <sup>3</sup>	179	61	10 889
	15.2	<u>Foundation Treatment</u>				
		(a) Treatment of Joints, Cracks and	m <sup>3</sup>	510	664	338 640
		(b) Treatment of Faults, Dykes, Shear	m <sup>3</sup>	510	660	336 600
16		<u>Scheduled Reinforcement items</u> Steel				
		(a) High tensile steel 16 mm diameter and	t	169	8 400	1 417 080
17		<u>Scheduled Concrete items</u> Blinding layer and Dental Concrete				
		(b) Dental concrete (Class 15/38)	m <sup>3</sup>	474	1 869	886 467
		Strength and Mass Concrete				
		(a) Strength Concrete (Class 30/38)	m <sup>3</sup>	1 687	1 500	2 530 500
		Secondary concrete (Class 30/19)	m <sup>3</sup>	100	1 870	187 000
18		<u>Unformed Surface Finishes</u>				
		Class U2 finish	m <sup>2</sup>	2 489	29	72 181
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>5 952 199</b>

SITE A, OPTION 2  
WITH  
OUTLET TO TUNNEL

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
					RAND	
19	1-12	<b>Landscaping</b> (% of 1-9)	%	932 200 320	5	46 610 016
20	1-12	<b>Miscellaneous</b> (% of 1-9)	%	932 200 320	15	139 830 048
		<b>SUB TOTAL A</b>				1 118 640 384
21		<b>Preliminary &amp; General</b> (% of sub-total A)	%	1 118 640 384	30	335 592 115
22		<b>Preliminary works</b>				
	22.1	(a) Access road	km	5	400 000	1 840 000.00
	22.2	(b) Electrical supply to site	Sum			1 000 000
	22.3	(c) Construction water to site	Sum			300 000
	22.4	(d) Railhead & materials handling	Sum			
	22.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				1 457 672 499
23		<b>Contingencies</b> (% of sub total B)	%	1 457 672 499	10	145 767 250
		<b>SUB TOTAL C</b>				1 603 439 749
24		<b>Planning design &amp; supervision</b> (% of sub total C)	%	1 603 439 749	15	240 515 962
		<b>SUB TOTAL D</b>				1 843 955 711
25		<b>VAT</b> (% of sub total D)	%	1 843 955 711	0	0
		<b>NETT PROJECT COST</b>				1 843 955 711
26		<b>Cost of relocations</b>	Sum			
27		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				1 843 955 711

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
1	1	<b>SITE CLEARANCE</b>				
	1.2	<u>Clear and grub</u>				
		(a) Right flank footprint	ha	12.60	26 600	335 160
		(b) RCC footprint	ha	1.80	26 601	47 882
	1.3	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2 m				
		(i) Whole footprint area	No	5	1 700	8 500
	1.4	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>				
		(a) Right flank embankment	m <sup>3</sup>	38 113	21	800 373
		(b) RCC	m <sup>3</sup>	5 481	21	115 101
2	2.0	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>				
	2.1	<u>Bulk Excavation</u>				
		(a) Excavate in all materials (to stockpile or dispose)				
		(i) Stockpile				
		(1) Right flank core	m <sup>3</sup>	19071	30	572 130
		(2) RCC excavation	m <sup>3</sup>	98485	30	2 954 550
		(b) Extra over for:				
		(i) Intermediate excavation	m <sup>3</sup>	35 267	4	141 067
		(ii) Hard rock excavation	m <sup>3</sup>	23 511	34	799 381
		(iii) Boulder excavation, Class A	m <sup>3</sup>	5 878	79	464 346
	(iv) Boulder excavation, Class B	m <sup>3</sup>	954	61	58 167	
2.2	<u>Foundation Treatment</u>					
	(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	5 400	665	3 591 000	
	(b) Treatment of Faults, Dykes, Shear Zones and Zones of	m <sup>3</sup>	5 400	658	3 553 200	
<b>TOTAL CARRIED FORWARD</b>						<b>13 440 857</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
3		<b>PART 2 : RIVER DIVERSION</b>	Sum	1		15 000 000
4		<b>EMBANKMENT</b>				
		<b>SECTION: EARTHFILL DAM CONSTRUCTION</b>				
		Embankment				
4.1		(a) Trial Embankment	No			146 619
4.2		(b) Forming right flank embankment				
		(1) Earth fill	m <sup>3</sup>	1824788	46	83 940 248
		(2) Filters	m <sup>3</sup>	80232	431	34 579 992
		(3) Riprap	m <sup>3</sup>	374	351	131 274
		(4) Clay core	m <sup>3</sup>	446072	50	22 303 600
5		<b>CONCRETE STRUCTURE</b>				
		<b>SECTION: CONVENTIONAL CONCRETE FOR DAMS</b>				
		SCHEDULED FORMWORK ITEMS				
		Class F2				
5.1		(a) Vertical				
		(1) Wall (downstream and upstream)	m <sup>2</sup>	44 456	610	27 118 160
		(2) Outletworks	m <sup>2</sup>	6 210	610	3 788 100
5.2		(c) Forming of Gallery				
		(1) Horizontal	m	411	6 500	2 671 500
		(2) Sloping	m	200	8 000	1 600 000
6		SCHEDULED REINFORCEMENT ITEMS	t	1 321	8 400	11 097 240
7		SCHEDULED CONCRETE ITEMS				
7.1		Strength & Mass Concrete				
		(a) Grade 25 MPa/19 mm				
		(1) Apron (160m x 1m x 23m)	m <sup>3</sup>	3 680	1 768	6 506 240
		(2) Outlet works	m <sup>3</sup>	9 531	1 768	16 850 808
		(3) River diversion slot	m <sup>3</sup>	30 654	1 768	54 196 272
7.2		UNFORMED SURFACE FINISH				
8	8.1	Class U2 (Wood-floated) finish				
		(a) Concrete wall structure	m <sup>2</sup>	17 496	50	874 800
		(b) Apron (downstream)	m <sup>2</sup>	3 680	50	184 000
		(c) Gallery floor	m <sup>2</sup>	411	50	20 550
		(d) Outlet works	m <sup>2</sup>	324	50	16 200
9		<b>ROAD DEVIATION TO ACCOMMODATE DAM LEVEL</b>				
		(a) Road (1 300 m long x 11,4 m wide)	m <sup>2</sup>	14 820	770	11 411 400
		(b) Bridges ( 230 m long bridges x 11.4 m wide)	m <sup>2</sup>	2 622	15 000	39 330 000
<b>TOTAL CARRIED FORWARD</b>						<b>331 767 003</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
<b>TOTAL BROUGHT FORWARD</b>						<b>331 767 003</b>
10		<b>SECTION: ROLLER COMPACTED CONCRETE FOR DAMS</b>				
	10.1	Roller Compacted Concrete				
	(a)	Grade 15 MPa concrete				
	(1)	Wall	m <sup>3</sup>	477 498	950	453 623 323
	(2)	Additional for two separate wall sections	m <sup>3</sup>	477 498	100	47 749 823
	10.2	(b) Immersion Vibrated Roller Compacted Concrete (IVRCC)				
	(1)	600 mm thick, upstream	m <sup>3</sup>	13 337	1 100	14 670 401
	(2)	600 mm thick, downstream	m <sup>2</sup>	16 410	1 100	18 051 040
	10.3	RCC Bedding Mortar				
	(a)	Grade 15 MPa concrete	m <sup>2</sup>	17 496	500	8 748 000
	9.4	Test Section	No.	1	840 000	840 000
11		<b>SECTION : DRILLING &amp; GROUTING</b>				
	11.1	<b>RCC WALL</b>				
	(a)	Curtain grouting	m	18 504	850	15 728 400
	(b)	Consolidation grouting	m	4 006	850	3 405 100
	11.2	<b>EARTH EMBANKMENT</b>				
	(a)	Curtain grouting	m	10 352	850	8 799 200
	(b)	Consolidation grouting	m	1 714	850	1 456 900
12		<b>SECTION: WATERSTOPS, JOINTING AND BEARINGS</b>				
		SCHEDULED ITEMS				
	12.1	Waterstops	m	1 482	700	1 037 301
13		<b>SECTION: MECHANICAL ITEMS</b>				
	(a)	Valves and gates	Sum			6 840 000
	(b)	Cranes and hoists	Sum			2 330 000
	(c)	Structural steel screens and guides	Sum			1 712 971
	(d)	Pipe (2 x 2m steel pipe)	m	100	20 000	2 000 000
<b>TOTAL CARRIED FORWARD</b>						<b>918 759 463</b>

# **Appendix J**

## **Smithfield Dam site B, Option 1**

### **BOQ**

SITE B, OPTION 1  
with  
INLET STRUCTURE TO PUMPSTATION



No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE RAND	AMOUNT
23		<b>Landscaping</b> (% of 1-9)	%	563 852 804	5	28 192 640
24		<b>Miscellaneous</b> (% of 1-9)	%	563 852 804	15	84 577 921
		<b>SUB TOTAL A</b>				676 623 365
25		<b>Preliminary &amp; General</b> (% of sub-total A)	%	676 623 365	30	202 987 010
26		<b>Preliminary works</b>				
	26.1	(a) Access road	km	4.6	400 000	1 840 000
	26.2	(b) Electrical supply to site	Sum			1 000 000
	26.3	(c) Construction water to site	Sum			300 000
	26.4	(d) Railhead & materials handling	Sum			
	26.5	(e ) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				883 050 375
27		<b>Contingencies</b> (% of sub total B)	%	883 050 375	10	88 305 037
		<b>SUB TOTAL C</b>				971 355 412
28		<b>Planning design &amp; supervision</b> (% of sub total C)	%	971 355 412	15	145 703 312
		<b>SUB TOTAL D</b>				1 117 058 724
29		<b>VAT</b> (% of sub total D)	%	1 117 058 724	0	0
		<b>NETT PROJECT COST</b>				1 117 058 724
30		<b>Cost of relocations</b>	Sum			
31		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				1 117 058 724

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
		<b>STAGE 1</b>				
1		<b>SITE CLEARANCE</b>				
	1.1	Clear and grub				
		(a) Portal footprints	ha	1.5	26 546	39 819
	1.2	Remove and grub large trees and tree stumps of girth				
		(a) over 1 m and up to and including 2m	No	2	1 700	3 400
	1.3	Remove topsoil to nominal depth of 150 mm and stockpile	m <sup>3</sup>	4525	20	90 500
2		<b>EXCAVATION AND BACKFILL FOR DAMS AND WATERWAYS</b>				
		Bulk Excavation				
	2.1	<b>Inlet portal</b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	20 564	21	431 844
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	5 141	3	16 965
		(ii) Hard Rock	m <sup>3</sup>	5 141	34	174 794
		(iii) Boulder, Class A	m <sup>3</sup>	2 056	78	160 399
		(iv) Boulder, Class B	m <sup>3</sup>	1 028	61	62 720
	2.2	<b>Outlet Portal</b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	170 633	21	3 583 293
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	42 658	3	140 772
		(ii) Hard Rock	m <sup>3</sup>	42 658	34	1 450 381
		(iii) Boulder, Class A	m <sup>3</sup>	25 595	78	1 996 406
		(iv) Boulder, Class B	m <sup>3</sup>	8 532	61	520 431
	2.3	Dewatering	Sum	1	100 000	100 000
		<b>STAGE 2</b>				
3		<b>SITE CLEARANCE</b>				
	3.1	Clear and grub				
		(a) Embankment footprint	ha	0.5	26 546	13 273
	3.2	Remove and grub large trees and tree stumps of girth				
		(a) over 1 m and up to and including 2 m	No	2	1 700	3 400
<b>TOTAL CARRIED FORWARD</b>						<b>8 788 397</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>8 788 397</b>
4		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>				
		(a) Excavate all materials				
		(i) Topsoil at Upstream & Downstream cofferdam	m <sup>3</sup>	1 638	21	34 398
5		<b>EMBANKMENT CONSTRUCTION</b>				
		Earthfill Upstream & Downstream Cofferdam Construction.				
		Forming Embankment				
	5.1	Using material from designated borrow areas or commercial sources				
		(4) Homogeneous Material	m <sup>3</sup>	25269	50	1 263 450
6		<b>TUNNEL CONSTRUCTION</b>				
	6.1	<b>TUNNEL EXCAVATION</b>				
		(a) Tunnel (Rock class II)	m <sup>3</sup>	37 186	2 051	76 268 896
	6.2	<b>ROCK SUPPORT</b>				
		(a) Rockbolts	m	15 768	37	577 314
		(b) Shotcrete	m <sup>3</sup>	756	2 500	1 891 023
		(c) Reinforcing mesh	m <sup>2</sup>	4 920	26	127 913
	6.3	<b>DEWATERING</b>	Sum	1	550 000	550 000
		<b>STAGE 3</b>				
		<b>MEDIUM PRESSURE PIPELINES</b>				
7		Supply, lay, and bed pipes complete with couplings				
		(a) 500 mm diameter concrete pipe (class 75D) in concrete	m	324	80.00	25 920
		(b) Water control in tunnel	Prov Sum	1	100 000	100 000
8		<b>PLUG OF TUNNEL</b>				
	8.1	<u>Scheduled Formwork items</u>				
		Class F1				
		(a) Vertical formwork	m <sup>2</sup>	310	550	170 500
	8.2	<u>Scheduled Concrete items</u>				
		Strength and Mass concrete				
		(a) Sealing of bulkheads shaft with mass concrete 25 Mpa/19	m <sup>3</sup>	1 050	1 100	1 155 000
		(c) Plug 25 MPa/19 mm	m <sup>3</sup>	708	1 100	778 250
	8.3	<u>Joints</u>				
		(e) Swellable water stops	m	30	500	15 000
	8.4	<u>Miscellaneous and Sundry items</u>				
		(a) Bulkheads incl reinforcement at 120 kg/m <sup>3</sup>	No	240	3 000	720 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>92 466 061</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
9	SANS 1200 C	<b>SITE CLEARANCE</b>					
		9.1	<u>Clear and grub</u>				
			(a) Main embankment footprint	ha	8.40	26 546	222 986
			(b) Spillway	ha	14.70	13 635	200 435
			(d) Saddle embankment footprint	ha	3.40	26 546	90 256
		9.2	<u>Remove and grub large trees and tree stumps of girth</u>				
			(a) over 1 m and up to and including 2 m				
			(i) Embankment footprint (Main & Saddle)	No	7	1 700	11 900
			(ii) Spillway	No	2	1 700	3 400
		9.3	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>				
			(a) Embankment footprint (Main & Saddle)	m <sup>3</sup>	42 638	21	895 398
	(b) Spillway	m <sup>3</sup>	44 160	16	706 560		
10		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b>					
		10.1	<u>Bulk Excavation</u>				
			(a) Excavate in all materials (to stockpile or dispose)				
			(i) Stockpile				
			(1) Embankment footprint (Use in rockfill)	m <sup>3</sup>	0	35	0
			(2) Spillway (Use in Rockfill)	m <sup>3</sup>	0	31	0
			(3) Outlet works (Use in Rockfill)	m <sup>3</sup>	0	35	0
		10.2	(b) Extra over for:				
			(i) Intermediate excavation	m <sup>3</sup>	0	3	0
			(ii) Hard rock excavation	m <sup>3</sup>	0	34	0
			(iii) Boulder excavation, Class A	m <sup>3</sup>	0	79	0
	(iv) Boulder excavation, Class B	m <sup>3</sup>	0	61	0		
10.3	<u>Foundation Treatment</u>						
	(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	10 296	664	4 864 464		
	(b) Treatment of Faults, Dykes, Shear Zones and Zones of	m <sup>3</sup>	10 296	660	4 835 160		
<b>TOTAL CARRIED FORWARD</b>						<b>11 830 559</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
11	P21	<b>EMBANKMENT CONSTRUCTION</b>				
	11.1	<u>Forming Embankment</u> Using material from designated borrow areas Main embankment				
		(1) Rockfill	m <sup>3</sup>	1 417 432	71	100 637 672
		(2) Clay Core	m <sup>3</sup>	294 356	50	14 717 800
		(3) Filter	m <sup>3</sup>	86 534	450	38 940 300
		Saddle embankment				
		(1) Rockfill	m <sup>3</sup>	160 782	71	11 415 522
		(2) Clay Core	m <sup>3</sup>	47 931	50	2 396 550
		(3) Filter	m <sup>3</sup>	41 864	450	18 838 800
	11.2	Rockfill trial (test) Embankment size as per specification	No	1	147 000	147 000
		Overhaul (Clay for 10 km)	m <sup>3</sup> .km	17 114	3	51 343
12		<b>SECTION : DRILLING &amp; GROUTING</b>				
	12.1	<b>Main embankment</b>				
		(a) Curtain grouting	m	8 464	850	7 194 400
		(b) Consolidation grouting	m	2 820	850	2 397 000
	12.2	<b>Saddle Embankment</b>				
		(a) Curtain grouting	m	2 687	850	2 283 950
		(b) Consolidation grouting	m	1 845	850	1 568 250
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>200 588 587</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
14	14.1	<u>Scheduled Formwork items</u>					
		Class F4					
		(a) Vertical					
		(1) Spillway	m <sup>2</sup>	8 736	530	4 630 080	
		(2) Transfer structure to pumpstation	m <sup>2</sup>	6 804	550	3 742 200	
		(b) Sloped					
		(1) Ogee of spillway	m <sup>2</sup>	1 328	581	771 568	
		(c) Sloping					
		(1) Stilling basin blocks	m <sup>2</sup>	33	581	19 173	
		(d) Horizontal	m <sup>2</sup>	352	581	204 512	
		Keyways on contraction joints					
	(a) Bridges dimensions to be given in detail design	m	20	100	2 000		
	14.2	<u>Scheduled Reinforcement items</u>	t	4 737	8 400	39 792 480	
	14.3	<u>Anchors</u>					
		Anchor bars (Y32 @ 2.5 m x 2 m)	t	108	8 500	920 377	
	14.4	<u>Scheduled Concrete items</u>					
		Strength & Mass Concrete					
	(a) Grade 25 MPa/19 mm						
	(1) Spillway, bridges and retaining wall	m <sup>3</sup>	36 611	1 500	54 916 500		
	(2) Transfer intake to pumpstation	m <sup>3</sup>	28 628	1 500	42 942 000		
		Secondary Concrete					
	(a) Grade 25 MPa/19 mm	m <sup>3</sup>	200	1 800	360 000		
	14.5	<u>Unformed Surface Finishes</u>					
	Class U2 (Wood-floated) finish						
(a) Top of chute	m <sup>2</sup>	468	23	10 764			
(b) Top of bridges	m <sup>2</sup>	197	23	4 531			
(c) Chute and Stilling basin floor	m <sup>2</sup>	34 320	23	789 360			
(d) Transfer intake	m <sup>2</sup>	862	25	21 540			
15		<b>MECHANICAL ITEMS</b>					
	(a) Valves and gates	Sum			6 840 000		
	(b) Cranes & Hoists	Sum			2 330 000		
	(c) Structural steelwork	Sum			1 712 971		
<b>TOTAL CARRIED FORWARD</b>						<b>160 010 056</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>160 010 056</b>
<b>16</b>		<b>WATERSTOPS, JOINTING AND BEARINGS</b>				
		<u>Scheduled items</u>				
	16.1	Waterstops				
		(a) 250 mm Centre bulb PVC waterstop	m	1 799	630	1 133 496
	16.2	Joint sealants				
		(a) Chute wall - 12mm expanding cork	m	1 799	10	17 992
		(b) Chute wall - 12m Impregnated Bitumen Fibre board	m	1 799	10	17 992
		(c) Chute wall - 12 x 12 mm Polysulphide sealant	m	1 799	10	17 992
<b>17</b>		<b>SUB-SOIL DRAINAGE</b>				
		<u>Scheduled items</u>				
	17.1	Excavation for sub-soil drainage system				
		(a) Excavating soft material situated within the following depth ranges below the surface level:				
		(i) 0 m to 1,5 m	m <sup>3</sup>	429	21	9 009
		(b) Extra over sub-item (a), irrespective of depth, for:				
		(ii) Excavation in hard material	m <sup>3</sup>	215	4	858
	17.2	Natural permeable material in sub-soil drainage systems				
		(b) Sand as specified on detail drawings	m <sup>3</sup>	412	550	226 512
	17.3	Pipes in sub-soil drainage system				
		(c) 110 NB, Class 6, HDPE pressure pipe, non perforated, complying with SANS 533, Part II	m	1 716	400	686 400
		(d) 75 NB, flexible slotted drainage pipes with smooth bore, "Drainex" or equivalent by Kaytech	m	520	330	171 600
	17.4	Caps to higher ends of sub-surface drain pipes				
		(a) High end of pipes of Drainex pipes	No	26	50	1 300
	17.5	Concrete outlet structures for sub-soil drainage systems complete as per drawings				
		(a) Concrete 1500 mm dia	No	8	600	4 800
		Overhaul for material hauled in excess of 1.0 km freehaul				
		(a) Sand for filter material (10 km)	m <sup>3</sup> .km	4 118	3	12 355
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>162 310 362</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
18	18.1	<b>SITE CLEARANCE</b> <u>Clear and grub</u> (a) Footprint	ha	0.20	26 546	5 309
	18.2	<u>Remove and grub large trees and tree stumps of</u> (a) over 1 m and up to and including 2 m  (i) Footprint	No	1	1 700	1 700
	18.3	Remove topsoil to nominal depth of 300 mm and (a) Footprint	m <sup>3</sup>	600	21	12 600
19	19.1	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b> Bulk Excavation  (a) Excavate in all materials (to stockpile or  (i) Stockpile  (1) Embankment footprint	m <sup>3</sup>	46400	35	1 624 000
		(b) Extra over for:  (i) Intermediate excavation	m <sup>3</sup>	13 920	3	44 544
		(ii) Hard rock excavation	m <sup>3</sup>	9 280	34	315 520
		(iii) Boulder excavation, Class A	m <sup>3</sup>	2 320	79	182 120
		(iv) Boulder excavation, Class B	m <sup>3</sup>	2 320	61	141 520
	19.2	<u>Foundation Treatment</u> (a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	600	664	398 400
		(b) Treatment of Faults, Dykes, Shear Zones and	m <sup>3</sup>	600	660	398 400
20		<u>Scheduled Reinforcement items</u> Steel  (a) High tensile steel 16 mm diameter and over	t	3 430	8 400	28 809 984
21	21.1	<u>Scheduled Concrete items</u> Blinding layer and Dental Concrete  (b) Dental concrete (Class 15/38)	m <sup>3</sup>	100	1 869	186 900
	21.2	Strength and Mass Concrete (a) Strength Concrete (Class 30/38)	m <sup>3</sup>	42 872	1 500	64 308 000
	21.3	Secondary concrete (Class 30/19)	m <sup>3</sup>	100	1 870	187 000
22		<u>Unformed Surface Finishes</u> Class U2 finish	m <sup>2</sup>	1 422	29	41 238
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>96 657 235</b>



SITE B, OPTION 1  
with  
INLET STRUCTURE TO TUNNEL

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE RAND	AMOUNT
18		<b>Landscaping</b> (% of 1-9)	%	471 859 003	5	23 592 950
19		<b>Miscellaneous</b> (% of 1-9)	%	471 859 003	15	70 778 850
		<b>SUB TOTAL A</b>				566 230 804
20		<b>Preliminary &amp; General</b> (% of sub-total A)	%	566 230 804	30	169 869 241
21		<b>Preliminary works</b>				
	21.1	(a) Access road	km	4.6	400 000	1 840 000
	21.2	(b) Electrical supply to site	Sum			1 000 000
	21.3	(c) Construction water to site	Sum			300 000
	21.4	(d) Railhead & materials handling	Sum			
	21.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				739 540 045
22		<b>Contingencies</b> (% of sub total B)	%	739 540 045	10	73 954 004
		<b>SUB TOTAL C</b>				813 494 049
23		<b>Planning design &amp; supervision</b> (% of sub total C)	%	813 494 049	15	122 024 107
		<b>SUB TOTAL D</b>				935 518 157
24		<b>VAT</b> (% of sub total D)	%	935 518 157	0	0
		<b>NETT PROJECT COST</b>				935 518 157
25		<b>Cost of relocations</b>	Sum			
26		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				935 518 157

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
		<b>STAGE 1</b>				
1		<b>SITE CLEARANCE</b>				
	1.1	<u>Clear and grub</u>				
		(a) Portal footprints	ha	1.5	26 546	39 819
	1.2	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2m	No	2	1 700	3 400
	1.3	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>	m <sup>3</sup>	4525	20	90 500
2		Bulk Excavation				
	2.1	<b><u>Inlet portal</u></b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	20 564	21	431 844
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	5 141	3	16 965
		(ii) Hard Rock	m <sup>3</sup>	5 141	34	174 794
		(iii) Boulder, Class A	m <sup>3</sup>	2 056	78	160 399
		(iv) Boulder, Class B	m <sup>3</sup>	1 028	61	62 720
	2.2	<b><u>Outlet Portal</u></b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	170 633	21	3 583 293
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	42 658	3	140 772
		(ii) Hard Rock	m <sup>3</sup>	42 658	34	1 450 381
		(iii) Boulder, Class A	m <sup>3</sup>	25 595	78	1 996 406
		(iv) Boulder, Class B	m <sup>3</sup>	8 532	61	520 431
	2.3	<b><u>Dewatering</u></b>	Sum	1	100 000	100 000
		<b>STAGE 2</b>				
3		<b>SITE CLEARANCE</b>				
	3.1	<u>Clear and grub</u>				
		(a) Embankment footprint	ha	0.5	26 546	13 273
	3.2	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2 m	No	2	1 700	3 400
<b>TOTAL CARRIED FORWARD</b>						<b>8 788 397</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>8 788 397</b>
4		(a) Excavate all materials (i) Topsoil at Upstream & Downstream cofferdam	m <sup>3</sup>	1 638	21	34 398
5		<b>EMBANKMENT CONSTRUCTION</b> Earthfill Upstream & Downstream Cofferdam Construction. Forming Embankment				
		(4) Homogeneous Material	m <sup>3</sup>	25269	50	1 263 450
6		<b>TUNNEL CONSTRUCTION</b>				
	6.1	<b>TUNNEL EXCAVATION</b>				
		(a) Tunnel (Rock class II)	m <sup>3</sup>	37 186	2 051	76 268 896
	6.2	<b>ROCK SUPPORT</b>				
		(a) Rockbolts	m	15 768	37	577 314
		(b) Shotcrete	m <sup>3</sup>	756	2 500	1 891 023
		(c) Reinforcing mesh	m <sup>2</sup>	4 920	26	127 913
	6.3	<b>DEWATERING</b>	Sum	1	550 000	550 000
<b>STAGE 3</b>						
7		<b>MEDIUM PRESSURE PIPELINES</b> Supply, lay, and bed pipes complete with couplings				
		(a) 500 mm diameter concrete pipe (class 75D) in concrete	m	324	80.00	25 920
		(b) Water control in tunnel	Prov Sum	1	100 000	100 000
<b>CONVENTIONAL CONCRETE FOR DAMS</b>						
8		<b>PLUG OF TUNNEL</b>				
	8.1	<u>Scheduled Formwork items</u>  Class F1				
		(a) Vertical formwork	m <sup>2</sup>	310	550	170 500
	8.2	<u>Scheduled Concrete items</u> Strength and Mass concrete				
		(a) Sealing of bulkheads shaft with mass concrete 25 Mpa/19	m <sup>3</sup>	1 050	1 100	1 155 000
		(c) Plug 25 MPa/19 mm	m <sup>3</sup>	708	1 100	778 250
	8.3	<u>Joints</u>				
		(e) Swellable water stops	m	30	500	15 000
	8.4	<u>Miscellaneous and Sundry items</u>				
		(a) Bulkheads incl reinforcement at 120 kg/m <sup>3</sup>	No	240	3 000	720 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>92 466 061</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
8		<b>SITE CLEARANCE</b>				
	8.1	<u>Clear and grub</u>				
		(a) Main embankment footprint	ha	8.40	26 546	222 986
		(b) Spillway	ha	14.70	13 635	200 435
		(d) Saddle embankment footprint	ha	3.40	26 546	90 256
	8.2	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2 m				
		(i) Embankment footprint (Main & Saddle)	No	7	1 700	11 900
		(ii) Spillway	No	2	1 700	3 400
	8.3	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>				
		(a) Embankment footprint (Main & Saddle)	m <sup>3</sup>	42 638	21	895 398
		(b) Spillway	m <sup>3</sup>	44 160	16	706 560
9		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b>				
	9.1	<u>Bulk Excavation</u>				
		(a) Excavate in all materials (to stockpile or dispose)				
		(i) Stockpile				
		(1) Embankment footprint (Use in rockfill)	m <sup>3</sup>	0	35	0
		(2) Spillway (Use in Rockfill)	m <sup>3</sup>	0	31	0
		(3) Outlet works (Use in Rockfill)	m <sup>3</sup>	0	35	0
		(b) Extra over for:				
		(i) Intermediate excavation	m <sup>3</sup>	0	3	0
		(ii) Hard rock excavation	m <sup>3</sup>	0	34	0
		(iii) Boulder excavation, Class A	m <sup>3</sup>	0	79	0
		(iv) Boulder excavation, Class B	m <sup>3</sup>	0	61	0
10		<b>FOUNDATION TREATMENT</b>				
		(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	10 296	664	4 864 464
		(b) Treatment of Faults, Dykes, Shear Zones and Zones of	m <sup>3</sup>	10 296	660	4 835 160
<b>TOTAL CARRIED FORWARD</b>						<b>11 830 559</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
11	11.1	<b>EMBANKMENT CONSTRUCTION</b>					
		<u>Forming Embankment</u>					
		Using material from designated borrow areas					
		Main embankment					
		(1) Rockfill	m <sup>3</sup>	1 417 432	71	100 637 672	
		(2) Clay Core	m <sup>3</sup>	294 356	50	14 717 800	
		(3) Filter	m <sup>3</sup>	86 534	450	38 940 300	
		Saddle embankment					
		(1) Rockfill	m <sup>3</sup>	160 782	71	11 415 522	
		(2) Clay Core	m <sup>3</sup>	47 931	50	2 396 550	
		(3) Filter	m <sup>3</sup>	41 864	450	18 838 800	
11	11.2	<u>Rockfill trial (test) Embankment size as per specification</u>	No	1	147 000	147 000	
		<u>Overhaul (Clay for 10 km)</u>	m <sup>3</sup> .km	17 114	3	51 343	
12	12.1	<b>SECTION : DRILLING &amp; GROUTING</b>					
		<b>Main embankment</b>					
		(a) Curtain grouting	m	8 464	850	7 194 400	
		(b) Consolidation grouting	m	2 820	850	2 397 000	
		12.2	<b>Saddle Embankment</b>				
			(a) Curtain grouting	m	2 687	850	2 283 950
		(b) Consolidation grouting	m	1 845	850	1 568 250	
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>200 588 587</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
13	13.1	<b>CONVENTIONAL CONCRETE FOR DAMS</b>					
		<u>Scheduled Formwork items</u>					
		Class F4					
		(a) Vertical					
		(1) Spillway	m <sup>2</sup>	8 736	530	4 630 080	
		(2) Transfer structure to tunnels	m <sup>2</sup>	6 804	550	3 742 200	
		(b) Sloped					
		(1) Ogee of spillway	m <sup>2</sup>	1 328	581	771 568	
		(2) Round	m <sup>2</sup>	2 337	581	1 357 797	
		(c) Sloping					
		(1) Stilling basin blocks	m <sup>2</sup>	33	581	19 173	
		(d) Horizontal	m <sup>2</sup>	352	581	204 512	
		13.2	Keyways on contraction joints				
		(a) Bridges dimensions to be given in detail design	m	20	100	2 000	
		13.3	<u>Scheduled Reinforcement items</u>	t	4 878	8 400	40 978 392
		13.4	<u>Anchors</u>				
			Anchor bars (Y32 @ 2.5 m x 2 m)	t	108	8 500	920 377
		13.5	<u>Scheduled Concrete items</u>				
			Strength & Mass Concrete				
		(a) Grade 25 MPa/19 mm					
(1) Spillway, bridges and retaining wall	m <sup>3</sup>	36 611	1 500	54 916 500			
(2) Transfer intake to tunnel	m <sup>3</sup>	30 040	1 500	45 059 700			
13.6	Secondary Concrete						
(a) Grade 25 MPa/19 mm	m <sup>3</sup>	200	1 800	360 000			
13.7	<u>Unformed Surface Finishes</u>						
	Class U2 (Wood-floated) finish						
(a) Top of chute	m <sup>2</sup>	468	23	10 764			
(b) Top of bridges	m <sup>2</sup>	197	23	4 531			
(c) Chute and Stilling basin floor	m <sup>2</sup>	34 320	23	789 360			
(d) Transfer intake	m <sup>2</sup>	943	25	23 565			
15		<b>MECHANICAL ITEMS</b>					
		(a) Valves and gates	Sum			6 840 000	
		(b) Cranes & Hoists	Sum			2 330 000	
	(c) Structural steelwork	Sum			1 712 971		
<b>TOTAL CARRIED FORWARD</b>						<b>164 673 490</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>164 673 490</b>
<b>16</b>		<b>WATERSTOPS, JOINTING AND BEARINGS</b>				
		<u>Scheduled items</u>				
	16.1	Waterstops				
		(a) 250 mm Centre bulb PVC waterstop	m	1 799	630	1 133 496
	16.2	Joint sealants				
		(a) Chute wall - 12mm expanding cork	m	1 799	10	17 992
		(b) Chute wall - 12m Impregnated Bitumen Fibre board	m	1 799	10	17 992
		(c) Chute wall - 12 x 12 mm Polysulphide sealant	m	1 799	10	17 992
<b>17</b>		<b>SUB-SOIL DRAINAGE</b>				
		<u>Scheduled items</u>				
	17.1	Excavation for sub-soil drainage system				
		(a) Excavating soft material situated within the following depth ranges below the surface level:				
		(i) 0 m to 1,5 m	m <sup>3</sup>	429	21	9 009
		(b) Extra over sub-item (a), irrespective of depth, for:				
		(ii) Excavation in hard material	m <sup>3</sup>	215	4	858
	17.2	Natural permeable material in sub-soil drainage systems				
		(b) Sand as specified on detail drawings	m <sup>3</sup>	412	550	226 512
	17.3	Pipes in sub-soil drainage system				
		(c) 110 NB, Class 6, HDPE pressure pipe, non perforated, complying with SANS 533, Part II	m	1 716	400	686 400
		(d) 75 NB, flexible slotted drainage pipes with smooth bore, "Drainex" or equivalent by Kaytech	m	520	330	171 600
	17.4	Caps to higher ends of sub-surface drain pipes				
		(a) High end of pipes of Drainex pipes	No	26	50	1 300
	17.5	Concrete outlet structures for sub-soil drainage systems complete as per drawings				
		(a) Concrete 1500 mm dia	No	8	600	4 800
	17.6	Overhaul for material hauled in excess of 1.0 km freehaul				
		(a) Sand for filter material (10 km)	m <sup>3</sup> .km	4 118	3	12 355
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>166 973 796</b>



SITE B, OPTION 3  
with  
INLET STRUCTURE TO PUMPSTATION

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
					RAND	
23		<b>Landscaping</b> (% of 1-9)	%	504 046 829	5	25 202 341
24		<b>Miscellaneous</b> (% of 1-9)	%	504 046 829	15	75 607 024
		<b>SUB TOTAL A</b>				604 856 195
25		<b>Preliminary &amp; General</b> (% of sub-total A)	%	604 856 195	30	181 456 858
26		<b>Preliminary works</b>				
	26.1	(a) Access road	km	5	400 000	1 840 000.00
	26.2	(b) Electrical supply to site	Sum			1 000 000
	26.3	(c) Construction water to site	Sum			300 000
	26.4	(d) Railhead & materials handling	Sum			
	26.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				789 753 053
27		<b>Contingencies</b> (% of sub total B)	%	789 753 053	10	78 975 305
		<b>SUB TOTAL C</b>				868 728 359
28		<b>Planning design &amp; supervision</b> (% of sub total C)	%	868 728 359	15	130 309 254
		<b>SUB TOTAL D</b>				999 037 613
29		<b>VAT</b> (% of sub total D)	%	999 037 613	0	0
		<b>NETT PROJECT COST</b>				999 037 613
30		<b>Cost of relocations</b>	Sum			
31		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				999 037 613

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
		<b>STAGE 1</b>				
1		<b>SITE CLEARANCE</b>				
	1.1	<u>Clear and grub</u>				
		(a) Portal footprints	ha	1.5	26 546	39 819
	1.2	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2m	No	2	1 700	3 400
	1.3	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>	m <sup>3</sup>	4525	20	90 500
2		<b>EXCAVATION AND BACKFILL FOR DAMS AND WATERWAYS</b>				
		Bulk Excavation				
	2.1	<b><u>Inlet portal</u></b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	20 564	21	431 844
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	5 141	3	16 965
		(ii) Hard Rock	m <sup>3</sup>	5 141	34	174 794
		(iii) Boulder, Class A	m <sup>3</sup>	2 056	78	160 399
		(iv) Boulder, Class B	m <sup>3</sup>	1 028	61	62 720
	2.2	<b><u>Outlet Portal</u></b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	170 633	21	3 583 293
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	42 658	3	140 772
		(ii) Hard Rock	m <sup>3</sup>	42 658	34	1 450 381
		(iii) Boulder, Class A	m <sup>3</sup>	25 595	78	1 996 406
		(iv) Boulder, Class B	m <sup>3</sup>	8 532	61	520 431
	2.3	<b><u>Dewatering</u></b>	Sum	1	100 000	100 000
		<b>STAGE 2</b>				
3		<b>SITE CLEARANCE</b>				
	3.1	<u>Clear and grub</u>				
		(a) Embankment footprint	ha	0.5	26 546	13 273
	3.2	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2 m	No	2	1 700.00	3 400
<b>TOTAL CARRIED FORWARD</b>						<b>8 788 397</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>8 788 397</b>
4		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b>				
		(a) Excavate all materials				
		(i) Topsoil at Upstream & Downstream cofferdam	m <sup>3</sup>	1 638	21	34 398
5		<b>EMBANKMENT CONSTRUCTION</b>				
		Earthfill Upstream & Downstream Cofferdam Construction.				
		Forming Embankment				
		Using material from designated borrow areas or commercial sources				
		(4) Homogeneous Material	m <sup>3</sup>	25269	50	1 263 450
6		<b>TUNNEL CONSTRUCTION</b>				
	6.1	<b>TUNNEL EXCAVATION</b>				
		(a) Tunnel (Rock class II)	m <sup>3</sup>	37 186	2 051	76 268 896
	6.2	<b>ROCK SUPPORT</b>				
		(a) Rockbolts	m	15 768	37	577 314
		(b) Shotcrete	m <sup>3</sup>	756	2 500	1 891 023
		(c) Reinforcing mesh	m <sup>2</sup>	4 920	26	127 913
	6.3	<b>DEWATERING</b>	Sum	1	550 000	550 000
		<b>STAGE 3</b>				
7		<b>MEDIUM PRESSURE PIPELINES</b>				
		Supply, lay, and bed pipes complete with couplings				
		(a) 500 mm diameter concrete pipe (class 75D) in concrete	m	324	80	25 920
		(b) Water control in tunnel	Prov Sum	1	100 000	100 000
8		<b>PLUG OF TUNNEL</b>				
	8.1	<u>Scheduled Formwork items</u>				
		Class F1				
		(a) Vertical formwork	m <sup>2</sup>	310	550	170 500
	8.2	<u>Scheduled Concrete items</u>				
		Strength and Mass concrete				
		(a) Sealing of bulkheads shaft with mass concrete 25 Mpa/19 mm	m <sup>3</sup>	1 050	1 100	1 155 000
		(c) Plug 25 MPa/19 mm	m <sup>3</sup>	708	1 100	778 250
	8.3	<u>Joints</u>				
		(e) Swellable water stops	m	30	500	15 000
	8.4	<u>Miscellaneous and Sundry items</u>				
		(a) Bulkheads incl reinforcement at 120 kg/m <sup>3</sup>	No	240	3 000	720 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>92 466 061</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
9	9.1	<b>SITE CLEARANCE</b>					
		<u>Clear and grub</u>					
		(a) Main embankment footprint	ha	8.40	26 546	222 986	
		(b) Spillway	ha	18.90	13 635	257 702	
		(c) Outlet Works	ha	0.20	13 635	2 727	
	(d) Saddle embankment footprint	ha	3.40	26 546	90 256		
	9.2	<u>Remove and grub large trees and tree stumps of girth</u>					
		(a) over 1 m and up to and including 2 m					
		(i) Embankment footprint (Main & Saddle)	No	7	1 700	11 900	
		(ii) Spillway	No	5	1 700	8 500	
	9.3	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>	(iii) Outlet works	No	2	1 700	3 400
			(a) Embankment footprint (Main & Saddle)	m <sup>3</sup>	42 638	21	895 398.00
			(b) Spillway	m <sup>3</sup>	57 288	16	916 608.00
			(c) Outlet/Inlet works	m <sup>3</sup>	750	21	15 750.00
10	10.1	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b>					
		<u>Bulk Excavation</u>					
		(a) Excavate in all materials (to stockpile or dispose)					
		(i) Stockpile					
		(1) Embankment footprint (Use in rockfill)	m <sup>3</sup>	0	35.00	0.00	
		(2) Spillway (Use in Rockfill)	m <sup>3</sup>	0	31.00	0.00	
		(3) Outlet works (Use in Rockfill)	m <sup>3</sup>	0	35.00	0.00	
		(b) Extra over for:					
		(i) Intermediate excavation	m <sup>3</sup>	0	3.20	0.00	
		(ii) Hard rock excavation	m <sup>3</sup>	0	34.00	0.00	
		(iii) Boulder excavation, Class A	m <sup>3</sup>	0	78.50	0.00	
		(iv) Boulder excavation, Class B	m <sup>3</sup>	0	61.00	0.00	
		11		<b>FOUNDATION TREATMENT</b>			
(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>			1 881	664	1 248 984	
(b) Treatment of Faults, Dykes, Shear Zones and Zones of	m <sup>3</sup>			1 881	660	1 241 460	
<b>TOTAL CARRIED FORWARD</b>						<b>4 915 671</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
12	12.1	<b>EMBANKMENT CONSTRUCTION</b>					
		<u>Forming Embankment</u>					
		Using material from designated borrow areas					
		Main embankment					
		(1) Rockfill	m <sup>3</sup>	1 417 432	71	100 637 672	
		(2) Clay Core	m <sup>3</sup>	294 356	50	14 717 800	
		(3) Filter	m <sup>3</sup>	86 534	450	38 940 300	
		Saddle embankment					
		(1) Rockfill	m <sup>3</sup>	160 782	71	11 415 522	
		(2) Clay Core	m <sup>3</sup>	47 931	50	2 396 550	
(3) Filter	m <sup>3</sup>	41 864	450	18 838 800			
12.2		<u>Rockfill trial (test) Embankment size as per specification</u>	No	1	147 000	147 000	
12.3		<u>Overhaul (Clay for 10 km)</u>	m <sup>3</sup> .km	17 114	3	51 343	
12.4		<u>Overhaul (Rockfill frm spillway 1km)</u>	m <sup>3</sup> km	1 417 432	3	4 252 296	
13	13.1	<b>SECTION : DRILLING &amp; GROUTING</b>					
		<b>Main embankment</b>					
		(a) Curtain grouting	m	8 464	850	7 194 400	
		(b) Consolidation grouting	m	2 820	850	2 397 000	
		13.2	<b>Saddle Embankment</b>				
			(a) Curtain grouting	m	2 687	850	2 283 950
		(b) Consolidation grouting	m	1 845	850	1 568 250	
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>204 840 883</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
14	14.1	<b>CONVENTIONAL CONCRETE FOR DAMS</b>					
		<u>Scheduled Formwork items</u>					
		Class F4					
		(a) Vertical					
		(1) Spillway	m <sup>2</sup>	1 444	530	765 320	
		(2) Transfer structure to tunnels	m <sup>2</sup>	6 804	550	3 742 200	
		(b) Sloped					
		(1) Ogee of spillway	m <sup>2</sup>	1 328	581	771 568	
		(c) Sloping					
		(1) Stilling basin blocks	m <sup>2</sup>	33	581	19 173	
		(d) Horizontal	m <sup>2</sup>	352	581	204 512	
		14.2	<u>Keyways on contraction joints</u>				
		(a) Bridges dimensions to be given in detail design	m	20	100	2 000	
		14.3	<u>Scheduled Reinforcement items</u>	t	3 410	8 400	28 643 160
		14.4	<u>Anchors</u>				
		Anchor bars (Y32 @ 2.5 m x 2 m)	t	20	8 500	168 146	
		14.5	<u>Scheduled Concrete items</u>				
		Strength & Mass Concrete					
		(a) Grade 25 MPa/19 mm					
		(1) Spillway, bridges and retaining wall	m <sup>3</sup>	10 713	1 500	16 069 500	
(2) Transfer intake to pumpstation	m <sup>3</sup>	28 628	1 500	42 942 000			
Secondary Concrete							
(a) Grade 25 MPa/19 mm	m <sup>3</sup>	200	1 800	360 000			
14.6	<u>Unformed Surface Finishes</u>						
Class U2 (Wood-floated) finish							
(a) Top of chute	m <sup>2</sup>	86	23	1 967			
(b) Top of bridges	m <sup>2</sup>	197	23	4 531			
(c) Chute and Stilling basin floor	m <sup>2</sup>	6 270	23	144 210			
(d) Transfer intake	m <sup>2</sup>	862	25	21 550			
15		<b>MECHANICAL ITEMS</b>					
		(a) Valves and gates	Sum			6 840 000	
		(b) Cranes & Hoists	Sum			2 330 000	
		(c) Structural steelwork	Sum			1 712 971	
<b>TOTAL CARRIED FORWARD</b>						<b>104 742 807</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>104 742 807.23</b>
16		<b>WATERSTOPS, JOINTING AND BEARINGS</b>				
	16.1	<u>Scheduled items</u>				
		Waterstops				
		(a) 250 mm Centre bulb PVC waterstop	m	329	630	207 081
		Joint sealants				
		(a) Chute wall - 12mm expanding cork	m	329	10	3 287
		(b) Chute wall - 12m Impregnated Bitumen Fibre board	m	329	10	3 287
		(c) Chute wall - 12 x 12 mm Polysulphide sealant	m	329	10	3 287
17		<b>SUB-SOIL DRAINAGE</b>				
		<u>Scheduled items</u>				
	17.1	Excavation for sub-soil drainage system				
		(a) Excavating soft material situated within the following depth ranges below the surface level:				
		(i) 0 m to 1,5 m	m <sup>3</sup>	78	21	1 646
		(b) Extra over sub-item (a), irrespective of depth, for:				
		(ii) Excavation in hard material	m <sup>3</sup>	39	4	157
	17.2	Natural permeable material in sub-soil drainage systems				
		(b) Sand as specified on detail drawings	m <sup>3</sup>	75	550	41 382
	17.3	Pipes in sub-soil drainage system				
		(c) 110 NB, Class 6, HDPE pressure pipe, non perforated, complying with SANS 533, Part II	m	314	400	125 400
		(d) 75 NB, flexible slotted drainage pipes with smooth bore, "Drainex" or equivalent by Kaytech	m	95	330	31 350
	17.4	Caps to higher ends of sub-surface drain pipes				
		(a) High end of pipes of Drainex pipes	No	5	50	238
	17.5	Concrete outlet structures for sub-soil drainage systems complete as per drawings				
		(a) Concrete 1500 mm dia	No	8	600	4 800
	17.6	Overhaul for material hauled in excess of 1.0 km freehaul				
		(a) Sand for filter material (10 km)	m <sup>3</sup> .km	752	3	2 257
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>105 166 978.55</b>



ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
18	18.1	<b>SITE CLEARANCE</b> <u>Clear and grub</u> (a) Footprint	ha	0.20	26 546	5 309
	18.2	<u>Remove and grub large trees and tree stumps of</u> (a) over 1 m and up to and including 2 m  (i) Footprint	No	1	1 700	1 700
	18.3	Remove topsoil to nominal depth of 300 mm and (a) Footprint	m <sup>3</sup>	600	21	12 600
19	19.1	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b> <b>Bulk Excavation</b>  (a) Excavate in all materials (to stockpile or  (i) Stockpile  (1) Embankment footprint	m <sup>3</sup>	46400	35	1 624 000
		(b) Extra over for:  (i) Intermediate excavation	m <sup>3</sup>	13 920	3	44 544
		(ii) Hard rock excavation	m <sup>3</sup>	9 280	34	315 520
		(iii) Boulder excavation, Class A	m <sup>3</sup>	2 320	79	182 120
		(iv) Boulder excavation, Class B	m <sup>3</sup>	2 320	61	141 520
	19.2	<u>Foundation Treatment</u> (a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	600	664	398 400
		(b) Treatment of Faults, Dykes, Shear Zones and	m <sup>3</sup>	600	660	398 400
20		<u>Scheduled Reinforcement items</u> Steel  (a) High tensile steel 16 mm diameter and over	t	3 430	8 400	28 809 984
21	21.1	<u>Scheduled Concrete items</u> Blinding layer and Dental Concrete  (b) Dental concrete (Class 15/38)	m <sup>3</sup>	100	1 869	186 900
	21.2	Strength and Mass Concrete  (a) Strength Concrete (Class 30/38)	m <sup>3</sup>	42 872	1 500	64 308 000
	21.3	Secondary concrete (Class 30/19)	m <sup>3</sup>	100	1 870	187 000
22		<u>Unformed Surface Finishes</u> Class U2 finish	m <sup>2</sup>	1 422	29	41 238
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>96 657 235</b>

SITE B, OPTION 3  
with  
Tunnel inlet structure

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
					RAND	
18		<b>Landscaping</b> (% of 1-9)	%	412 053 028	5	20 602 651
19		<b>Miscellaneous</b> (% of 1-9)	%	412 053 028	15	61 807 954
		<b>SUB TOTAL A</b>				494 463 634
20		<b>Preliminary &amp; General</b> (% of sub-total A)	%	494 463 634	30	148 339 090
21		<b>Preliminary works</b>				
	21.1	(a) Access road	km	5	400 000	1 840 000.00
	21.2	(b) Electrical supply to site	Sum			1 000 000
	21.3	(c) Construction water to site	Sum			300 000
	21.4	(d) Railhead & materials handling	Sum			
	21.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				646 242 724
22		<b>Contingencies</b> (% of sub total B)	%	646 242 724	10	64 624 272
		<b>SUB TOTAL C</b>				710 866 996
23		<b>Planning design &amp; supervision</b> (% of sub total C)	%	710 866 996	15	106 630 049
		<b>SUB TOTAL D</b>				817 497 045
24		<b>VAT</b> (% of sub total D)	%	817 497 045	0	0
		<b>NETT PROJECT COST</b>				817 497 045
25		<b>Cost of relocations</b>	Sum			
26		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				817 497 045

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>STAGE 1</b>						
1		<b>SITE CLEARANCE</b>				
	1.1	<u>Clear and grub</u>				
		(a) Portal footprints	ha	1.5	26 546	39 819
	1.2	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2m	No	2	1 700	3 400
	1.3	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>	m <sup>3</sup>	4525	20	90 500
2		<b>EXCAVATION AND BACKFILL FOR DAMS AND Bulk Excavation</b>				
	2.1	<b><u>Inlet portal</u></b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	20 564	21	431 844
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	5 141	3	16 965
		(ii) Hard Rock	m <sup>3</sup>	5 141	34	174 794
		(iii) Boulder, Class A	m <sup>3</sup>	2 056	78	160 399
		(iv) Boulder, Class B	m <sup>3</sup>	1 028	61	62 720
	2.2	<b><u>Outlet Portal</u></b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	170 633	21	3 583 293
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	42 658	3	140 772
		(ii) Hard Rock	m <sup>3</sup>	42 658	34	1 450 381
		(iii) Boulder, Class A	m <sup>3</sup>	25 595	78	1 996 406
		(iv) Boulder, Class B	m <sup>3</sup>	8 532	61	520 431
	2.3	<b><u>Dewatering</u></b>	Sum	1	100 000	100 000
<b>STAGE 2</b>						
3		<b>SITE CLEARANCE</b>				
	3.1	<u>Clear and grub</u>				
		(a) Embankment footprint	ha	0.5	26 546	13 273
	3.2	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2 m	No	2	1 700.00	3 400
<b>TOTAL CARRIED FORWARD</b>						<b>8 788 397</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>8 788 397</b>
4		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b>				
		(a) Excavate all materials				
		(i) Topsoil at Upstream & Downstream cofferdam	m <sup>3</sup>	1 638	21	34 398
5		<b>EMBANKMENT CONSTRUCTION</b>				
		Earthfille Upstream & Downstream Cofferdam Construction.				
		Forming Embankment				
		Using material from designated borrow areas or commercial				
		(4) Homogeneous Material	m <sup>3</sup>	25269	50	1 263 450
6		<b>TUNNEL CONSTRUCTION</b>				
	6.1	<b>TUNNEL EXCAVATION</b>				
		(a) Tunnel (Rock class II)	m <sup>3</sup>	37 186	2 051	76 268 896
	6.2	<b>ROCK SUPPORT</b>				
		(a) Rockbolts	m	15 768	37	577 314
		(b) Shotcrete	m <sup>3</sup>	756	2 500	1 891 023
		(c) Reinforcing mesh	m <sup>2</sup>	4 920	26	127 913
	6.3	<b>DEWATERING</b>	Sum	1	550 000	550 000
		<b>STAGE 3</b>				
7		<b>MEDIUM PRESSURE PIPELINES</b>				
		Supply, lay, and bed pipes complete with couplings				
		(a) 500 mm diameter concrete pipe (class 75D) in concrete	m	324	80	25 920
		(b) Water control in tunnel	Prov Sum	1	100 000	100 000
8		<b>PLUG OF TUNNEL</b>				
	8.1	<u>Scheduled Formwork items</u>				
		Class F1				
		(a) Vertical formwork	m <sup>2</sup>	310	550	170 500
	8.2	<u>Scheduled Concrete items</u>				
		Strength and Mass concrete				
		(a) Sealing of bulkheads shaft with mass concrete 25 Mpa/19	m <sup>3</sup>	1 050	1 100	1 155 000
		(c) Plug 25 MPa/19 mm	m <sup>3</sup>	708	1 100	778 250
	8.3	<u>Joints</u>				
		(e) Swellable water stops	m	30	500	15 000
	8.4	<u>Miscellaneous and Sundry items</u>				
		(a) Bulkheads incl reinforcement at 120 kg/m <sup>3</sup>	No	240	3 000	720 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>92 466 061</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
9	9.1	<b>SITE CLEARANCE</b>				
		<u>Clear and grub</u>				
		(a) Main embankment footprint	ha	8.40	26 546	222 986
		(b) Spillway	ha	18.90	13 635	257 702
		(c) Outlet Works	ha	0.20	13 635	2 727
	9.2	(d) Saddle embankment footprint	ha	3.40	26 546	90 256
		<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2 m				
		(i) Embankment footprint (Main & Saddle)	No	7	1 700	11 900
		(ii) Spillway	No	5	1 700	8 500
	9.3	(iii) Outlet works	No	2	1 700	3 400
		<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>				
		(a) Embankment footprint (Main & Saddle)	m <sup>3</sup>	42 638	21	895 398.00
		(b) Spillway	m <sup>3</sup>	57 288	16	916 608.00
(c) Outlet/Inlet works		m <sup>3</sup>	750	21	15 750.00	
10	10.1	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b>				
		<u>Bulk Excavation</u>				
		(a) Excavate in all materials (to stockpile or dispose)				
		(i) Stockpile				
		(1) Embankment footprint (Use in rockfill)	m <sup>3</sup>	0	35.00	0.00
		(2) Spillway (Use in Rockfill)	m <sup>3</sup>	0	31.00	0.00
		(3) Outlet works (Use in Rockfill)	m <sup>3</sup>	0	35.00	0.00
		(b) Extra over for:				
		(i) Intermediate excavation	m <sup>3</sup>	0	3.20	0.00
		(ii) Hard rock excavation	m <sup>3</sup>	0	34.00	0.00
		(iii) Boulder excavation, Class A	m <sup>3</sup>	0	78.50	0.00
		(iv) Boulder excavation, Class B	m <sup>3</sup>	0	61.00	0.00
		11		<b>FOUNDATION TREATMENT</b>		
(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>			1 881	664	1 248 984
(b) Treatment of Faults, Dykes, Shear Zones and Zones of Poor Rock	m <sup>3</sup>			1 881	660	1 241 460
<b>TOTAL CARRIED FORWARD</b>						<b>4 915 671</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
12	12.1	<b>EMBANKMENT CONSTRUCTION</b>					
		<u>Forming Embankment</u>					
		Using material from designated borrow areas					
		Main embankment					
		(1) Rockfill	m <sup>3</sup>	1 417 432	71	100 637 672	
		(2) Clay Core	m <sup>3</sup>	294 356	50	14 717 800	
		(3) Filter	m <sup>3</sup>	86 534	450	38 940 300	
		Saddle embankment					
		(1) Rockfill	m <sup>3</sup>	160 782	71	11 415 522	
		(2) Clay Core	m <sup>3</sup>	47 931	50	2 396 550	
		(3) Filter	m <sup>3</sup>	41 864	450	18 838 800	
	12.2	<u>Rockfill trial (test) Embankment size as per specification</u>	No	1	147 000	147 000	
	12.3	<u>Overhaul (Clay for 10 km)</u>	m <sup>3</sup> .km	17 114	3	51 343	
	12.4	<u>Overhaul (Rockfill from spillway for 1 km)</u>	m <sup>3</sup> .km	1 417 432	3	4 252 296	
13	13.1	<b>SECTION : DRILLING &amp; GROUTING</b>					
		<b>Main embankment</b>					
		(a) Curtain grouting	m	8 464	850	7 194 400	
		(b) Consolidation grouting	m	2 820	850	2 397 000	
		13.2	<b>Saddle Embankment</b>				
			(a) Curtain grouting	m	2 687	850	2 283 950
		(b) Consolidation grouting	m	1 845	850	1 568 250	
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>204 840 883</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
14	14.1	<b>CONVENTIONAL CONCRETE FOR DAMS</b>					
		<u>Scheduled Formwork items</u>					
		Class F4					
		(a) Vertical					
		(1) Spillway	m <sup>2</sup>	1 444	530	765 320	
		(2) Transfer structure to tunnels	m <sup>2</sup>	6 804	550	3 742 200	
		(b) Sloped					
		(1) Ogee of spillway	m <sup>2</sup>	1 328	581	771 568	
		(2) Round	m <sup>2</sup>	2 337	581	1 357 797	
		(c) Sloping					
		(1) Stilling basin blocks	m <sup>2</sup>	33	581	19 173	
		(d) Horizontal	m <sup>2</sup>	352	581	204 512	
		14.2	<u>Keyways on contraction joints</u>				
		(a) Bridges dimensions to be given in detail design	m	20	100	2 000	
		14.3	<u>Scheduled Reinforcement items</u>				
		14.4	<u>Anchors</u>				
		Anchor bars (Y32 @ 2.5 m x 2 m)	t	20	8 500	168 146	
		14.5	<u>Scheduled Concrete items</u>				
		Strength & Mass Concrete					
		(a) Grade 25 MPa/19 mm					
(1) Spillway, bridges and retaining wall	m <sup>3</sup>	10 713	1 500	16 069 500			
(2) Transfer intake tunnel	m <sup>3</sup>	30 040	1 500	45 059 700			
Secondary Concrete							
(a) Grade 25 MPa/19 mm	m <sup>3</sup>	200	1 800	360 000			
14.6	<u>Unformed Surface Finishes</u>						
Class U2 (Wood-floated) finish							
(a) Top of chute	m <sup>2</sup>	86	23	1 967			
(b) Top of bridges	m <sup>2</sup>	197	23	4 531			
(c) Chute and Stilling basin floor	m <sup>2</sup>	6 270	23	144 210			
(d) Transfer intake	m <sup>2</sup>	943	25	23 575			
15		<b>MECHANICAL ITEMS</b>					
		(a) Valves and gates	Sum			6 840 000	
		(b) Cranes & Hoists	Sum			2 330 000	
		(c) Structural steelwork	Sum			1 712 971	
<b>TOTAL CARRIED FORWARD</b>						<b>109 406 241</b>	



ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>109 406 241.23</b>
<b>16</b>		<b>WATERSTOPS, JOINTING AND BEARINGS</b>				
	16.1	<u>Scheduled items</u> Waterstops				
		(a) 250 mm Centre bulb PVC waterstop	m	329	630	207 081
	16.2	Joint sealants				
		(a) Chute wall - 12mm expanding cork	m	329	10	3 287
		(b) Chute wall - 12m Impregnated Bitumen Fibre board	m	329	10	3 287
		(c) Chute wall - 12 x 12 mm Polysulphide sealant	m	329	10	3 287
<b>17</b>		<b>SUB-SOIL DRAINAGE</b>				
	17.1	<u>Scheduled items</u> Excavation for sub-soil drainage system				
		(a) Excavating soft material situated within the following depth ranges below the surface level:				
		(i) 0 m to 1,5 m	m <sup>3</sup>	78	21	1 646
		(b) Extra over sub-item (a), irrespective of depth, for:				
		(ii) Excavation in hard material	m <sup>3</sup>	39	4	157
		Natural permeable material in sub-soil drainage systems				
	17.2	(b) Sand as specified on detail drawings	m <sup>3</sup>	75	550	41 382
	17.3	Pipes in sub-soil drainage system				
		(c) 110 NB, Class 6, HDPE pressure pipe, non perforated, complying with SANS 533, Part II	m	314	400	125 400
		(d) 75 NB, flexible slotted drainage pipes with smooth bore, "Drainex" or equivalent by Kaytech	m	95	330	31 350
	17.4	Caps to higher ends of sub-surface drain pipes				
		(a) High end of pipes of Drainex pipes	No	5	50	238
	17.5	Concrete outlet structures for sub-soil drainage systems complete as per drawings				
		(a) Concrete 1500 mm dia	No	8	600	4 800
		Overhaul for material hauled in excess of 1.0 km freehaul				
		(a) Sand for filter material (10 km)	m <sup>3</sup> .km	752	3	2 257
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>109 830 412.55</b>

# **Appendix K**

## **Smithfield Dam site B, Option 2**

### **BOQ**

SITE B, OPTION 2  
with  
INLET STRUCTURE TO PUMPSTATION

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE RAND	AMOUNT
16		<b>Landscaping</b> (% of 1-9)	%	795 841 237	5	39 792 062
17		<b>Miscellaneous</b> (% of 1-9)	%	795 841 237	15	119 376 186
		<b>SUB TOTAL A</b>				955 009 485
18		<b>Preliminary &amp; General</b> (% of sub-total A)	%	955 009 485	30	286 502 845
19		<b>Preliminary works</b>				
	19.1	(a) Access road	km	5	400 000	1 840 000.00
	19.2	(b) Electrical supply to site	Sum			1 000 000
	19.3	(c) Construction water to site	Sum			300 000
	19.4	(d) Railhead & materials handling	Sum			
	19.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				1 244 952 330
20		<b>Contingencies</b> (% of sub total B)	%	1 244 952 330	10	124 495 233
		<b>SUB TOTAL C</b>				1 369 447 563
21		<b>Planning design &amp; supervision</b> (% of sub total C)	%	1 369 447 563	15	205 417 134
		<b>SUB TOTAL D</b>				1 574 864 697
22		<b>VAT</b> (% of sub total D)	%	1 574 864 697	0	0
		<b>NETT PROJECT COST</b>				1 574 864 697
23		<b>Cost of relocations</b>	Sum			
24		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				1 574 864 697

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
1	1.1	<b>SITE CLEARANCE</b>					
		<u>Clear and grub</u>					
		(a) Right Earth embankment	ha	5.40	26 600	143 640	
		(b) RCC	ha	1.80	26 600	47 880	
		(c) Left Embankment	ha	0.40	26 600	10 640	
	1.2	(d) Saddle embankment	ha	3.40	26 600	90 440	
		<u>Remove and grub large trees and tree stumps of girth</u>					
	1.3	(a) over 1 m and up to and including 2 m					
		(i) Whole footprint area	No	10	1 700	17 000	
	2	2.1	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>				
			(a) Right Earth embankment	m <sup>3</sup>	16 723	21	351 183
			(b) RCC	m <sup>3</sup>	5 413	21	113 673
			(c) Left Embankment	m <sup>3</sup>	8 883	21	186 543
			(d) Saddle embankment	m <sup>3</sup>	17 140	21	359 940
2	2.1	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>					
		<u>Bulk Excavation</u>					
		(a) Excavate in all materials (to stockpile or dispose)					
		(i) Stockpile					
		(1) RCC excavation	m <sup>3</sup>	88395	30	2 651 850	
		(2) Right flank core excavation	m <sup>3</sup>	73418	30	2 202 540	
		(3) Left flank core excavation	m <sup>3</sup>	43391	30	1 301 730	
		(4) Saddle dam core excavation	m <sup>3</sup>	6782	30	203 460	
		(5) Outlet works	m <sup>3</sup>	16240	30	487 200	
		(b) Extra over for:					
		(i) Intermediate excavation	m <sup>3</sup>	68 468	4	273 871	
		(ii) Hard rock excavation	m <sup>3</sup>	45 645	34	1 551 937	
		(iii) Boulder excavation, Class A	m <sup>3</sup>	11 411	79	901 493	
		(iv) Boulder excavation, Class B	m <sup>3</sup>	11 411	61	696 089	
3		<b>FOUNDATION TREATMENT</b>					
		(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	5 880	665	3 910 200	
		(b) Treatment of Faults, Dykes, Shear Zones and Zones of	m <sup>3</sup>	5 880	658	3 869 040	
<b>TOTAL CARRIED FORWARD</b>						<b>19 370 349</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
5		<b>EMBANKMENT</b>				
		<b>SECTION: EARTHFILL DAM CONSTRUCTION</b>				
		Embankment				
		(a) Trial Embankment	No			146 619
		(b) Forming right flank embankment				
		(1) Earth fill	m <sup>3</sup>	383775	46	17 653 650
		(2) Filters	m <sup>3</sup>	16059	431	6 921 429
		(3) Riprap	m <sup>3</sup>	224	351	78 624
		(4) Clay core	m <sup>3</sup>	93360	50	4 668 000
		(b) Forming left flank embankment				
		(1) Earth fill	m <sup>3</sup>	185481	46	8 532 126
		(2) Filters	m <sup>3</sup>	15032	431	6 478 792
		(3) Riprap	m <sup>3</sup>	131	351	45 981
		(4) Clay core	m <sup>3</sup>	48724	50	2 436 200
		(b) Forming saddle embankment				
	(1) Earth fill	m <sup>3</sup>	130207	46	5 989 522	
	(2) Filters	m <sup>3</sup>	27117	431	11 687 427	
	(3) Riprap	m <sup>3</sup>	520	351	182 520	
	(4) Clay core	m <sup>3</sup>	41866	50	2 093 300	
6		<b>CONCRETE STRUCTURE</b>				
		<b>SECTION: CONVENTIONAL CONCRETE FOR</b>				
	6.1	SCHEDULED FORMWORK ITEMS				
		Class F2				
		(a) Vertical				
		(1) Wall (downstream and upstream)	m <sup>2</sup>	40 817	610	24 898 370
		(2) Transfer structure to pumpstation	m <sup>2</sup>	6 804	550	3 742 200
		(c) Forming of Gallery				
		(1) Horizontal	m	414	6 500	2 691 000
		(2) Sloping	m	391	8 000	3 128 000
	6.2	SCHEDULED REINFORCEMENT ITEMS	t	3 258	8 400	27 368 712
	6.3	SCHEDULED CONCRETE ITEMS				
		Strength & Mass Concrete				
		(a) Grade 25 MPa/19 mm				
		(1) Apron (160m x 1m x 22m)	m <sup>3</sup>	3 520	1 768	6 223 360
	(2) Transfer intake to pumpstation	m <sup>3</sup>	29 062	1 500	43 592 700	
	Secondary Concrete					
	(a) Grade 25 MPa/19 mm	m <sup>3</sup>	200	1 800	360 000	
6.4	<b>UNFORMED SURFACE FINISH</b>					
	Class U2 (Wood-floated) finish					
	(a) Concrete wall structure	m <sup>2</sup>	17 496	50	874 800	
	(b) Apron (downstream)	m <sup>2</sup>	3 520	50	176 000	
	(c) Gallery floor	m <sup>2</sup>	453	50	22 650	
	(d) Transfer intake	m <sup>2</sup>	862	25	21 550	
<b>TOTAL CARRIED FORWARD</b>						<b>180 013 532</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
<b>TOTAL BROUGHT FORWARD</b>						<b>180 013 532</b>
7		<b>SECTION: ROLLER COMPACTED CONCRETE FOR</b>				
	7.1	Roller Compacted Concrete				
		(a) Grade 15 MPa concrete				
		(1) Wall	m <sup>3</sup>	411 352	950	390 784 400
		(2) Additional for river diversion slot (Not continuous placing of RCC)	m <sup>3</sup>	411 352	100	41 135 200
		(b) Immersion Vibrated Roller Compacted Concrete				
		(1) 600 mm thick, upstream	m <sup>3</sup>	12 245	1 100	13 469 500
		(2) 600 mm thick, downstream	m <sup>2</sup>	15 123	1 100	16 635 300
	7.2	RCC Bedding Mortar				
		(a) Grade 15 MPa concrete	m <sup>2</sup>	5 400	500	2 700 000
	7.3	Test Section	No.	1	840 000	840 000
8		<b>SECTION : DRILLING &amp; GROUTING</b>				
	8.1	<b>Right embankment</b>				
		(a) Curtain grouting	m	3 826	850	3 252 100
		(b) Consolidation grouting	m	1 111	850	944 350
	8.2	<b>RCC</b>				
		(a) Curtain grouting	m	11 602	850	9 861 700
		(b) Consolidation grouting	m	3 915	850	3 327 750
	8.3	<b>Left embankment</b>				
		(a) Curtain grouting	m	1 340	850	1 139 000
		(b) Consolidation grouting	m	700	850	595 000
	8.4	<b>Saddle</b>				
		(a) Curtain grouting	m	1 209	850	1 027 650
		(b) Consolidation grouting	m	2 650	850	2 252 500
9		<b>SECTION: WATERSTOPS, JOINTING AND BEARING</b>				
		SCHEDULED ITEMS				
	9.1	Waterstops	m	1 361	700	952 700
10		<b>MECHANICAL ITEMS</b>				
		(a) Valves and gates	Sum			6 840 000
		(b) Cranes & Hoists	Sum			2 330 000
		(c) Structural steelwork	Sum			1 712 971
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>679 813 653</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
11	11.1	<b>SITE CLEARANCE</b> <u>Clear and grub</u> (a) Footprint	ha	0.20	26 546	5 309
	11.2	<u>Remove and grub large trees and tree stumps of</u> (a) over 1 m and up to and including 2 m  (i) Footprint	No	1	1 700	1 700
	11.3	Remove topsoil to nominal depth of 300 mm and (a) Footprint	m <sup>3</sup>	600	21	12 600
12	12.1	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b> Bulk Excavation  (a) Excavate in all materials (to stockpile or  (i) Stockpile  (1) Embankment footprint	m <sup>3</sup>	46400	35	1 624 000
		(b) Extra over for:  (i) Intermediate excavation	m <sup>3</sup>	13 920	3	44 544
		(ii) Hard rock excavation	m <sup>3</sup>	9 280	34	315 520
		(iii) Boulder excavation, Class A	m <sup>3</sup>	2 320	79	182 120
		(iv) Boulder excavation, Class B	m <sup>3</sup>	2 320	61	141 520
	12.2	<u>Foundation Treatment</u> (a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	600	664	398 400
	(b) Treatment of Faults, Dykes, Shear Zones and	m <sup>3</sup>	600	660	398 400	
13		<u>Scheduled Reinforcement items</u> Steel  (a) High tensile steel 16 mm diameter and over	t	3 430	8 400	28 809 984
	14	<u>Scheduled Concrete items</u> Blinding layer and Dental Concrete  (b) Dental concrete (Class 15/38)	m <sup>3</sup>	100	1 869	186 900
14.2		Strength and Mass Concrete (a) Strength Concrete (Class 30/38)	m <sup>3</sup>	42 872	1 500	64 308 000
14.3		Secondary concrete (Class 30/19)	m <sup>3</sup>	100	1 870	187 000
15		<u>Unformed Surface Finishes</u> Class U2 finish	m <sup>2</sup>	1 422	29	41 238
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>96 657 235</b>



SITE B, OPTION 3  
with  
Tunnel inlet structure

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
					RAND	
18		<b>Landscaping</b> (% of 1-9)	%	412 053 028	5	20 602 651
19		<b>Miscellaneous</b> (% of 1-9)	%	412 053 028	15	61 807 954
		<b>SUB TOTAL A</b>				494 463 634
20		<b>Preliminary &amp; General</b> (% of sub-total A)	%	494 463 634	30	148 339 090
21		<b>Preliminary works</b>				
	21.1	(a) Access road	km	5	400 000	1 840 000.00
	21.2	(b) Electrical supply to site	Sum			1 000 000
	21.3	(c) Construction water to site	Sum			300 000
	21.4	(d) Railhead & materials handling	Sum			
	21.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				646 242 724
22		<b>Contingencies</b> (% of sub total B)	%	646 242 724	10	64 624 272
		<b>SUB TOTAL C</b>				710 866 996
23		<b>Planning design &amp; supervision</b> (% of sub total C)	%	710 866 996	15	106 630 049
		<b>SUB TOTAL D</b>				817 497 045
24		<b>VAT</b> (% of sub total D)	%	817 497 045	0	0
		<b>NETT PROJECT COST</b>				817 497 045
25		<b>Cost of relocations</b>	Sum			
26		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				817 497 045

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>STAGE 1</b>						
1		<b>SITE CLEARANCE</b>				
	1.1	<u>Clear and grub</u>				
		(a) Portal footprints	ha	1.5	26 546	39 819
	1.2	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2m	No	2	1 700	3 400
	1.3	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>	m <sup>3</sup>	4525	20	90 500
2		<b>EXCAVATION AND BACKFILL FOR DAMS AND Bulk Excavation</b>				
	2.1	<b><u>Inlet portal</u></b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	20 564	21	431 844
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	5 141	3	16 965
		(ii) Hard Rock	m <sup>3</sup>	5 141	34	174 794
		(iii) Boulder, Class A	m <sup>3</sup>	2 056	78	160 399
		(iv) Boulder, Class B	m <sup>3</sup>	1 028	61	62 720
	2.2	<b><u>Outlet Portal</u></b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	170 633	21	3 583 293
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	42 658	3	140 772
		(ii) Hard Rock	m <sup>3</sup>	42 658	34	1 450 381
		(iii) Boulder, Class A	m <sup>3</sup>	25 595	78	1 996 406
		(iv) Boulder, Class B	m <sup>3</sup>	8 532	61	520 431
	2.3	<b><u>Dewatering</u></b>	Sum	1	100 000	100 000
<b>STAGE 2</b>						
3		<b>SITE CLEARANCE</b>				
	3.1	<u>Clear and grub</u>				
		(a) Embankment footprint	ha	0.5	26 546	13 273
	3.2	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2 m	No	2	1 700.00	3 400
<b>TOTAL CARRIED FORWARD</b>						<b>8 788 397</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>8 788 397</b>
4		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b>				
		(a) Excavate all materials				
		(i) Topsoil at Upstream & Downstream cofferdam	m <sup>3</sup>	1 638	21	34 398
5		<b>EMBANKMENT CONSTRUCTION</b>				
		Earthfille Upstream & Downstream Cofferdam Construction.				
		Forming Embankment				
		Using material from designated borrow areas or commercial				
		(4) Homogeneous Material	m <sup>3</sup>	25269	50	1 263 450
6		<b>TUNNEL CONSTRUCTION</b>				
	6.1	<b>TUNNEL EXCAVATION</b>				
		(a) Tunnel (Rock class II)	m <sup>3</sup>	37 186	2 051	76 268 896
	6.2	<b>ROCK SUPPORT</b>				
		(a) Rockbolts	m	15 768	37	577 314
		(b) Shotcrete	m <sup>3</sup>	756	2 500	1 891 023
		(c) Reinforcing mesh	m <sup>2</sup>	4 920	26	127 913
	6.3	<b>DEWATERING</b>	Sum	1	550 000	550 000
		<b>STAGE 3</b>				
7		<b>MEDIUM PRESSURE PIPELINES</b>				
		Supply, lay, and bed pipes complete with couplings				
		(a) 500 mm diameter concrete pipe (class 75D) in concrete	m	324	80	25 920
		(b) Water control in tunnel	Prov Sum	1	100 000	100 000
8		<b>PLUG OF TUNNEL</b>				
	8.1	<u>Scheduled Formwork items</u>				
		Class F1				
		(a) Vertical formwork	m <sup>2</sup>	310	550	170 500
	8.2	<u>Scheduled Concrete items</u>				
		Strength and Mass concrete				
		(a) Sealing of bulkheads shaft with mass concrete 25 Mpa/19	m <sup>3</sup>	1 050	1 100	1 155 000
		(c) Plug 25 MPa/19 mm	m <sup>3</sup>	708	1 100	778 250
	8.3	<u>Joints</u>				
		(e) Swellable water stops	m	30	500	15 000
	8.4	<u>Miscellaneous and Sundry items</u>				
		(a) Bulkheads incl reinforcement at 120 kg/m <sup>3</sup>	No	240	3 000	720 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>92 466 061</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
9	9.1	<b>SITE CLEARANCE</b>				
		<u>Clear and grub</u>				
		(a) Main embankment footprint	ha	8.40	26 546	222 986
		(b) Spillway	ha	18.90	13 635	257 702
		(c) Outlet Works	ha	0.20	13 635	2 727
	9.2	(d) Saddle embankment footprint	ha	3.40	26 546	90 256
		<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2 m				
		(i) Embankment footprint (Main & Saddle)	No	7	1 700	11 900
		(ii) Spillway	No	5	1 700	8 500
	9.3	(iii) Outlet works	No	2	1 700	3 400
		<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>				
		(a) Embankment footprint (Main & Saddle)	m <sup>3</sup>	42 638	21	895 398.00
		(b) Spillway	m <sup>3</sup>	57 288	16	916 608.00
10	10.1	(c) Outlet/Inlet works	m <sup>3</sup>	750	21	15 750.00
		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b>				
		<u>Bulk Excavation</u>				
		(a) Excavate in all materials (to stockpile or dispose)				
		(i) Stockpile				
		(1) Embankment footprint (Use in rockfill)	m <sup>3</sup>	0	35.00	0.00
		(2) Spillway (Use in Rockfill)	m <sup>3</sup>	0	31.00	0.00
		(3) Outlet works (Use in Rockfill)	m <sup>3</sup>	0	35.00	0.00
		(b) Extra over for:				
		(i) Intermediate excavation	m <sup>3</sup>	0	3.20	0.00
		(ii) Hard rock excavation	m <sup>3</sup>	0	34.00	0.00
		(iii) Boulder excavation, Class A	m <sup>3</sup>	0	78.50	0.00
		(iv) Boulder excavation, Class B	m <sup>3</sup>	0	61.00	0.00
11		<b>FOUNDATION TREATMENT</b>				
		(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	1 881	664	1 248 984
		(b) Treatment of Faults, Dykes, Shear Zones and Zones of Poor Rock	m <sup>3</sup>	1 881	660	1 241 460
<b>TOTAL CARRIED FORWARD</b>						<b>4 915 671</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
12	12.1	<b>EMBANKMENT CONSTRUCTION</b>					
		<u>Forming Embankment</u>					
		Using material from designated borrow areas					
		Main embankment					
		(1) Rockfill	m <sup>3</sup>	1 417 432	71	100 637 672	
		(2) Clay Core	m <sup>3</sup>	294 356	50	14 717 800	
		(3) Filter	m <sup>3</sup>	86 534	450	38 940 300	
		Saddle embankment					
		(1) Rockfill	m <sup>3</sup>	160 782	71	11 415 522	
		(2) Clay Core	m <sup>3</sup>	47 931	50	2 396 550	
		(3) Filter	m <sup>3</sup>	41 864	450	18 838 800	
	12.2	<u>Rockfill trial (test) Embankment size as per specification</u>	No	1	147 000	147 000	
	12.3	<u>Overhaul (Clay for 10 km)</u>	m <sup>3</sup> .km	17 114	3	51 343	
	12.4	<u>Overhaul (Rockfill from spillway for 1 km)</u>	m <sup>3</sup> .km	1 417 432	3	4 252 296	
13	13.1	<b>SECTION : DRILLING &amp; GROUTING</b>					
		<b>Main embankment</b>					
		(a) Curtain grouting	m	8 464	850	7 194 400	
		(b) Consolidation grouting	m	2 820	850	2 397 000	
		13.2	<b>Saddle Embankment</b>				
			(a) Curtain grouting	m	2 687	850	2 283 950
		(b) Consolidation grouting	m	1 845	850	1 568 250	
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>204 840 883</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
14	14.1	<b>CONVENTIONAL CONCRETE FOR DAMS</b>					
		<u>Scheduled Formwork items</u>					
		Class F4					
		(a) Vertical					
		(1) Spillway	m <sup>2</sup>	1 444	530	765 320	
		(2) Transfer structure to tunnels	m <sup>2</sup>	6 804	550	3 742 200	
		(b) Sloped					
		(1) Ogee of spillway	m <sup>2</sup>	1 328	581	771 568	
		(2) Round	m <sup>2</sup>	2 337	581	1 357 797	
		(c) Sloping					
		(1) Stilling basin blocks	m <sup>2</sup>	33	581	19 173	
		(d) Horizontal	m <sup>2</sup>	352	581	204 512	
		14.2	<u>Keyways on contraction joints</u>				
		(a) Bridges dimensions to be given in detail design	m	20	100	2 000	
		14.3	<u>Scheduled Reinforcement items</u>	t	3 551	8 400	29 829 072
		14.4	<u>Anchors</u>				
		Anchor bars (Y32 @ 2.5 m x 2 m)	t	20	8 500	168 146	
		14.5	<u>Scheduled Concrete items</u>				
		Strength & Mass Concrete					
		(a) Grade 25 MPa/19 mm					
(1) Spillway, bridges and retaining wall	m <sup>3</sup>	10 713	1 500	16 069 500			
(2) Transfer intake tunnel	m <sup>3</sup>	30 040	1 500	45 059 700			
Secondary Concrete							
(a) Grade 25 MPa/19 mm	m <sup>3</sup>	200	1 800	360 000			
14.6	<u>Unformed Surface Finishes</u>						
Class U2 (Wood-floated) finish							
(a) Top of chute	m <sup>2</sup>	86	23	1 967			
(b) Top of bridges	m <sup>2</sup>	197	23	4 531			
(c) Chute and Stilling basin floor	m <sup>2</sup>	6 270	23	144 210			
(d) Transfer intake	m <sup>2</sup>	943	25	23 575			
15		<b>MECHANICAL ITEMS</b>					
		(a) Valves and gates	Sum			6 840 000	
		(b) Cranes & Hoists	Sum			2 330 000	
		(c) Structural steelwork	Sum			1 712 971	
<b>TOTAL CARRIED FORWARD</b>						<b>109 406 241</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>109 406 241.23</b>
<b>16</b>		<b>WATERSTOPS, JOINTING AND BEARINGS</b>				
	16.1	<u>Scheduled items</u> Waterstops				
		(a) 250 mm Centre bulb PVC waterstop	m	329	630	207 081
	16.2	Joint sealants				
		(a) Chute wall - 12mm expanding cork	m	329	10	3 287
		(b) Chute wall - 12m Impregnated Bitumen Fibre board	m	329	10	3 287
		(c) Chute wall - 12 x 12 mm Polysulphide sealant	m	329	10	3 287
<b>17</b>		<b>SUB-SOIL DRAINAGE</b>				
	17.1	<u>Scheduled items</u> Excavation for sub-soil drainage system				
		(a) Excavating soft material situated within the following depth ranges below the surface level:				
		(i) 0 m to 1,5 m	m <sup>3</sup>	78	21	1 646
		(b) Extra over sub-item (a), irrespective of depth, for:				
		(ii) Excavation in hard material	m <sup>3</sup>	39	4	157
		Natural permeable material in sub-soil drainage systems				
	17.2	(b) Sand as specified on detail drawings	m <sup>3</sup>	75	550	41 382
	17.3	Pipes in sub-soil drainage system				
		(c) 110 NB, Class 6, HDPE pressure pipe, non perforated, complying with SANS 533, Part II	m	314	400	125 400
		(d) 75 NB, flexible slotted drainage pipes with smooth bore, "Drainex" or equivalent by Kaytech	m	95	330	31 350
	17.4	Caps to higher ends of sub-surface drain pipes				
		(a) High end of pipes of Drainex pipes	No	5	50	238
	17.5	Concrete outlet structures for sub-soil drainage systems complete as per drawings				
		(a) Concrete 1500 mm dia	No	8	600	4 800
		Overhaul for material hauled in excess of 1.0 km freehaul				
		(a) Sand for filter material (10 km)	m <sup>3</sup> .km	752	3	2 257
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>109 830 412.55</b>



# **Appendix L**

## **Smithfield Dam site B, Option 3**

### **BOQ**

SITE B, OPTION 3  
with  
INLET STRUCTURE TO PUMPSTATION

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
					RAND	
23		Landscaping (% of 1-9)	%	504 046 829	5	25 202 341
24		Miscellaneous (% of 1-9)	%	504 046 829	15	75 607 024
		<b>SUB TOTAL A</b>				604 856 195
25		Preliminary & General (% of sub-total A)	%	604 856 195	30	181 456 858
26		<b>Preliminary works</b>				
	26.1	(a) Access road	km	5	400 000	1 840 000.00
	26.2	(b) Electrical supply to site	Sum			1 000 000
	26.3	(c) Construction water to site	Sum			300 000
	26.4	(d) Railhead & materials handling	Sum			
	26.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				789 753 053
27		Contingencies (% of sub total B)	%	789 753 053	10	78 975 305
		<b>SUB TOTAL C</b>				868 728 359
28		Planning design & supervision (% of sub total C)	%	868 728 359	15	130 309 254
		<b>SUB TOTAL D</b>				999 037 613
29		VAT (% of sub total D)	%	999 037 613	0	0
		<b>NETT PROJECT COST</b>				999 037 613
30		Cost of relocations	Sum			
31		Cost of land acquisition	Sum			
		<b>TOTAL PROJECT COST</b>				999 037 613

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
		<b>STAGE 1</b>				
1		<b>SITE CLEARANCE</b>				
	1.1	<u>Clear and grub</u>				
		(a) Portal footprints	ha	1.5	26 546	39 819
	1.2	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2m	No	2	1 700	3 400
	1.3	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>	m <sup>3</sup>	4525	20	90 500
2		<b>EXCAVATION AND BACKFILL FOR DAMS AND WATERWAYS</b>				
		Bulk Excavation				
	2.1	<b><u>Inlet portal</u></b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	20 564	21	431 844
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	5 141	3	16 965
		(ii) Hard Rock	m <sup>3</sup>	5 141	34	174 794
		(iii) Boulder, Class A	m <sup>3</sup>	2 056	78	160 399
		(iv) Boulder, Class B	m <sup>3</sup>	1 028	61	62 720
	2.2	<b><u>Outlet Portal</u></b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	170 633	21	3 583 293
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	42 658	3	140 772
		(ii) Hard Rock	m <sup>3</sup>	42 658	34	1 450 381
		(iii) Boulder, Class A	m <sup>3</sup>	25 595	78	1 996 406
		(iv) Boulder, Class B	m <sup>3</sup>	8 532	61	520 431
	2.3	<b><u>Dewatering</u></b>	Sum	1	100 000	100 000
		<b>STAGE 2</b>				
3		<b>SITE CLEARANCE</b>				
	3.1	<u>Clear and grub</u>				
		(a) Embankment footprint	ha	0.5	26 546	13 273
	3.2	<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2 m	No	2	1 700.00	3 400
<b>TOTAL CARRIED FORWARD</b>						<b>8 788 397</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>8 788 397</b>
4		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b>				
		(a) Excavate all materials				
		(i) Topsoil at Upstream & Downstream cofferdam	m <sup>3</sup>	1 638	21	34 398
5		<b>EMBANKMENT CONSTRUCTION</b>				
		Earthfill Upstream & Downstream Cofferdam Construction.				
		Forming Embankment				
		Using material from designated borrow areas or commercial sources				
		(4) Homogeneous Material	m <sup>3</sup>	25269	50	1 263 450
6		<b>TUNNEL CONSTRUCTION</b>				
	6.1	<b>TUNNEL EXCAVATION</b>				
		(a) Tunnel (Rock class II)	m <sup>3</sup>	37 186	2 051	76 268 896
	6.2	<b>ROCK SUPPORT</b>				
		(a) Rockbolts	m	15 768	37	577 314
		(b) Shotcrete	m <sup>3</sup>	756	2 500	1 891 023
		(c) Reinforcing mesh	m <sup>2</sup>	4 920	26	127 913
	6.3	<b>DEWATERING</b>	Sum	1	550 000	550 000
		<b>STAGE 3</b>				
7		<b>MEDIUM PRESSURE PIPELINES</b>				
		Supply, lay, and bed pipes complete with couplings				
		(a) 500 mm diameter concrete pipe (class 75D) in concrete	m	324	80	25 920
		(b) Water control in tunnel	Prov Sum	1	100 000	100 000
8		<b>PLUG OF TUNNEL</b>				
	8.1	<u>Scheduled Formwork items</u>				
		Class F1				
		(a) Vertical formwork	m <sup>2</sup>	310	550	170 500
	8.2	<u>Scheduled Concrete items</u>				
		Strength and Mass concrete				
		(a) Sealing of bulkheads shaft with mass concrete 25 Mpa/19 mm	m <sup>3</sup>	1 050	1 100	1 155 000
		(c) Plug 25 MPa/19 mm	m <sup>3</sup>	708	1 100	778 250
	8.3	<u>Joints</u>				
		(e) Swellable water stops	m	30	500	15 000
	8.4	<u>Miscellaneous and Sundry items</u>				
		(a) Bulkheads incl reinforcement at 120 kg/m <sup>3</sup>	No	240	3 000	720 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>92 466 061</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
9	9.1	<b>SITE CLEARANCE</b>				
		<u>Clear and grub</u>				
		(a) Main embankment footprint	ha	8.40	26 546	222 986
		(b) Spillway	ha	18.90	13 635	257 702
		(c) Outlet Works	ha	0.20	13 635	2 727
	9.2	(d) Saddle embankment footprint	ha	3.40	26 546	90 256
		<u>Remove and grub large trees and tree stumps of girth</u>				
		(a) over 1 m and up to and including 2 m				
		(i) Embankment footprint (Main & Saddle)	No	7	1 700	11 900
		(ii) Spillway	No	5	1 700	8 500
	9.3	(iii) Outlet works	No	2	1 700	3 400
		<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>				
		(a) Embankment footprint (Main & Saddle)	m <sup>3</sup>	42 638	21	895 398.00
		(b) Spillway	m <sup>3</sup>	57 288	16	916 608.00
(c) Outlet/Inlet works		m <sup>3</sup>	750	21	15 750.00	
10	10.1	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b>				
		<u>Bulk Excavation</u>				
		(a) Excavate in all materials (to stockpile or dispose)				
		(i) Stockpile				
		(1) Embankment footprint (Use in rockfill)	m <sup>3</sup>	0	35.00	0.00
		(2) Spillway (Use in Rockfill)	m <sup>3</sup>	0	31.00	0.00
		(3) Outlet works (Use in Rockfill)	m <sup>3</sup>	0	35.00	0.00
		(b) Extra over for:				
		(i) Intermediate excavation	m <sup>3</sup>	0	3.20	0.00
		(ii) Hard rock excavation	m <sup>3</sup>	0	34.00	0.00
		(iii) Boulder excavation, Class A	m <sup>3</sup>	0	78.50	0.00
		(iv) Boulder excavation, Class B	m <sup>3</sup>	0	61.00	0.00
		11		<b>FOUNDATION TREATMENT</b>		
(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>			1 881	664	1 248 984
(b) Treatment of Faults, Dykes, Shear Zones and Zones of	m <sup>3</sup>			1 881	660	1 241 460
<b>TOTAL CARRIED FORWARD</b>						<b>4 915 671</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
12	12.1	<b>EMBANKMENT CONSTRUCTION</b>					
		<u>Forming Embankment</u>					
		Using material from designated borrow areas					
		Main embankment					
		(1) Rockfill	m <sup>3</sup>	1 417 432	71	100 637 672	
		(2) Clay Core	m <sup>3</sup>	294 356	50	14 717 800	
		(3) Filter	m <sup>3</sup>	86 534	450	38 940 300	
		Saddle embankment					
		(1) Rockfill	m <sup>3</sup>	160 782	71	11 415 522	
		(2) Clay Core	m <sup>3</sup>	47 931	50	2 396 550	
(3) Filter	m <sup>3</sup>	41 864	450	18 838 800			
12.2		<u>Rockfill trial (test) Embankment size as per specification</u>	No	1	147 000	147 000	
12.3		<u>Overhaul (Clay for 10 km)</u>	m <sup>3</sup> .km	17 114	3	51 343	
12.4		<u>Overhaul (Rockfill frm spillway 1km)</u>	m <sup>3</sup> km	1 417 432	3	4 252 296	
13	13.1	<b>SECTION : DRILLING &amp; GROUTING</b>					
		<b>Main embankment</b>					
		(a) Curtain grouting	m	8 464	850	7 194 400	
		(b) Consolidation grouting	m	2 820	850	2 397 000	
		13.2	<b>Saddle Embankment</b>				
			(a) Curtain grouting	m	2 687	850	2 283 950
		(b) Consolidation grouting	m	1 845	850	1 568 250	
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>204 840 883</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
14	14.1	<b>CONVENTIONAL CONCRETE FOR DAMS</b>					
		<u>Scheduled Formwork items</u>					
		Class F4					
		(a) Vertical					
		(1) Spillway	m <sup>2</sup>	1 444	530	765 320	
		(2) Transfer structure to tunnels	m <sup>2</sup>	6 804	550	3 742 200	
		(b) Sloped					
		(1) Ogee of spillway	m <sup>2</sup>	1 328	581	771 568	
		(c) Sloping					
		(1) Stilling basin blocks	m <sup>2</sup>	33	581	19 173	
		(d) Horizontal	m <sup>2</sup>	352	581	204 512	
		14.2	<u>Keyways on contraction joints</u>				
		(a) Bridges dimensions to be given in detail design	m	20	100	2 000	
		14.3	<u>Scheduled Reinforcement items</u>	t	3 410	8 400	28 643 160
		14.4	<u>Anchors</u>				
		Anchor bars (Y32 @ 2.5 m x 2 m)	t	20	8 500	168 146	
		14.5	<u>Scheduled Concrete items</u>				
		Strength & Mass Concrete					
		(a) Grade 25 MPa/19 mm					
(1) Spillway, bridges and retaining wall	m <sup>3</sup>	10 713	1 500	16 069 500			
(2) Transfer intake to pumpstation	m <sup>3</sup>	28 628	1 500	42 942 000			
Secondary Concrete							
(a) Grade 25 MPa/19 mm	m <sup>3</sup>	200	1 800	360 000			
14.6	<u>Unformed Surface Finishes</u>						
Class U2 (Wood-floated) finish							
(a) Top of chute	m <sup>2</sup>	86	23	1 967			
(b) Top of bridges	m <sup>2</sup>	197	23	4 531			
(c) Chute and Stilling basin floor	m <sup>2</sup>	6 270	23	144 210			
(d) Transfer intake	m <sup>2</sup>	862	25	21 550			
15		<b>MECHANICAL ITEMS</b>					
		(a) Valves and gates	Sum			6 840 000	
		(b) Cranes & Hoists	Sum			2 330 000	
		(c) Structural steelwork	Sum			1 712 971	
<b>TOTAL CARRIED FORWARD</b>						<b>104 742 807</b>	



ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>104 742 807.23</b>
<b>16</b>		<b>WATERSTOPS, JOINTING AND BEARINGS</b>				
	16.1	<u>Scheduled items</u>				
		Waterstops				
		(a) 250 mm Centre bulb PVC waterstop	m	329	630	207 081
		Joint sealants				
		(a) Chute wall - 12mm expanding cork	m	329	10	3 287
		(b) Chute wall - 12m Impregnated Bitumen Fibre board	m	329	10	3 287
		(c) Chute wall - 12 x 12 mm Polysulphide sealant	m	329	10	3 287
<b>17</b>		<b>SUB-SOIL DRAINAGE</b>				
		<u>Scheduled items</u>				
	17.1	Excavation for sub-soil drainage system				
		(a) Excavating soft material situated within the following depth ranges below the surface level:				
		(i) 0 m to 1,5 m	m <sup>3</sup>	78	21	1 646
		(b) Extra over sub-item (a), irrespective of depth, for:				
		(ii) Excavation in hard material	m <sup>3</sup>	39	4	157
	17.2	Natural permeable material in sub-soil drainage systems				
		(b) Sand as specified on detail drawings	m <sup>3</sup>	75	550	41 382
	17.3	Pipes in sub-soil drainage system				
		(c) 110 NB, Class 6, HDPE pressure pipe, non perforated, complying with SANS 533, Part II	m	314	400	125 400
		(d) 75 NB, flexible slotted drainage pipes with smooth bore, "Drainex" or equivalent by Kaytech	m	95	330	31 350
	17.4	Caps to higher ends of sub-surface drain pipes				
		(a) High end of pipes of Drainex pipes	No	5	50	238
	17.5	Concrete outlet structures for sub-soil drainage systems complete as per drawings				
		(a) Concrete 1500 mm dia	No	8	600	4 800
	17.6	Overhaul for material hauled in excess of 1.0 km freehaul				
		(a) Sand for filter material (10 km)	m <sup>3</sup> .km	752	3	2 257
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>105 166 978.55</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
18	18.1	<b>SITE CLEARANCE</b> <u>Clear and grub</u> (a) Footprint	ha	0.20	26 546	5 309
	18.2	<u>Remove and grub large trees and tree stumps of</u> (a) over 1 m and up to and including 2 m  (i) Footprint	No	1	1 700	1 700
	18.3	Remove topsoil to nominal depth of 300 mm and (a) Footprint	m <sup>3</sup>	600	21	12 600
19	19.1	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b> Bulk Excavation  (a) Excavate in all materials (to stockpile or  (i) Stockpile  (1) Embankment footprint	m <sup>3</sup>	46400	35	1 624 000
		(b) Extra over for:  (i) Intermediate excavation	m <sup>3</sup>	13 920	3	44 544
		(ii) Hard rock excavation	m <sup>3</sup>	9 280	34	315 520
		(iii) Boulder excavation, Class A	m <sup>3</sup>	2 320	79	182 120
	(iv) Boulder excavation, Class B	m <sup>3</sup>	2 320	61	141 520	
	19.2	<u>Foundation Treatment</u> (a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	600	664	398 400
	(b) Treatment of Faults, Dykes, Shear Zones and	m <sup>3</sup>	600	660	398 400	
20		<u>Scheduled Reinforcement items</u> Steel  (a) High tensile steel 16 mm diameter and over	t	3 430	8 400	28 809 984
21	21.1	<u>Scheduled Concrete items</u> Blinding layer and Dental Concrete  (b) Dental concrete (Class 15/38)	m <sup>3</sup>	100	1 869	186 900
		21.2	Strength and Mass Concrete (a) Strength Concrete (Class 30/38)	m <sup>3</sup>	42 872	1 500
	21.3	Secondary concrete (Class 30/19)	m <sup>3</sup>	100	1 870	187 000
22		<u>Unformed Surface Finishes</u> Class U2 finish	m <sup>2</sup>	1 422	29	41 238
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>96 657 235</b>

# **Appendix M**

## **Smithfield Dam site C, Option 1**

### **BOQ**

SITE C, OPTION 1  
WITH  
INLET STRUCTURE TO TUNNEL

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
					RAND	
23		<b>Landscaping</b> (% of 1-9)	%	620 632 225	5	31 031 611
24		<b>Miscellaneous</b> (% of 1-9)	%	620 632 225	15	93 094 834
		<b>SUB TOTAL A</b>				744 758 670
25		<b>Preliminary &amp; General</b> (% of sub-total A)	%	744 758 670	30	223 427 601
26		<b>Preliminary works</b>				
	26.1	(a) Access road	km	5	400 000	1 840 000.00
	26.2	(b) Electrical supply to site	Sum			1 000 000
	26.3	(c) Construction water to site	Sum			300 000
	26.4	(d) Railhead & materials handling	Sum			
	26.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				971 626 271
27		<b>Contingencies</b> (% of sub total B)	%	971 626 271	10	97 162 627
		<b>SUB TOTAL C</b>				1 068 788 899
28		<b>Planning design &amp; supervision</b> (% of sub total C)	%	1 068 788 899	15	160 318 335
		<b>SUB TOTAL D</b>				1 229 107 233
29		<b>VAT</b> (% of sub total D)	%	1 229 107 233	0	0
		<b>NETT PROJECT COST</b>				1 229 107 233
30		<b>Cost of relocations</b>	Sum			
31		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				1 229 107 233

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
		<b>STAGE 1</b>				
1		<b>SITE CLEARANCE</b>				
	1.1	Clear and grub (a) Portal footprints	ha	3.6	26 546	95 948
	1.2	Remove and grub large trees and tree stumps of girth (a) over 1 m and up to and including 2m	No	2	1 700	3 400
	1.3	Remove topsoil to nominal depth of 150 mm and stockpile	m <sup>3</sup>	10842	20	216 840
2		<b>EXCAVATION AND BACKFILL FOR DAMS AND WATERWAYS</b>				
		Bulk Excavation				
	2.1	<b><u>Inlet portal</u></b> (a) Excavate in all materials (i) Excavation (stockpile)	m <sup>3</sup>	178 826	21	3 755 346
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	44 707	3	147 531
		(ii) Hard Rock	m <sup>3</sup>	44 707	34	1 520 021
		(iii) Boulder, Class A	m <sup>3</sup>	17 883	78	1 394 843
		(iv) Boulder, Class B	m <sup>3</sup>	8 941	61	545 419
	2.2	<b><u>Outlet Portal</u></b> (a) Excavate in all materials (i) Excavation (stockpile)	m <sup>3</sup>	303 202	21	6 367 242
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	75 801	3	250 142
		(ii) Hard Rock	m <sup>3</sup>	75 801	34	2 577 217
		(iii) Boulder, Class A	m <sup>3</sup>	45 480	78	3 547 463
		(iv) Boulder, Class B	m <sup>3</sup>	15 160	61	924 766
	2.3	<b><u>Dewatering</u></b>	Sum	1	100 000	100 000
		<b>STAGE 2</b>				
3		<b>SITE CLEARANCE</b>				
	3.1	Clear and grub (a) Embankment footprint	ha	2.2	26 546	59 147
	3.2	Remove and grub large trees and tree stumps of girth (a) over 1 m and up to and including 2 m	No	2	1 700	3 400
<b>TOTAL CARRIED FORWARD</b>						<b>21 508 726</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>21 508 726</b>
4		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>				
		(a) Excavate all materials				
		(i) Topsoil at Upstream & Downstream cofferdam	m <sup>3</sup>	6 685	21	140 385
5		<b>EMBANKMENT CONSTRUCTION</b>				
		Earthfill Upstream & Downstream Cofferdam Construction.				
		Forming Embankment				
		Using material from designated borrow areas or commercial				
	5.1	(4) Homogeneous Material	m <sup>3</sup>	163242	50	8 162 100
6		<b>TUNNEL CONSTRUCTION</b>				
	<b>6.1</b>	<b>TUNNEL EXCAVATION</b>				
		(a) Tunnel (Rock class II)	m <sup>3</sup>	57053	2051	117 015 293
	<b>6.2</b>	<b>ROCK SUPPORT</b>				
		(a) Rockbots	m	24192	37	895 104
		(b) Shotcrete	m <sup>3</sup>	803	2500	2 006 948
		(c) Reinforcing mesh	m <sup>2</sup>	5221	26	135 755
	6.3	DEWATERING	Sum	1	550 000	550 000
		<b>STAGE 3</b>				
		<b>MEDIUM PRESSURE PIPELINES</b>				
		Supply, lay, and bed pipes complete with couplings				
		(a) 500 mm diameter concrete pipe (class 75D) in concrete	m	333	80	26 640
		(b) Water control in tunnel	Prov Sum	1	100 000	100 000
		<b>CONVENTIONAL CONCRETE FOR DAMS</b>				
8		<b>PLUG OF TUNNEL</b>				
	8.1	<u>Scheduled Formwork items</u>				
		Class F1				
		(a) Vertical formwork	m <sup>2</sup>	310	550	170 500
	8.2	<u>Scheduled Concrete items</u>				
		Strength and Mass concrete				
		(a) Sealing of bulkheads shaft with mass concrete 25 Mpa/19	m <sup>3</sup>	1 050	1 100	1 155 000
		(c) Plug 25 MPa/19 mm	m <sup>3</sup>	708	1 100	778 250
	8.3	<u>Joints</u>				
		(e) Swellable water stops	m	30	500	15 000
	8.4	<u>Miscellaneous and Sundry items</u>				
		(a) Bulkheads incl reinforcement at 120 kg/m <sup>3</sup>	No	240	3 000	720 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>153 379 700</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)		
10	10.1	<b>SITE CLEARANCE</b>						
		<u>Clear and grub</u>						
		(a) Main & Saddle embankment footprint	ha	7.73	26 546	205 245		
		(b) Spillway	ha	9.40	13 635	128 169		
		(c) Outlet Works	ha	0.41	13 635	5 530		
		10.2	<u>Remove and grub large trees and tree stumps of girth</u>					
			(a) over 1 m and up to and including 2 m					
			(i) Main & saddle embankment footprint	No	7	1 700	11 900	
			(ii) Spillway	No	2	1 700	3 400	
		10.3	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>					
			(a) Main & Saddle embankment footprint	m <sup>3</sup>	24 590	21	516 390	
			(b) Spillway	m <sup>3</sup>	28 625	16	458 000	
		11	11.1	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>				
				<u>Bulk Excavation</u>				
(a) Excavate in all materials (to stockpile or dispose)								
(i) Stockpile								
(1) Embankment footprint (Use in rockfill)	m <sup>3</sup>			0	35	0		
(2) Spillway (Use in Rockfill)	m <sup>3</sup>			0	31	0		
(3) Outlet works (Use in Rockfill)	m <sup>3</sup>			0	35	0		
(b) Extra over for:								
(i) Intermediate excavation	m <sup>3</sup>			0	3	0		
(ii) Hard rock excavation	m <sup>3</sup>			0	34	0		
(iii) Boulder excavation, Class A	m <sup>3</sup>			0	79	0		
(iv) Boulder excavation, Class B	m <sup>3</sup>			0	61	0		
12				<b>FOUNDATION TREATMENT</b>				
				(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	4 737	664.00	3 145 368
		(b) Treatment of Faults, Dykes, Shear Zones and Zones of Poor Rock	m <sup>3</sup>	4 737	660.00	3 126 420		
<b>TOTAL CARRIED FORWARD</b>						<b>7 631 074.99</b>		



ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
13		<b>EMBANKMENT CONSTRUCTION</b>				
		<u>Forming Embankment</u>				
		Using material from designated borrow areas				
	13.1	<b>Main embankment</b>				
		(1) Rockfill	m <sup>3</sup>	1 519 916	71	107 914 036
		(2) Clay Core	m <sup>3</sup>	311 495	50	15 574 750
		(3) Filter	m <sup>3</sup>	87 847	450	39 531 150
	13.2	<b>Saddle embankment</b>				
		(1) Rockfill	m <sup>3</sup>	123 615	71	8 776 665
		(2) Clay Core	m <sup>3</sup>	72 557	50	3 627 850
	(3) Filter	m <sup>3</sup>	30 456	450	13 705 200	
13.3		Rockfill trial (test) Embankment size as per specification	No	1	147 000	147 000
13.4		Overhaul (Clay for 10 km)	m <sup>3</sup> .km	75 996	3.00	227 987
14		<b>SECTION : DRILLING &amp; GROUTING</b>				
	14.1	<b>Main embankment</b>				
		(a) Curtain grouting	m	7 074	850	6 012 900
		(b) Consolidation grouting	m	1 080	850	918 000
	14.2	<b>Saddle Embankment</b>				
		(a) Curtain grouting	m	2 890	850	2 456 500
	(b) Consolidation grouting	m	1 406	850	1 195 100	
15		<b>MECHANICAL ITEMS</b>				
		(a) Valves and gates	Sum			6 840 000
		(b) Cranes & Hoists	Sum			2 330 000
		(c) Structural steelwork	Sum			1 712 971
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>210 970 109.40</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
16	16.1	<u>Scheduled Formwork items</u> Class F4 (a) Vertical (1) Spillway (2) Outlet works (b) Sloped (1) Ogee of spillway (c) Sloping (1) Stilling basin blocks (d) Round (e) Horizontal	m <sup>2</sup>	4 988	530	2 643 640
			m <sup>2</sup>	6 888	530	3 650 640
			m <sup>2</sup>	1 328	581	771 568
			m <sup>2</sup>	33	581	19 173
			m <sup>2</sup>	2 337	581	1 357 797
			m <sup>2</sup>	352	581	204 512
	16.2	<u>Keyways on contraction joints</u> (a) Bridges dimensions to be given in detail design	m	20	100	2 000
	16.3	<u>Scheduled Reinforcement items</u>	t	3 787	8 400	31 809 960
17		<u>Anchors</u> Anchor bars (Y32 @ 2.5 m x 2 m)	t	45	8 500	380 540
18		<u>Scheduled Concrete items</u>				
	18.1	Strength & Mass Concrete (a) Grade 25 MPa/19 mm (1) Spillway, bridges and retaining wall (2) Outlet works	m <sup>3</sup>	30 843	1 500	46 264 500
			m <sup>3</sup>	30 040	1 500	45 060 000
	18.2	Secondary Concrete (a) Grade 25 MPa/19 mm	m <sup>3</sup>	100	1 800	180 000
19		<u>Unformed Surface Finishes</u> Class U2 (Wood-floated) finish (a) Top of chute (b) Top of bridges (c) Chute and Stilling basin floor (d) Outlet works	m <sup>2</sup>	194	23	4 451
			m <sup>2</sup>	197	23	4 531
			m <sup>2</sup>	14 190	23	326 370
			m <sup>2</sup>	772	23	17 756
20	20.1	ADDITIONAL TRANSFER TUNNEL COST DUE TO (a) Additional tunnel	m	2 300	50 000	115 000 000
<b>TOTAL CARRIED FORWARD</b>						<b>247 697 438</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>247 697 438</b>
21		<b>WATERSTOPS, JOINTING AND BEARINGS</b>				
		<u>Scheduled items</u>				
	21.1	Waterstops				
		(a) 250 mm Centre bulb PVC waterstop	m	744	630	468 657
	21.2	Joint sealants				
		(a) Chute wall - 12mm expanding cork	m	744	10	7 439
		(b) Chute wall - 12m Impregnated Bitumen Fibre board	m	744	10	7 439
		(c) Chute wall - 12 x 12 mm Polysulphide sealant	m	744	10	7 439
22		<b>SUB-SOIL DRAINAGE</b>				
		<u>Scheduled items</u>				
	22.1	Excavation for sub-soil drainage system				
		(a) Excavating soft material situated within the following				
		(i) 0 m to 1,5 m	m <sup>3</sup>	177	21	3 725
		(b) Extra over sub-item (a), irrespective of depth, for:				
		(ii) Excavation in hard material	m <sup>3</sup>	89	4	355
	22.2	Natural permeable material in sub-soil drainage systems				
		(b) Sand as specified on detail drawings	m <sup>3</sup>	170	550	93 654
	22.3	Pipes in sub-soil drainage system				
		(c) 110 NB, Class 6, HDPE pressure pipe, non perforated, complying with SANS 533, Part II	m	710	400	283 800
		(d) 75 NB, flexible slotted drainage pipes with smooth bore,	m	215	330	70 950
	22.4	Caps to higher ends of sub-surface drain pipes				
		(a) High end of pipes of Drainex pipes	No	11	50	538
	22.5	Concrete outlet structures for sub-soil drainage systems				
		(a) Concrete 1500 mm dia	No	8	600	4 800
	22.6	Overhaul for material hauled in excess of 1.0 km freehaul				
		(a) Sand for filter material (10 km)	m <sup>3</sup> .km	1 703	3	5 108
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>248 651 341</b>

# **Appendix N**

## **Smithfield Dam site C, Option 2**

### **BOQ**

SITE C, OPTION 2  
with  
OUTLET TO PUMPSTATION

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE RAND	AMOUNT
10		<b>Landscaping</b> (% of 1-9)	%	834 114 425	5	41 705 721
11		<b>Miscellaneous</b> (% of 1-9)	%	834 114 425	15	125 117 164
		<b>SUB TOTAL A</b>				1 000 937 310
12		<b>Preliminary &amp; General</b> (% of sub-total A)	%	1 000 937 310	30	300 281 193
13		<b>Preliminary works</b>				
	13.1	(a) Access road	km	5	400 000	1 840 000.00
	13.2	(b) Electrical supply to site	Sum			1 000 000
	13.3	(c) Construction water to site	Sum			300 000
	13.4	(d) Railhead & materials handling	Sum			
	13.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				1 304 658 503
14		<b>Contingencies</b> (% of sub total B)	%	1 304 658 503	10	130 465 850
		<b>SUB TOTAL C</b>				1 435 124 353
15		<b>Planning design &amp; supervision</b> (% of sub total C)	%	1 435 124 353	15	215 268 653
		<b>SUB TOTAL D</b>				1 650 393 006
16		<b>VAT</b> (% of sub total D)	%	1 650 393 006	0	0
		<b>NETT PROJECT COST</b>				1 650 393 006
17		<b>Cost of relocations</b>	Sum			
18		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				1 650 393 006

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
1	1.1	<b>SITE CLEARANCE</b>					
		<u>Clear and grub</u>					
		(a) Excavation of RCC wall footprint	ha	3.00	26 600.00	79 800.00	
			(b) Saddle footprint	ha	2.20	26 601	58 522
			(c) Outlet works	ha	0.16	13 625	2 180
	1.2	<u>Remove and grub large trees and tree stumps of girth</u>					
		(a) over 1 m and up to and including 2 m					
		(i) Embankment footprint (Main and Saddle)	No	5	1 700	8 500	
			(ii) Outlet works	No	2	1 700	3 400
	1.3	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>					
		(a) RCC excavation - removal of topsoil	m <sup>3</sup>	9 300	21	195 300	
		(b) Saddle topsoil	m <sup>3</sup>	6 600	22	145 200	
		(c) Outlet works	m <sup>3</sup>	480	22	10 560	
2		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>					
		<u>Bulk Excavation</u>					
		(a) Excavate in all materials (to stockpile or dispose)					
		(i) Stockpile					
		(1) RCC foundation excavation	m <sup>3</sup>	224779	30	6 743 370	
		(2) Saddle embankment core excavation	m <sup>3</sup>	5493	30	164 790	
		(3) Outlet works	m <sup>3</sup>	16240	30	487 200	
		(b) Extra over for:					
		(i) Intermediate excavation	m <sup>3</sup>	73 954	4	295 814	
		(ii) Hard rock excavation	m <sup>3</sup>	73 954	34	2 514 422	
		(iii) Boulder excavation, Class A	m <sup>3</sup>	12 326	79	973 722	
		(iv) Boulder excavation, Class B	m <sup>3</sup>	12 326	61	751 862	
	3		<b>FOUNDATION TREATMENT</b>				
		(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	5 173	665	3 439 979	
		(b) Treatment of Faults, Dykes, Shear Zones and Zones of Poor Rock	m <sup>3</sup>	5 173	658	3 403 768	
<b>TOTAL CARRIED FORWARD</b>						<b>19 278 390</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT	
4	4.1	<b>SECTION: EARTHFILL DAM CONSTRUCTION</b>					
		Embankment					
		(a) Trial Embankment	No			146 619	
		(b) Forming Embankment (Saddle)					
		(1) Earthfill	m <sup>3</sup>	120987	46	5 565 402	
		(2) Filters	m <sup>3</sup>	37443	431	16 137 933	
		(3) Riprap	m <sup>3</sup>	271	351	95 121	
		(4) Clay core	m <sup>3</sup>	68524	50	3 426 200	
		SCHEDULED REINFORCMENT ITEMS					
		5	5.1	<b>SECTION: CONVENTIONAL CONCRETE FOR DAMS</b>			
SCHEDULED FORMWORK ITEMS							
Class F2							
(a) Vertical							
(1) Wall (downstream and upstream)	m <sup>2</sup>			42 270	610	25 784 700	
(2) Outlet structure to pumpstation	m <sup>2</sup>			6 804	550	3 742 200	
(c) Forming of Gallery							
(1) Horizontal	m			70	2 000	140 000	
(2) Sloping	m			370	3 000	1 110 000	
5.2	SCHEDULED REINFORCEMENT ITEMS			t	2 619	8 400	22 002 624
5.3	SCHEDULED CONCRETE ITEMS						
Strength & Mass Concrete							
(a) Grade 25 MPa/19 mm							
(1) Apron (160m x 1m x 23m)	m <sup>3</sup>			3 680	1 768	6 506 240	
(2) Transfer intake to pumpstation	m <sup>3</sup>			29 062	1 500	43 593 000	
Secondary Concrete							
(a) Grade 25 MPa/19 mm	m <sup>3</sup>			200	1 800	360 000	
5.4	UNFORMED SURFACE FINISH						
Class U2 (Wood-floated) finish							
(a) Concrete wall structure	m <sup>2</sup>	17 871	50	893 550			
(b) Apron (downstream)	m <sup>2</sup>	3 680	50	184 000			
(c) Gallery floor	m <sup>2</sup>	440	50	22 000			
(d) Transfer intake	m <sup>2</sup>	862	50	43 100			
<b>TOTAL CARRIED FORWARD</b>						<b>129 752 689</b>	



ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
<b>TOTAL BROUGHT FORWARD</b>						<b>129 752 689</b>
6		<b>SECTION: ROLLER COMPACTED CONCRETE FOR DAMS</b>				
	6.1	Roller Compacted Concrete (a) Grade 15 MPa concrete (1) Wall	m <sup>3</sup>	447 789	950	425 399 550
		(b) Immersion Vibrated Roller Compacted Concrete (IVRCC) (1) 600 mm thick, upstream	m <sup>2</sup>	12 783	350	4 474 050
		(2) 600 mm thick, downstream	m <sup>2</sup>	51 924	350	18 173 400
	6.2	RCC Bedding Mortar (a) Grade 15 MPa concrete	m <sup>2</sup>	4 693	100	469 290
	6.3	Test Section	No.	1	840 000	840 000
7		<b>SECTION: DRILLING &amp; GROUTING</b>				
	7.1	RCC (a) Curtain grouting	m <sup>3</sup>	7 975	850	6 778 750
		(b) Consolidation grouting	m <sup>3</sup>	2 412	850	2 050 200
	7.2	Saddle (a) Curtain grouting	m <sup>3</sup>	2 468	850	2 097 800
		(b) Consolidation grouting	m <sup>3</sup>	1 406	850	1 195 100
8		<b>SECTION: WATERSTOPS, JOINTING AND BEARINGS</b>				
		SCHEDULED ITEMS				
		Waterstops	m	1420	750	1 065 000
9		<b>MECHANICAL ITEMS</b>				
		(a) Valves and gates	Sum			6 840 000
		(b) Cranes & Hoists	Sum			2 330 000
		(c) Structural steelwork	Sum			1 712 971
20	20.1	ADDITIONAL TRANSFER TUNNEL COST DUE TO FURTHER SITE (a) Additional tunnel	m	2 300	50 000	115 000 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>718 178 800</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
11	11.1	<b>SITE CLEARANCE</b> <u>Clear and grub</u> (a) Footprint	ha	0.20	26 546	5 309
	11.2	<u>Remove and grub large trees and tree stumps of</u> (a) over 1 m and up to and including 2 m  (i) Footprint	No	1	1 700	1 700
	11.3	Remove topsoil to nominal depth of 300 mm and (a) Footprint	m <sup>3</sup>	600	21	12 600
12	12.1	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND</b> <b>Bulk Excavation</b> (a) Excavate in all materials (to stockpile or  (i) Stockpile  (1) Embankment footprint	m <sup>3</sup>	46400	35	1 624 000
		(b) Extra over for:  (i) Intermediate excavation	m <sup>3</sup>	13 920	3	44 544
		(ii) Hard rock excavation	m <sup>3</sup>	9 280	34	315 520
		(iii) Boulder excavation, Class A	m <sup>3</sup>	2 320	79	182 120
		(iv) Boulder excavation, Class B	m <sup>3</sup>	2 320	61	141 520
	12.2	<u>Foundation Treatment</u> (a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	600	664	398 400
		(b) Treatment of Faults, Dykes, Shear Zones and	m <sup>3</sup>	600	660	398 400
13		<u>Scheduled Reinforcement items</u> Steel  (a) High tensile steel 16 mm diameter and over	t	3 430	8 400	28 809 984
14	14.1	<u>Scheduled Concrete items</u> Blinding layer and Dental Concrete  (b) Dental concrete (Class 15/38)	m <sup>3</sup>	100	1 869	186 900
	14.2	Strength and Mass Concrete (a) Strength Concrete (Class 30/38)	m <sup>3</sup>	42 872	1 500	64 308 000
	14.3	Secondary concrete (Class 30/19)	m <sup>3</sup>	100	1 870	187 000
15		<u>Unformed Surface Finishes</u> Class U2 finish	m <sup>2</sup>	1 422	29	41 238
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>96 657 235</b>

SITE C, OPTION 2  
with  
OUTLET TO TUNNEL

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
					RAND	
11		<b>Landscaping</b> (% of 1-9)	%	742 214 661	5	37 110 733
12		<b>Miscellaneous</b> (% of 1-9)	%	742 214 661	15	111 332 199
		<b>SUB TOTAL A</b>				890 657 593
13		<b>Preliminary &amp; General</b> (% of sub-total A)	%	890 657 593	30	267 197 278
14		<b>Preliminary works</b>				
	13.1	(a) Access road	km	5	400 000	1 840 000.00
	13.2	(b) Electrical supply to site	Sum			1 000 000
	13.3	(c) Construction water to site	Sum			300 000
	13.4	(d) Railhead & materials handling	Sum			
	13.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				1 161 294 871
14		<b>Contingencies</b> (% of sub total B)	%	1 161 294 871	10	116 129 487
		<b>SUB TOTAL C</b>				1 277 424 358
15		<b>Planning design &amp; supervision</b> (% of sub total C)	%	1 277 424 358	15	191 613 654
		<b>SUB TOTAL D</b>				1 469 038 012
16		<b>VAT</b> (% of sub total D)	%	1 469 038 012	0	0
		<b>NETT PROJECT COST</b>				1 469 038 012
17		<b>Cost of relocations</b>	Sum			
18		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				1 469 038 012

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
1	1.1	<b>SITE CLEARANCE</b>					
		<u>Clear and grub</u>					
		(a) Excavation of RCC wall footprint	ha	3.00	26 600.00	79 800.00	
			(b) Saddle footprint	ha	2.20	26 601	58 522
			(c) Outlet works	ha	0.41	13 625	5 586
	1.2	<u>Remove and grub large trees and tree stumps of girth</u>					
		(a) over 1 m and up to and including 2 m					
		(i) Embankment footprint (Main and Saddle)	No	5	1 700	8 500	
			(ii) Outlet works	No	3	1 700	5 100
	1.3	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>					
		(a) RCC excavation - removal of topsoil	m <sup>3</sup>	9 300	21	195 300	
		(b) Saddle topsoil	m <sup>3</sup>	6 600	22	145 200	
		(c) Outlet works	m <sup>3</sup>	1 217	22	26 774	
2		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>					
		<u>Bulk Excavation</u>					
		(a) Excavate in all materials (to stockpile or dispose)					
		(i) Stockpile					
		(1) RCC foundation excavation	m <sup>3</sup>	224779	30	6 743 370	
		(2) Saddle embankment core excavation	m <sup>3</sup>	5493	30	164 790	
		(3) Outlet works	m <sup>3</sup>	16471	30	494 127	
		(b) Extra over for:					
		(i) Intermediate excavation	m <sup>3</sup>	74 023	4	296 091	
		(ii) Hard rock excavation	m <sup>3</sup>	74 023	34	2 516 778	
		(iii) Boulder excavation, Class A	m <sup>3</sup>	12 337	79	974 634	
		(iv) Boulder excavation, Class B	m <sup>3</sup>	12 337	61	752 566	
	3		<b>FOUNDATION TREATMENT</b>				
		(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>	5 923	665	3 938 729	
		(b) Treatment of Faults, Dykes, Shear Zones and Zones of Poor Rock	m <sup>3</sup>	5 923	658	3 897 268	
<b>TOTAL CARRIED FORWARD</b>						<b>20 303 136</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT	
4	4.1	<b>SECTION: EARTHFILL DAM CONSTRUCTION</b>					
		Embankment					
		(a) Trial Embankment	No			146 619	
		(b) Forming Embankment (Saddle)					
		(1) Earthfill	m <sup>3</sup>	120987	46	5 565 402	
5	5.1	<b>SECTION: CONVENTIONAL CONCRETE FOR DAMS</b>					
		SCHEDULED FORMWORK ITEMS					
		Class F2					
		(a) Vertical					
		(1) Wall (downstream and upstream)	m <sup>2</sup>	42 270	610	25 784 700	
		(2) Outlet structure to pumpstation	m <sup>2</sup>	6 888	550	3 788 400	
		(c) Forming of Gallery					
		(1) Horizontal	m	70	2 000	140 000	
		(2) Sloping	m	370	3 000	1 110 000	
		(e) Round	m <sup>2</sup>	2 337	581	1 357 797	
		(f) Horizontal	m <sup>2</sup>	352	581	204 512	
		5.2	SCHEDULED REINFORCEMENT ITEMS	t	2 698	8 400	22 659 840
		5.3	SCHEDULED CONCRETE ITEMS				
			Strength & Mass Concrete				
			(a) Grade 25 MPa/19 mm				
	(1) Apron (160m x 1m x 23m)	m <sup>3</sup>	3 680	1 768	6 506 240		
	(2) Transfer intake to pumpstation	m <sup>3</sup>	30 040	1 500	45 060 000		
	Secondary Concrete						
	(a) Grade 25 MPa/19 mm	m <sup>3</sup>	200	1 800	360 000		
5.4	UNFORMED SURFACE FINISH						
	Class U2 (Wood-floated) finish						
	(a) Concrete wall structure	m <sup>2</sup>	17 871	50	893 550		
	(b) Apron (downstream)	m <sup>2</sup>	3 680	50	184 000		
	(c) Gallery floor	m <sup>2</sup>	440	50	22 000		
	(d) Transfer intake	m <sup>2</sup>	862	50	43 100		
<b>TOTAL CARRIED FORWARD</b>						<b>133 485 414</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
<b>TOTAL BROUGHT FORWARD</b>						<b>133 485 414</b>
6		<b>SECTION: ROLLER COMPACTED CONCRETE FOR DAMS</b>				
	6.1	Roller Compacted Concrete (a) Grade 15 MPa concrete (1) Wall	m <sup>3</sup>	447 789	950	425 399 550
		(b) Immersion Vibrated Roller Compacted Concrete (IVRCC) (1) 600 mm thick, upstream	m <sup>2</sup>	12 783	350	4 474 050
		(2) 600 mm thick, downstream	m <sup>2</sup>	51 924	350	18 173 400
	6.2	RCC Bedding Mortar (a) Grade 15 MPa concrete	m <sup>2</sup>	4 693	100	469 290
	6.3	Test Section	No.	1	840 000	840 000
7		<b>SECTION: DRILLING &amp; GROUTING</b>				
	7.1	RCC (a) Curtain grouting	m <sup>3</sup>	7 975	850	6 778 750
		(b) Consolidation grouting	m <sup>3</sup>	2 412	850	2 050 200
	7.2	Saddle (a) Curtain grouting	m <sup>3</sup>	2 468	850	2 097 800
		(b) Consolidation grouting	m <sup>3</sup>	1 406	850	1 195 100
8		<b>SECTION: WATERSTOPS, JOINTING AND BEARINGS</b>				
		<b>SCHEDULED ITEMS</b>				
		Waterstops	m	1420	750	1 065 000
9		<b>MECHANICAL ITEMS</b>				
		(a) Valves and gates	Sum			6 840 000
		(b) Cranes & Hoists	Sum			2 330 000
		(c) Structural steelwork	Sum			1 712 971
10		<b>ADDITIONAL TRANSFER TUNNEL COST DUE TO</b>				
	10.1	(a) Additional tunnel	m	2 300	50 000	115 000 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>721 911 525</b>

# **Appendix O**

## **Baynesfield balancing dam, Option 2 BOQ**



BAYNESFIELD DAM  
OPTION 2

No	PAY REF	DESCRIPTION	UNIT	QUANTITY	RATE RAND	AMOUNT
15		<b>Landscaping</b> (% of 1-9)	%	447 907 342	5	22 395 367
16		<b>Miscellaneous</b> (% of 1-9)	%	447 907 342	15	67 186 101
		<b>SUB TOTAL A</b>				537 488 810
17		<b>Preliminary &amp; General</b> (% of sub-total A)	%	537 488 810	30	161 246 643
18		<b>Preliminary works</b>				
	18.1	(a) Access road	km	2.5	400 000	1 000 000
	18.2	(b) Electrical supply to site	Sum			1 000 000
	18.3	(c) Construction water to site	Sum			300 000
	18.4	(d) Railhead & materials handling	Sum			
	18.5	(e) Accommodation	Sum			300 000
		<b>SUB TOTAL B</b>				701 335 453
19		<b>Contingencies</b> (% of sub total B)	%	701 335 453	10	70 133 545
		<b>SUB TOTAL C</b>				771 468 999
20		<b>Planning design &amp; supervision</b> (% of sub total C)	%	771 468 999	15	115 720 350
		<b>SUB TOTAL D</b>				887 189 348
21		<b>VAT</b> (% of sub total D)	%	887 189 348	0	0
		<b>NETT PROJECT COST</b>				887 189 348
22		<b>Cost of relocations</b>	Sum			
23		<b>Cost of land acquisition</b>	Sum			
		<b>TOTAL PROJECT COST</b>				887 189 348

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
		<b>STAGE 1</b>				
1	1.1	<b>SITE CLEARANCE</b> Clear and grub				
		(a) Portal footprints	ha	0.23	26 546	6 087
		Remove and grub large trees and tree stumps of girth				
		(a) over 1 m and up to and including 2m	No	5	1 700	8 500
	1.2	Remove topsoil to nominal depth of 150 mm and stockpile	m <sup>3</sup>	344	20	6 879
2		<b>EXCAVATION AND BACKFILL FOR DAMS AND</b>				
		Bulk Excavation				
	2.1	<b>Inlet portal</b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	3 195	21	67 095
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	799	3	2 636
		(ii) Hard Rock	m <sup>3</sup>	799	34	27 158
		(iii) Boulder, Class A	m <sup>3</sup>	320	78	24 921
		(iv) Boulder, Class B	m <sup>3</sup>	160	61	9 745
	2.2	<b>Outlet Portal</b>				
		(a) Excavate in all materials				
		(i) Excavation (stockpile)	m <sup>3</sup>	127 969	21	2 687 349
		(b) Extra over for:				
		(i) Intermediate	m <sup>3</sup>	31 992	3	105 574
		(ii) Hard Rock	m <sup>3</sup>	31 992	34	1 087 737
		(iii) Boulder, Class A	m <sup>3</sup>	19 195	78	1 497 237
		(iv) Boulder, Class B	m <sup>3</sup>	6 398	61	390 305
3		<b>EMBANKMENT CONSTRUCTION</b>				
		Dewatering	Sum	1	100 000	100 000
4		First stage cofferdam	Sum	1		3 831 152
		<b>STAGE 2</b>				
4		<b>SITE CLEARANCE</b>				
	4.1	Clear and grub				
		(a) Embankment footprint	ha	3	26 546	76 030
		Remove and grub large trees and tree stumps of girth				
	4.2	(a) over 1 m and up to and including 2 m	No	2	1 700	3 400
5		<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>				
		(a) Excavate all materials				
		(i) Excavate and dispose footprint of Upstream cofferdam	m <sup>3</sup>	28 656	21	601 776
<b>TOTAL CARRIED FORWARD</b>						<b>10 533 581</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>10 533 581</b>
6		<b>EMBANKMENT CONSTRUCTION</b> Earthfill Upstream & Downstream Cofferdam Construction. Forming Embankment Using material from designated borrow areas or commercial sources				
		(4) Homogeneous Material	m <sup>3</sup>	216245	50	10 812 250
7		<b>TUNNEL CONSTRUCTION</b>				
	7.1	<b>Tunnel excavation</b>				
		(a) Tunnel (Rock class II)	m <sup>3</sup>	12735	2 051	26 113 459
	7.2	<b>Rock support</b>				
		(a) Rockbolts	m	5400	37	197 710
		(b) Shotcrete	m <sup>3</sup>	652	2 500	1 630 192
		(c) Reinforcing mesh	m <sup>2</sup>	4241	26	110 270
	7.3	Dewatering	Sum	1	550 000	550 000
		<b>STAGE 3</b>				
8		<b>MEDIUM PRESSURE PIPELINES</b> Supply, lay, and bed pipes complete with couplings				
		(a) 500 mm diameter concrete pipe (class 75D) in concrete	m	225	80	18 000
		(b) Water control in tunnel	Prov Sum	1	100 000	100 000
9		<b>Plug of Tunnel (Stage 3)</b>				
	9.1	<u>Scheduled Formwork items</u> Class F1				
		(a) Vertical formwork	m <sup>2</sup>	124	550	68 200
	9.2	<u>Scheduled Concrete items</u> Strength and Mass concrete				
		(a) Sealing of bulkheads shaft with mass concrete 25 Mpa/19 mm	m <sup>3</sup>	420	1 100	462 000
		(c) Plug 25 MPa/19 mm	m <sup>3</sup>	283	1 100	311 300
	9.3	<u>Joints</u>				
		(e) Swellable water stops	m	12	500	6 000
	9.4	<u>Miscellaneous and Sundry items</u>				
		(a) Bulkheads incl reinforcement at 120 kg/m <sup>3</sup>	No	96	3 000	288 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>51 200 963</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)	
6	6.1	<b>SITE CLEARANCE</b>					
		<u>Clear and grub</u>					
			(a) Embankment footprint	ha	11.03	26 546	292 670
			(b) Spillway	ha	2.94	13 635	40 079
	6.2		<u>Remove and grub large trees and tree stumps of girth</u>				
			(a) over 1 m and up to and including 2 m				
			(i) Embankment footprint	No	5	1 700	8 500
			(ii) Spillway	No	2	1 700	3 400
	6.3		<u>Remove topsoil to nominal depth of 300 mm and stockpile</u>				
			(a) Embankment footprint	m <sup>3</sup>	33 075	21	694 575
		(b) Spillway	m <sup>3</sup>	8 818	16	141 091	
7	7.1	<b>EXCAVATIONS AND BACKFILL FOR DAMS AND WATERWAYS</b>					
		<u>Bulk Excavation</u>					
		(a) Excavate in all materials (to stockpile or dispose)					
		(i) Stockpile					
		(1) Embankment footprint (Use in rockfill)	m <sup>3</sup>	0	35	0	
		(2) Spillway (Use in Rockfill)	m <sup>3</sup>	0	31	0	
		(3) Portals (Use in Rockfill)	m <sup>3</sup>	0	35	0	
		(b) Extra over for:					
		(i) Intermediate excavation	m <sup>3</sup>	0	3	0	
		(ii) Hard rock excavation	m <sup>3</sup>	0	34	0	
		(iii) Boulder excavation, Class A	m <sup>3</sup>	0	79	0	
		(iv) Boulder excavation, Class B	m <sup>3</sup>	0	61	0	
		7.3		<u>Foundation Treatment</u>			
(a) Treatment of Joints, Cracks and Fissures	m <sup>3</sup>			1 422	664	944 208	
		(b) Treatment of Faults, Dykes, Shear Zones and Zones of Poor Rock	m <sup>3</sup>	1 422	660	938 520	
<b>TOTAL CARRIED FORWARD</b>						<b>3 063 043</b>	

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
8		<b>EMBANKMENT CONSTRUCTION</b>				
	8.1	<u>Forming Embankment</u>				
		Using material from designated borrow areas				
		(1) Rockfill	m <sup>3</sup>	1 707 255	71	121 215 105
		(2) Clay Core	m <sup>3</sup>	380 911	50	19 045 550
		(3) Filter	m <sup>3</sup>	156 846	440	69 012 240
		Overhaul (Clay for 10 km)	m <sup>3</sup> .km	85 363	3	256 088
9		<b>SECTION : DRILLING &amp; GROUTING</b>				
		(a) Curtain grouting	m	8 349	13 457	112 352 493
		(b) Consolidation grouting	m	2 550	2 820	7 191 000
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>329 072 476</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
10	10.1	<b>CONVENTIONAL CONCRETE FOR DAMS</b>				
		<u>Scheduled Formwork items</u>				
		Class F4				
		(a) Vertical				
		(1) Spillway	m <sup>2</sup>	2 656	550	1 460 800
		(2) Outlet works	m <sup>2</sup>	11 643	550	6 403 650
		(3) Transfer water outlet	m <sup>2</sup>	630	550	346 500
		(b) Sloped				
		(1) Ogee of spillway - Drawing (05/02)	m <sup>2</sup>	576	550	316 800
		(2) Transfer water outlet	m <sup>2</sup>	1 533	550	843 150
		(c) Sloping				
		(1) Stilling basin blocks	m <sup>2</sup>	33	550	18 150
		(e) Horizontal Outlet works	m <sup>2</sup>	855	550	470 250
	10.2	Keyways on contraction joints				
	(a) Bridges dimensions to be given in detail design	m	20	100	2 000	
	10.3	<u>Scheduled Reinforcement items</u>	t	387	8 400	3 250 800
	10.4	<u>Anchors</u>				
		Anchor bars (Y32 @ 2.5 m x 2 m)	t	15	8 500	126 085
	10.5	<u>Scheduled Concrete items</u>				
		Strength & Mass Concrete				
	(a) Grade 25 MPa/19 mm					
	(1) Spillway, bridges and retaining wall	m <sup>3</sup>	3 743	1 500	5 614 500	
	(2) Outlet works	m <sup>3</sup>	1 899	1 500	2 848 500	
(3) Transfer structure	m <sup>3</sup>	8 820	1 500	13 230 000		
	Secondary Concrete					
(a) Grade 25 MPa/19 mm	m <sup>3</sup>	100	1 800	180 000		
10.6	<u>Unformed Surface Finishes</u>					
	Class U2 (Wood-floated) finish					
(a) Top of chute	m <sup>2</sup>	135	23	3 105		
(b) Top of bridges	m <sup>2</sup>	200	23	4 600		
(c) Chute and Stilling basin floor	m <sup>2</sup>	4 500	23	103 500		
(d) Outlet works	m <sup>2</sup>	595	25	14 880		
11		<b>MECHANICAL ITEMS</b>				
	(a) Valves and gates	Sum			3 420 000	
	(b) Cranes & Hoists	Sum			1 713 000	
	(c) Structural steelwork	Sum			1 712 971	
	(d) Pipe (2 x 1diam steel pipe)	m	426	10 000	4 260 000	
	(e) Transfer outlet pipes (2 x 2,5 m steel)	m	20	25 000	500 000	
12		<b>ESKOM LINE DEVIATION</b>				
	(a) Pre Engineering study	Sum			1 609 757	
	(b) Deviation	km	2.6290	6 000 000	15 774 000	
<b>TOTAL CARRIED FORWARD</b>						<b>64 226 998</b>

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE (R)	AMOUNT (R)
<b>TOTAL BROUGHT FORWARD</b>						<b>64 226 998</b>
<b>13</b>		<b>WATERSTOPS, JOINTING AND BEARINGS</b>				
		<u>Scheduled items</u>				
	13.1	Waterstops				
		(a) 250 mm Centre bulb PVC waterstop	m	215	630	135 198
	13.2	Joint sealants				
		(a) Chute wall - 12mm expanding cork	m	215	10	2 146
		(b) Chute wall - 12m Impregnated Bitumen Fibre board	m	215	10	2 146
		(c) Chute wall - 12 x 12 mm Polysulphide sealant	m	215	10	2 146
<b>14</b>		<b>SUB-SOIL DRAINAGE</b>				
		<u>Scheduled items</u>				
	14.1	Excavation for sub-soil drainage system				
		(a) Excavating soft material situated within the following depth ranges below the surface level:				
		(i) 0 m to 1,5 m	m <sup>3</sup>	56	21	1 181
		(b) Extra over sub-item (a), irrespective of depth, for:				
		(ii) Excavation in hard material	m <sup>3</sup>	28	4	113
	14.2	Natural permeable material in sub-soil drainage systems				
		(b) Sand as specified on detail drawings	m <sup>3</sup>	54	550	29 700
	14.3	Pipes in sub-soil drainage system				
		(c) 110 NB, Class 6, HDPE pressure pipe, non perforated, complying with SANS 533, Part II	m	225	400	90 000
		(d) 75 NB, flexible slotted drainage pipes with smooth bore, "Drainex" or equivalent by Kaytech	m	225	330	74 250
	14.4	Caps to higher ends of sub-surface drain pipes				
		(a) High end of pipes of Drainex pipes	No	11	50	563
	14.5	Concrete outlet structures for sub-soil drainage systems complete as per drawings				
		(a) Concrete 1500 mm dia	No	8	600	4 800
	14.6	Overhaul for material hauled in excess of 1.0 km freehaul				
		(a) Sand for filter material (10 km)	m <sup>3</sup> .km	540	3	1 620
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>						<b>64 570 860</b>