



water affairs

Department:
Water Affairs
REPUBLIC OF SOUTH AFRICA



REPORT NO: P WMA 11/U10/00/3312/3/2/4


The uMkhomazi Water Project Phase 1: Module 1: Technical Feasibility Study: Raw Water

SUPPORTING DOCUMENT 4:

LANGA BALANCING DAM: MATERIALS AND
GEOTECHNICAL INVESTIGATION

FINAL

NOVEMBER 2014



Project name: The uMkhomazi Water Project Phase 1: Module 1: Technical Feasibility Study Raw Water

Report title: Geotechnical report

Sub-report title: Supporting document 4: Langa Balancing Dam: Materials and geotechnical investigation

Author: A van Schalkwyk

PSP project reference no.: J01763

DWA Report no.: P WMA 11/U10/00/3312/3/2/4


Status of report: Final

First issue: January 2014


Final issue: November 2014

CONSULTANTS: AECOM (BKS*) in association with AGES, MM&A and Urban-Econ.

Approved for Consultants:



A van Schalkwyk
Sub-Task Leader



DB Badenhorst
Task Leader

DEPARTMENT OF WATER AFFAIRS (DWA): Directorate: Options Analysis

Approved for DWA:



K Bester
Chief Engineer: Options Analysis (East)



LS Mabuda
Chief Director: Integrated Water Resource Planning

* BKS (Pty) Ltd was acquired by AECOM Technology Corporation on 1 November 2012

Prepared by:

AECOM

AECOM SA (Pty) Ltd
PO Box 3173
Pretoria
0001

In association with:
Africa Geo-Environmental Services



Mogoba Maphuthi and Associates



Mogoba Maphuthi & Associates (MMA)

Urban-Econ




PREAMBLE

In June 2014, two years after the commencement of the uMkhomazi Water Project Phase 1 Feasibility Study, a new Department of Water and Sanitation was formed by Cabinet, including the formerly known Department of Water Affairs.

In order to maintain consistent reporting, all reports emanating from Module 1 of the study will be published under the Department of Water Affairs name.

The uMkhomazi Water Project Phase 1

LIST OF REPORTS



Executive summary

The objectives of this report are to describe the results of construction materials and geotechnical investigations for the proposed Langa Balancing Dam as part of the uMkhomazi Water Project. The following aspects are dealt with:

- ◆ *Foundations for earth core rockfill or zoned embankment dams both with approach channel, side spillway with chute and plunge pool on the left flank.*
- ◆ *Alternatively, foundations for a concrete faced rockfill dam with approach channel, side spillway with chute and plunge pool on the left flank.*
- ◆ *Construction material sources for the above dams.*

Information from published geological maps was used to describe the general geology of the area, while the site geology was determined by means of surface mapping, test pits and rotary core drilling.

The area around the site is underlain by rocks of the Pietermaritzburg Formation of the Eccca Group, comprising shales and siltstones with subordinate sandstones. One near-horizontal dolerite sill had intruded concordantly into the sedimentary strata.

Due to the presence of an extensive wetland in the dam basin and of cultivated lands on the left flank, environmental restrictions were placed on seismic surveys, test pits and boreholes in certain areas.

Seismic refraction surveys were conducted across the dam centre line. Although the seismic velocities tended to over-estimate the depth of sound rock, they were useful in showing the presence of the dolerite sill below a cover of shale and also to identify the position of a fault.

A Probabilistic Seismic Hazard Analysis (PSHA) for both the Smithfield Dam and Langa Balancing Dam sites was conducted by Dr A Kijko of the Natural Hazards Assessment Consultancy and classified the site as of low seismic risk. The Langa Balancing Dam site is located in the same seismo-tectonic province and the seismic risk is considered to be similarly low.

Four potential sources for construction materials were investigated, namely (i) spoil from the tunnel excavation, (ii) material excavated for the tunnel outlet portal, (iii) material excavated from the spillway approach area, and (iv) material from a quarry located below FSL in the dam basin.

It appears that none of the available materials qualify as impervious fill, and that the available quantity of semi-pervious material is not quite sufficient to provide twice the required volume for a zoned embankment dam.

A considerable volume of soft rockfill (weathered shale) will have to be removed from the quarry in order to reach the underlying hard shale and dolerite for rockfill. This soft material can be used in certain zones of any of the alternative embankment dam types.

There is sufficient hard shale and dolerite rockfill for construction of a Concrete Faced Rockfill (CFR) Dam or Earth Core Rockfill (ECR) Dam. For any of these dam types, durable dolerite may have to be imported from a commercial quarry (Pietermaritzburg) to serve as protective layer above the shale or dolerite/shale mixture from the tunnel excavation and the quarry. However, it is possible that some or all of this dolerite might be obtained from the quarry but this will require further investigation.

Spoil from the tunnel excavation is expected to have the properties of G5 gravel and can be compacted to form part of a rockfill embankment. Due to the absence of impervious core material, consideration will have to be given to a CFR dam or a CCR dam with impervious core comprising a mixture of soil and bentonite. The CFR option appears to be the more feasible, since the available soils contain too much clay to mix with bentonite.

For the shells of an earth embankment, 0.6 m – 1.5 m organic topsoil and loose transported soil has to be removed along the centre line and founding will take place on stiff transported sandy clay or weak completely weathered shale or weak residual dolerite.

For the shells of a rockfill embankment, between 1.6 m and 5.3 m of colluvium and residual soil/completely weathered shale has to be removed along most parts of the centre line. However in an area on the right flank, weak completely weathered shale and dolerite extend to a depth of over 17 m and will have to be removed.

*For the **core of an embankment dam** the depth of excavation will vary between 3.1 m to 5 m along the centre line. The depth for the **plinth of a concrete faced rockfill dam** will be the same or slightly deeper than for a core trench, except in an area on the right flank where it is much deeper.*

*Excavation depths for a **concrete gravity dam** will reach between 5 m and 8.5 m in the river section and up to 23 m along a section of the right flank.*

It will be necessary to make provision for a grout curtain to a depth of about 66% of the water head along the centre line.

A spillway control structure and concrete lined return channel can be founded on moderately weathered shale at an average depth of about 5.5 m. A stilling basin and apron will have to be provided at the end of the chute.

The risk for slope failures around the rim of the reservoir that might endanger the dam wall is considered negligible.

As a result of environmental restrictions on the positioning of seismic lines, test pits and boreholes, this investigation was limited.

Recommendations are made for additional test pitting, core drilling, sampling and laboratory tests during the design stage to confirm the properties and volumes of construction materials actually required and to confirm founding conditions for the selected type of dam and spillway structure.

TABLE OF CONTENTS

	Page
1 INTRODUCTION.....	1-1
1.1 Background to the project	1-1
1.2 Study area.....	1-2
1.3 Objective of the study.....	1-3
1.4 Scope of this report	1-4
1.5 Purpose of the report	1-5
1.6 Contents of the report	1-5
2 PREVIOUS INVESTIGATIONS.....	2-1
3 PRESENT INVESTIGATIONS	3-1
3.1 Need for geotechnical investigations	3-1
3.1.1 <i>Geological mapping</i>	3-1
3.1.2 <i>Seismic risk analysis</i>	3-1
3.1.3 <i>Seismic refraction survey</i>	3-1
3.1.4 <i>Test pitting, soil sampling and laboratory testing</i>	3-1
3.1.5 <i>Core drilling</i>	3-1
3.1.6 <i>Reservoir slope stability</i>	3-2
3.2 Geological mapping	3-2
3.3 Seismic hazard analysis.....	3-2
3.4 Seismic refraction survey	3-3
3.5 Test pits	3-3
3.6 Rotary core drilling	3-4
3.7 Laboratory testing	3-5
3.8 Reservoir slope stability study.....	3-6
4 GEOLOGY.....	4-1
5 CONSTRUCTION MATERIALS INVESTIGATION	5-1
5.1 Test pits and boreholes	5-2
5.2 Laboratory tests on soil samples	5-6
5.3 Laboratory tests on rock samples.....	5-8
5.3.1 <i>Unconfined compressive strength and E-Modulus</i>	5-8
5.3.2 <i>Tests on slightly weathered and moderately weathered shale</i>	5-9
5.3.3 <i>Exposure tests on slightly weathered and moderately weathered shale</i>	5-10

5.3.4	<i>Tests on highly and moderately weathered shale</i>	5-13
5.4	Available volumes of various materials.....	5-14
5.5	Material parameters for design.....	5-15
6	GEOTECHNICAL INVESTIGATIONS.....	6-1
6.1	Seismic refraction surveys	6-1
6.2	Core drilling and water testing.....	6-2
6.2.1	<i>Discussion of drilling results</i>	6-6
6.2.2	<i>Founding conditions for alternative dam types</i>	6-7
6.3	Spillway control and return channel.....	6-10
7	RESERVOIR RIM STABILITY	7-1
7.1	Reservoir rim stability	7-1
8	CONCLUSIONS	8-1
8.1	Available information.....	8-1
8.2	General geology.....	8-1
8.3	Seismic refraction surveys	8-1
8.4	Seismic risk analysis	8-1
8.5	Materials investigation.....	8-2
8.6	Geotechnical investigation	8-3
8.7	Stability of reservoir rim.....	8-4
9	RECOMMENDATIONS.....	9-1
10	REFERENCES.....	10-1

LIST OF FIGURES

- Figure A1.1 Locality map: Study area of the uMWP
- Figure A4.1 Regional geological map
- Figure A4.2 Geological map of dam site
- Figure A5.1 Plan showing layout of proposed structures, seismic lines, test pits and boreholes
- Figure A5.2 Proposed tunnel outlet portal excavation
- Figure A5.3 Section B-B: Long section through proposed quarry
- Figure A5.4 Section C-C: Cross section through proposed quarry
- Figure A6.1 Section A-A: Centre line with seismic and geology
- Figure A6.2 Section A-A: Centre line with core trench and concrete gravity excavation
- Figure A6.3 Section A-A: Centre line with rockfill shell excavation
- Figure A6.4 Section A-A: Centre line with rockfill plinth excavation

LIST OF TABLES

	Page
Table 3.1: Summary of test pits.....	3-4
Table 3.2: Summary of cored boreholes.....	3-5
Table 5.1: Approximate volumes of construction material (2 x required).....	5-1
Table 5.2: Typical specifications for earth fill materials (Badenhorst, 1988).....	5-2
Table 5.3: Summary of test pit results	5-4
Table 5.4: Summary of results from boreholes in the quarry.....	5-5
Table 5.5: Summary of laboratory foundation indicator test.....	5-7
Table 5.6: Summary of other laboratory test results	5-8
Table 5.7: Summary of laboratory tests on slightly weathered and unweathered shale and dolerite	5-9
Table 5.8: Summary of laboratory test on crushed slightly weathered and moderately weathered shale	5-10
Table 5.9: Summary of laboratory tests on slightly weathered shale	5-11
Table 5.10: Summary of laboratory tests on moderately weathered shale.....	5-12
Table 5.11: Summary of laboratory tests on crushed rock cores	5-14
Table 5.12: Estimated volumes of embankment materials from borrow areas, tunnel spoil and the tunnel outlet portal	5-15
Table 5.13: Estimated material parameters for design.....	5-17
Table 6.1: Summary of boreholes results at the dam site	6-3
Table 6.2: Summary of water pressure test results.....	6-5
Table 6.3: Water rest levels in boreholes.....	6-6
Table 6.4: Recommended excavation depths at the various borehole positions.....	6-9
Table 8.1: Estimated volume of embankment materials from borrow areas, tunnel spoil and the tunnel outlet portal	8-2

ANNEXURES

ANNEXURE A **FIGURES**

ANNEXURE B **TEST PIT PROFILES**

ANNEXURE C **DRILLER'S JOURNALS**

WATER TEST RESULTS

BOREHOLE CORE LOGS

BOREHOLE CORE PHOTOGRAPHS

LIST OF ABBREVIATIONS

ACV	Aggregate Crushing Value
AEG	Association of Engineering Geologists
BKS	BKS (Pty) Ltd
CCR	Clay Core Rockfill
CFR	Concrete Faced Rockfill
CGS	Council for Geoscience
D:NWRP	Directorate: National Water Resource Planning
D:NWRP	Directorate: National Water Resource Planning
D ₁₀	Effective size (sieve size passing 10% of soil)
FSL	Full Supply Level
KZN	KwaZulu-Natal
LL	Liquid Limit
LM	Local Municipality
LS	Linear Shrinkage
masl	Metres above sea level
MDD	Maximum Dry Density
MMA	Mogoba Maphuthi and Associates
OMC	Optimum Moisture Content
PE	Potential Expansiveness
PI	Plasticity Index
SAICE	South African Institution of Civil Engineering
SAIEG	South African Institute of Engineering and Environmental Geologists
TLB	Tractor Loader Backhoe
UCS	Unconfined Compressive Strength
uMWP	uMkhomazi Water Project
uMWP-1	uMkhomazi Water Project – Phase 1
uMWP-2	uMkhomazi Water Project – Phase 2
USCS	Unified Soil Classification System

LIST OF UNITS

a	annum
ha	hectare
hrs	hours
kℓ	kilolitre
km	kilometre
km ²	square kilometre
kW/m ²	kilowatt per square metre
ℓ	litre
ℓ/c/d	litre per capita per day
ℓ/cap/day	litre per capita per day
m	metre
m/s	metre per second
m ³	cubic meter
m ³ /s	cubic metre per second
masl	metre above sea level
million m ³	million cubic metre
million m ³ /a	million cubic metres per annum
Mℓ/day	mega litre per day
mm	millimetre
MW	megawatt
Ø	diameter in millimetres
s	second

1 INTRODUCTION

The Department of Water Affairs appointed **BKS (Pty) Ltd** in association with three sub-consultants **Africa Geo-Environmental Services, MM&A and Urban-Econ** with effect from 1 December 2011 to undertake the **uMkhomazi Water Project Phase 1: Module 1: Technical Feasibility Study Raw Water** study.

On 1 November 2012, BKS (Pty) Ltd was acquired by **AECOM Technology Corporation**. The new entity is a fully-fledged going concern with the same company registration number as that for BKS. As a result of the change in name and ownership of the company during the study period, all the final study reports are published under the AECOM name.

*In 2010, the Department of Arts and Culture published a list of name changes in the Government Gazette (GG No 33584, 1 October 2010). In this list, the Mkomazi River's name was changed to the **uMkhomazi River**. The published spelling will thus be used throughout this technical feasibility study.*

1.1 BACKGROUND TO THE PROJECT

The current water resources of the Mgeni system are insufficient to meet the long-term water demands of the system. The Mgeni System is the main water source that supplies about five million people and industries in the eThekweni Municipality, uMgungundlovu District Municipality (DM) and Msunduzi Local Municipality (LM), all of which comprise the economic powerhouse of the KwaZulu-Natal Province.

The Mgeni System comprises the Midmar, Albert Falls, Nagle and Inanda Dams in KwaZulu-Natal, a water transfer scheme from the Mooi River including the newly constructed Spring Grove Dam. The current system (Midmar, Albert Falls, Nagel and Inanda Dams and the MMTS-1) has a stochastic yield of 334 million m³/annum (measured at Inanda Dam) at a 99% assurance of supply. The short-term augmentation measure, Phase 2 of the Mooi Mgeni Transfer Scheme (MMTS-2), currently being implemented with the construction of Spring Grove Dam, will increase water supply from the Mgeni system by 60 million m³/year. However, this will not be sufficient to meet the long-term requirements of the system.

Pre-feasibility investigations indicated that Phase 1 of the uMkhomazi Water Project (uMWP 1), which entails the transfer of water from the undeveloped uMkhomazi River to the existing Mgeni system, is the scheme most likely to fulfil this requirement. The uMkhomazi River is the third-largest river in KwaZulu-Natal in terms of mean annual runoff (MAR).

Eight alternative schemes were initially identified as possible alternatives, and the Impendle and Smithfield scheme configurations have emerged as suitable for further investigation. The pre-feasibility investigation, concluded in 1998, recommended that the Smithfield Scheme be taken to a detailed feasibility-level investigation as its transfer conveyances would be independent of the existing Mgeni System, thus reducing the risk of limited or non-supply to eThekweni and some areas of Pietermaritzburg, and providing a back-up to the Mgeni System.

The *Mkomazi-Mgeni Transfer Pre-feasibility Study* concluded that the first phase of the uMWP would comprise a new dam at Smithfield on the uMkhomazi River near Richmond, a multi-level intake tower and pump station, a water transfer pipeline/tunnel to a balancing dam at Baynesfield Dam or a similar in-stream dam, a water treatment works at Baynesfield in the uMlaza River valley and a gravity pipeline to the Umgeni bulk distribution reservoir system, below the reservoir at Umlaas Road. From here, water will be distributed under gravity to eThekweni and possibly low-lying areas of Pietermaritzburg. Phase two of the uMWP may be implemented when needed, and could comprise the construction of a large dam at Impendle further upstream on the uMkhomazi River to release water to the downstream Smithfield Dam. Together, these developments have been identified as having a 99% assured stochastic yield of about 388 million m³/year.

The DWA aims to have this scheme implemented by 2022.

1.2 STUDY AREA

The study focus and key objective are related to the feasibility investigation of the Smithfield Dam and related raw water conveyance infrastructure. However, this is a multi-disciplinary project with the study area defined as the uMkhomazi River catchment, stretching to the north to include the uMngeni River catchment, refer to **Figure A1.1** included in **Annexure A**. The various tasks have specific focus area, defined as:

- ◆ Water Resources: uMkhomazi and Mgeni River catchments;
- ◆ Water requirements: water users in the Mgeni System and the uMkhomazi River catchment;
- ◆ Engineering Investigations: proposed dams at Impendle (only for costing purposes) and Smithfield, and the raw water conveyance infrastructure corridor between Smithfield Dam and the Water Treatment Plant of Umgeni Water;
- ◆ Environmental screening as input for the Environmental Impact Assessment; and
- ◆ Socio-economic impact assessment: regional, provincial (KwaZulu-Natal (KZN)) and national.

1.3 OBJECTIVE OF THE STUDY

According to the Terms of Reference (November 2010), the objective of the study project is to undertake a feasibility study to finalise the planning of the proposed uMkhomazi Water Project (uMWP) at a very detailed level for the scheme to be accurately compared with other possible alternatives and be ready for implementation (detailed design and construction) on completion of the study.

The feasibility study has been divided into the following modules, which will run concurrently:

- ◆ Module 1: Technical Feasibility Raw Water (DWA) (*defined below*);
- ◆ Module 2: Environmental Impact Assessment (DWA); and
- ◆ Module 3: Technical Feasibility Potable Water (Umgeni Water) (*ranging from the Water Treatment Plant to the tie-in point with the eThekweni distribution system*).

This module, the raw water technical feasibility study considers water resources aspects, engineering investigations and project planning and scheduling and implementation tasks, as well as an environmental screening and assessment of socio-economic impacts of the proposed project.

Some specific objectives for this study, recommended in the Mkomazi-Mgeni Transfer Scheme Pre-feasibility are listed below:

- ◆ Smithfield Dam (Phase 1) to be investigated to a detailed feasibility level;
- ◆ Investigate the availability of water from Impendle Dam (Phase 2) as a future resource to release to Smithfield Dam, and refine the phasing of the selected schemes;
- ◆ Optimise the conveyance system between Smithfield Dam and the proposed Baynesfield Water Treatment Plant;
- ◆ Undertake a water resources assessment of the uMkhomazi River Catchment, including water availability to the lower uMkhomazi;
- ◆ Evaluate the use of Baynesfield dam (now Langa Balancing Dam) as a balancing dam; and
- ◆ Investigate the social and economic impact of the uMWP.

This one of three studies was undertaken in close collaboration with the DWA, Umgeni and the PSPs of the other modules.

1.4 SCOPE OF THIS REPORT

This report deals exclusively with the construction materials and geotechnical investigations conducted at the site for the Langa Balancing Dam located on Baynesfield Estate near the outlet of the conveyance tunnel leading from the proposed Smithfield Dam. The name Langa has evolved after the field investigations were completed and the field data records in **Annexures B** and **C** therefore still contain the name Nooitgedacht (after the name of the farm).

A site for a balancing dam, located just upstream of the existing Mbangweni Dam was initially considered and called the New Mbangweni site. Seismic refraction surveys were conducted there, but due to poor foundation conditions and a wide river section, that site was not further investigated. The centre line for the Langa site was selected where the width of the wetland was the least and where shallow bedrock was visible on both sides of the river.

The activities specific to the *geotechnical and materials task* included:

- ◆ Review the available geotechnical information.
- ◆ Describe the general geology of the area.
- ◆ Conduct seismic refraction surveys along the centre line for the Langa Balancing Dam site.
- ◆ Consider the seismic risk.

- ◆ Conduct investigations for sources of dam construction materials by means of test pitting rotary core drilling and laboratory testing,
- ◆ Undertake geotechnical investigations for the foundations of the dam and spillway structure by means of rotary core drilling and Lugeon water pressure testing.
- ◆ Assess the stability of slopes around the reservoir rim.

1.5 PURPOSE OF THE REPORT

The objectives of this report are to describe the results of construction materials and geotechnical investigations for the proposed Langa Balancing Dam. The following components were dealt with:

- ◆ Foundations for an Earth Core Rockfill or zoned embankment dam with approach channel and side spillway with chute and plunge pool on the left flank.
- ◆ Alternatively, foundations for a Concrete Faced Rockfill dam with approach channel and side spillway with chute and plunge pool on the left flank.
- ◆ Construction material sources for the above dams.

The report presents the site conditions, methodology and results of the geological and materials investigation task of the study. The information is based on a desktop study and field investigations conducted between January and April 2013. The seismic survey report was completed in April 2013 and most of the laboratory testing was completed in July 2013.

The information from this report is required input into the engineering, financial and institutional investigations tasks, and this report is thus a supporting report to the main study report.

1.6 CONTENTS OF THE REPORT

This report is the *Supporting Document 4* for the main *Geotechnical Report* and refers to *Supporting Document 1* on the Seismic Hazard Assessment for both the Smithfield and Langa Dam sites, *Supporting Document 2* on the Seismic Refraction Survey and *Supporting Document 3* on the Materials and Geotechnical Investigation for the Smithfield Dam site.

This report comprises of the following parts:

- ◆ Text (*Volume 1 of 2*);
- ◆ Annexure A: Figures referred to in the text (*Volume 2 of 2*);
- ◆ Annexure B: Test pit profiles and laboratory tests (*Volume 2 of 2*); and
- ◆ Annexure C: Drilling results (*Volume 2 of 2*)

2 PREVIOUS INVESTIGATIONS

No previous investigations had been conducted at sites for a balancing dam.

3 PRESENT INVESTIGATIONS

3.1 NEED FOR GEOTECHNICAL INVESTIGATIONS

Based on a study of the available information, AECOM identified the need for the following geotechnical investigations:

3.1.1 Geological mapping

Geological mapping of the Langa Balancing Dam site, based on the observation of surface outcrops and the results of core drilling and test pitting must be conducted.

3.1.2 Seismic risk analysis

The seismic risk must be assessed.

3.1.3 Seismic refraction survey

Seismic refraction surveys must be conducted along the proposed dam centre line to ensure that boreholes are drilled at the most appropriate locations and to interpret geological conditions between boreholes.

3.1.4 Test pitting, soil sampling and laboratory testing

Test pits (up to 5 m deep) must be dug within the dam basin to investigate sources for embankment material, particularly impervious material for the core. The test pits must be geotechnically logged and representative samples taken for additional laboratory testing. Laboratory tests must include Grading and Atterberg Limits. In addition, samples of rock must be subjected to tests for rockfill.

3.1.5 Core drilling

It was considered necessary to drill boreholes and conduct water pressure tests to assess the required depths of foundation excavation and to determine the permeability and need for grouting. The drilling of boreholes to investigate foundation conditions for a spillway structure was also necessary. Core drilling was also required to investigate the quantity and quality of material for rockfill. Drilling and test pit information from the tunnel outlet portal area could be used to assess the suitability of excavated material for dam construction.

3.1.6 Reservoir slope stability

Slopes within the dam basin must be studied in order to determine the risk of failures and the effect of such failures on the dam structure.

3.2 GEOLOGICAL MAPPING

A regional geological map of the area around the site for the proposed Langa Balancing Dam was compiled from information on the published Geological Map, The regional geological map is attached as **Figure A4.1** included in **Annexure A**.

Due to the limited outcrops of rock other than shale, the detailed geological map on **Figure A4.2** included in **Annexure A** mainly serves to indicate the extent of the wetland areas and the suspected fault that intersects the dam centre line.

3.3 SEISMIC HAZARD ANALYSIS

A Probabilistic Seismic Hazard Analysis (PSHA) for both the Smithfield and Langa sites was conducted by Dr A Kijko of the Natural Hazards Assessment Consultancy in Centurion (*Report no P WMA 11/U10/00/3312/3/2/1: Supporting document 1: Probabilistic hazard analysis for Smithfield Dam, Langa Balancing Dam and the conveyance system*).

The PSHA was performed using conventional Cornell-McGuire procedures where the integration across the uncertainty in the peak ground acceleration (PGA) prediction equation is an integral part of the methodology.

In accordance with current seismic regulations provided in Bulletin 72 of ICOLD (1989), Eurocode 8 (2004) and ASCE (2005), three seismic designated levels were considered namely the Operating Basis Earthquake (OBE), Maximum Design Earthquake (MDE) and Maximum Credible Earthquake (MCE).

Results for the horizontal component of earthquake acceleration are as follows:

◆ Operating Basis Earthquake (Return period 144 years)	=0.016 g
◆ Maximum Design Earthquake (Return Period 475 years)	=0.021 g
◆ Maximum Credible Earthquake (Return period 10 000 years)	=0.113 g

The above results classify the site as of low seismic risk.

3.4 SEISMIC REFRACTION SURVEY

Seismic refraction surveys were undertaken by Open Ground Resources to determine the succession of seismic velocity layers and depth to sound bedrock at the following locations (*Report no P WMA 11/U10/00/3312/3/2/2: Supporting document 2: Seismic refraction investigation at the proposed uMkhomazi Water Project Phase 1*):

◆ New Mbangweni dam site - left flank:	160 m
◆ New Mbangweni dam site – right flank:	115 m
◆ Tunnel outlet portal area:	475 m
◆ Langa dam site – left flank:	115 m
◆ Langa dam site – river section:	115 m
◆ Langa dam site – right flank:	235 m

Figure A5.1 included in **Annexure A** shows the positions of the seismic lines at the Langa site.

3.5 TEST PITS

Test pits were excavated to investigate the subsurface conditions to a maximum depth of about 5 m. A 20-ton excavator was used (instead of a TLB) to speed up the work and to penetrate possible zones of hardpan ferricrete.

Large parts of the dam basin are classified as a wetland or contain rare plant species and could not be investigated (see **Figure A4.2** included in **Annexure A**). The flat areas just above FSL on the left flank are potential sources for impervious embankment material but they were under cultivation by maize and could not be investigated in detail. A few test pits were dug along tracks within and around the lands.

Table 3.1 provides details of 19 test pits that were excavated along the dam centre line, the proposed borrow area and the tunnel outlet portal.

Table 3.1: Summary of test pits

Project area	Number of test pits	Test pit numbers
Langa dam centre line	3	MTP1, MTP2, MTP4
Borrow area	12	MTP5, MTP7-MTP16, MTP18
Tunnel outlet portal	4	TP01 – TP 04

The test pits were excavated to a maximum reach of machine or to partial refusal (caused by dense/stiff material), whichever occurred first. Test pits were profiled by an engineering geologist according to the current standards and practice in South Africa (*IAEG/AEG/SAICE-Geotechnical Division, 2002*). Representative samples were taken for laboratory testing.

Immediately after completing the profiling and sampling of each test pit, the excavated material was placed back into the hole and compacted in layers. Material from the upper fertile soil layer was kept separate and placed on top of the backfilled material. The ground surface was restored as near as possible to its original condition.

Each test pit was positioned using a hand-held GPS. **Figure A5.1** included in **Annexure A** shows the positions of test pits.

3.6 ROTARY CORE DRILLING

Rotary core drilling was undertaken to obtain relatively undisturbed samples of soil and rock to depths of 20 m - 25 m below ground surface and to conduct packer permeability tests to these depths along the dam centre line.

Borehole cores were profiled by an engineering geologist according to the current standards and practice in South Africa (*SAIEG/AEG/SAICE-Geotechnical Division, 2002*).

Water pressure testing was carried out within the boreholes along the dam centreline to assess the permeability of the foundation materials. Special provision was made in the drilling contract for water pressure (Lugeon) testing in weathered rock conditions where conventional packers cannot be used. In these materials the packers were seated within a tight-fitted (drilled-in) casing so that packer tests could be conducted from about 2 m depth.

Samples comprising moderately and slightly weathered shale from boreholes in the proposed quarry were taken for laboratory tests to determine their properties with respect to use as soft rockfill.

Table 3.2 summarises the distribution of the core-drilled boreholes. Positions of boreholes were surveyed to an accuracy of 200 mm both horizontally and vertically. The positions of boreholes are shown on **Figure A5.1** included in **Annexure A**.

Table 3.2: Summary of cored boreholes

Project area	Number of boreholes	Borehole No's
Langa Dam site, left flank	3	NM1, NM2, NM9
Langa Dam site, river section	1	NM3
Langa Dam site, right flank	4	NM4 – NM7
Langa Dam, left spillway	1	NM10
Langa Dam, right spillway	1	NM8
Langa Quarry site	3	NQ1 – NQ3
Tunnel outlet	1	BH8

Borehole cores were profiled by an engineering geologist according to the current standards and practice in South Africa (*SAIEG/AEG/SAICE-Geotechnical Division, 2002*).

At the end of the drilling investigation, all the borehole cores were transported to the DWA offices at Midmar Dam where the core boxes were stacked in a dedicated carport. The results of the drilling (i.e. driller's journals, borehole logs, core photographs and water test results) are included in **Annexure C**.

3.7 LABORATORY TESTING

Soil samples taken from the cultivated lands on the left flank and from the dam basin were taken to Geostrada soils laboratory for grading, Atterberg testing and double hydrometer dispersivity testing.

Samples from the tunnel outlet portal were subjected to the following tests (as part of the tunnel investigation):

- ◆ Grading to minus 0.002 mm and Atterberg Limits
- ◆ Mod. AAHSTO Compaction
- ◆ Chemical dispersion

- ◆ Shear box
- ◆ Flexible wall permeability.

Samples of moderately and slightly weathered shale from boreholes in the proposed quarry area were subjected to the following laboratory tests to determine their properties with respect to their use as soft rockfill:

- ◆ Crushing to minus 53 mm
- ◆ Grading analysis
- ◆ Determination of the Atterberg Limits, where possible
- ◆ Aggregate Crushing Values (wet and dry)

The results of the laboratory tests are contained in **Annexure B** of this report.

3.8 RESERVOIR SLOPE STABILITY STUDY

The available contour map of the basin area was used to determine the slope angles of the area above and below FSL around the rim of the reservoir. From observations of rock outcrops and overburden along the steeper slopes, an assessment of the stability of slopes as a result of fluctuating water levels could be made.

4 GEOLOGY

The area of interest is underlain by sedimentary strata of the Karoo Supergroup that were subsequently intruded by younger dolerites in the form of sills and dykes (**Figure A4.1** included in **Annexure A**)

The dam site is underlain by rocks of the Pietermaritzburg Formation of the Ecca Group, comprising shales and siltstones with sub-ordinate sandstones. The sedimentary strata are essentially horizontal, and largely undisturbed. Regional dips of 3 - 5 degrees were recorded.

Neither the rocks of the Pietermaritzburg Formation nor the intrusive dolerites which underlie the dam basin are typically associated with economically-important mineral deposits.

At the dam site the shales had been intruded by at least one near-horizontal dolerite sill. It varies in thickness between about 5 m and 10 m and occurs along the dam centre line and in the main quarry area where it is covered by shale. On the left flank, the sill had been displaced downwards along a fault by about 8 m. This fault appears to intersect the dam centre line along the lower right flank. The dolerite does not crop out anywhere on site (**Figure A4.2** included in **Annexure A**).

Bedrock is mostly very shallow and it is only along the lower right flank where there is a deposit of colluvium overlying the dolerite. The river section is occupied by a wetland that varies in width between 50 m and 150 m.

5 CONSTRUCTION MATERIALS INVESTIGATION

During the present feasibility stage of the project, various types of dams are being considered, and therefore the available quantities and properties of different types of construction materials were investigated. The aim of the construction materials investigation was to locate sources of natural construction materials (soil and rock) in environmentally suitable locations, capable of providing the volumes as shown in **Table 5.1**. These quantities include the normal “safety factor” whereby twice the volume of material required for construction, is proved during the site investigation.

Table 5.1: Approximate volumes of construction material (2 x required)

Structure	Type of material (m ³)				
	Impervious core	Semi-pervious	Rockfill	Rip-rap	Rock for aggregate, filters, drains
Zoned embankment dam	350 000	1 020 000	-	80 000	200 000
Clay Core Rockfill dam	250 000	-	800 000	-	110 000
Concrete Faced Rockfill dam	-	-	1 000 000	-	-

A typical specification for embankment materials is given in **Table 5.2**.

Table 5.2: Typical specifications for earth fill materials (Badenhorst, 1988)

Property	Embankment zones		
	Impervious	Semi-pervious	Pervious
Clay content (%)	10-30	<55	<10
PI (%)	12-35	<12	<5
LL (%)	30-60	<30	<20
LS (%)	6-10	<7	<2
Standard Proctor MDD (kg/m ³)	1450-1880	1750-2000	1700-2100
Standard Proctor OMC (%)	12-25	10-15	6-12
Cohesion (kPa)	12-30	8-15	<10
Friction angle (°)	18-30	28-38	>35
Permeability (m/sec)	<1x10 ⁻⁸	1x10 ⁻⁷ – 1x10 ⁻⁵	>1x10 ⁻⁵

Five potential sources for embankment construction materials were identified, namely:

- ◆ Spoil from the conveyance tunnel excavation;
- ◆ Excavated material from the tunnel outlet portal;
- ◆ Excavated material from the spillway approach on the upper left flank;
- ◆ Borrow area within the dam basin; and
- ◆ Quarry in the dam basin.

5.1 TEST PITS AND BOREHOLES

Test pits were dug by means of a 20 ton tracked excavator with a maximum reach of about 5 m depth while boreholes were drilled with a rotary core drill. The positions of test pits and boreholes at the Langa site are shown on **Figure A5.1** included in **Annexure A**.

Material to be excavated for the outlet portal of the conveyance tunnel was investigated by means of four test pits (TPO 1 – TPO 4) and Borehole BH 8. The positions of these test pits and borehole are shown on **Figure A5.2**, while the position of the portal is shown on **Figure A1.1**, both included in **Annexure A**.

The area of the proposed spillway approach cut was under cultivation by maize, and four test pits (MTP 5, MTP 7, MTP 15 and MTP 18) were dug around the cultivated

lands and along tracks between the lands. The results from Boreholes NM 9 and NM 10 are also considered to be representative of conditions in this area.

The proposed borrow area within the dam basin were investigated by means of eight test pits (MTP 8 – MTP 14 and MTP 16). The positions for test pits had to be carefully selected to fall outside the extensive wetland within the dam basin.

The only potential quarry site within the dam basin was identified as a spur within the proposed borrow area. A potential quarry area of about 60 000 m² was identified (see **Figure A5.1** included in **Annexure A**). Here also, the positions for boreholes had to be carefully selected to fall outside the extensive wetland within the dam basin.

The detailed test pit and borehole logs are provided in Annexure B and summaries of the results are presented in **Table 5.3** and **Table 5.4**.

Table 5.3: Summary of test pit results

TP No.	LAYER THICKNESS (m)				COMMENTS DE = Difficult excavation
	Organic soil	Clayey sand/silt A = Alluvium C = Colluvium P = Pedogenic ferricrete RD = Residual dolerite RS = Residual shale	Boulders and clayey silt C = Colluvium A = Alluvium	Soft rock P = pedogenic S = Shale D = Dolerite	
MTP 5	0.0 – 0.4	0.4 – 1.1 (C)		1.1 – 3.8 (S)	DE
MTP 7	0.0 – 0.5	0.5 – 2.1 (C)		2.1 – 4.0(S)	DE
MTP 8	0.0 – 0.5	0.5 – 1.5 (C)		1.5 – 3.0(S)	DE
MTP 9	0.0 – 0.5		0.5 – 1.5 (C)	1.5 – 3.5(S)	DE
MTP 10	0.0 – 0.2			0.2 – 2.0(S)	DE
MTP 11	0.0 – 0.5	0.5 – 1.2 (C)		1.2 – 3.5(S)	DE
MTP 12	0.0 – 0.2			0.2 – 2.0(S)	DE
MTP 13	0.0 – 0.2			0.2 – 4.0(S)	DE
MTP 14	0.0 – 0.2			0.2 – 2.4(S)	DE
MTP 15	0.0 – 0.5			0.2 – 3.5(S)	DE
MTP 16	0.0 – 0.7			0.7 – 2.4(S)	DE
MTP 18	0.0 – 0.4	0.4 – 1.1 (A)		1.1 – 3.8(S)	DE
TPO 1		0.6 – 1.8(RS)	0.0 – 0.6 (C)	1.8 – 4.6(S)	DE
TPO 2	0.0 – 0.6	2.6 – 5.0(RS)	0.6 – 2.6 (C)		DE (water 1m)
TPO 3	0.0 – 0.6		0.6 – 1.0 (C)	1.0 – 4.3(S)	DE(water 3m)
TPO 4		0.4 – 2.3(RS)	0.0 – 0.4 (C)	2.3 – 5.0(S)	DE

Table 5.4: Summary of results from boreholes in the quarry

BH No.	TYPE OF MATERIAL/DEGREE OF WEATHERING Organic soil = O, Sandy clay = SC, Gravel in clay = GC, Gravel in sand = GS Shale = S; Indurated shale = I, Dolerite = D					
	LAYER THICKNESS (m)					
	TRANSPORTED SOIL	RESIDUAL SOIL/ COMPLETELY WEATHERED	HIGHLY	MODERATELY	SLIGHTLY	UNWEATHERED
NQ 1	0.0 – 0.55(O)	0.55 – 1.35 (S)	1.35 – 5.16(S)	5.16–11.5 (S)		11.5-20.19(S)
NQ 2			0.0-5.12(S) 6.57-8.07(S)	5.12-6.57(S) 8.07-10.07(S)		10.07-10.07(S)
NQ 3		0.0 – 2.0(S)	2.0-3.48(S)	3.48-4,35(S)	4.35-9.0(S)	9.0-10.73(S) 10.73-17.67(D) 17.67-20.18(S)
NM 9	0.0 – 0.25(O)	0.25-1.7(S)	1.7-3.1(S) 4.2-5.14(S) 6.25-8.73(S)	3.1-4.2(S) 5.14-6.25(S) 8.73-9.30(S)	9.3-12.0(S)	12.0-20.11(S)
NM 10		0.9 – 1.5(S) 5.14-5.28(S)	0.0 – 0.9(S) 1.5-5.14(S)		5.28-7.4(S)	7.4-20.02(S)
BH 8*	0.0 – 0.26(O)	0.26 – 8.77(S)		8.77 – 11.22(S)	11.22-20.17(S)	

*BH8 is located at the tunnel outlet portal

The quarry is underlain by a very thin layer of topsoil, followed by 2 m – 3 m of completely weathered shale. A layer of moderately to highly weathered shale varies in thickness between 2 m and 10 m and this is underlain by slightly weathered and unweathered shale.

Borehole NQ 3 in the quarry encountered a 7 m thick dolerite sill that may continue all the way to the dam centre line (see **Figure A5.3** included in **Annexure A**). This might provide a considerable volume of unweathered dolerite and needs to be further investigated by means of deeper boreholes during the design stage investigation

5.2 LABORATORY TESTS ON SOIL SAMPLES

Small samples for foundation indicator tests and duplicate large samples for compaction and other tests were taken from representative soil horizons encountered in the test pits.

Geostrada Soils Laboratory in Pretoria conducted three foundation indicator tests consisting of grading analysis to minus 0.002 mm, and determination of the Atterberg Limits.

Samples from the tunnel outlet portal were also tested for grading, Atterberg Limits, Mod. AAHSTO Compaction, CBR, chemical dispersion, shear box and permeability.

The results of the grading and Atterberg tests are summarised in **Table 5.5**, and the detailed results are provided in **Annexure B**. The selection of samples for laboratory testing was based on the soil type (grain size), which was visually determined during the soil profiling. Since this determination is a rough estimate that is affected by the moisture condition of the soil, grain shape, grain composition and experience of the profiler, both the profile descriptions and the laboratory results (in italics) for grain sizes are given in the fourth column of **Table 5.5**.

Table 5.5: Summary of laboratory foundation indicator test

Site	Test Pit No.	Depth (m)	Visual Soil Profile Description (<i>Lab result in italics %</i>)	Soil Properties				
				Atterberg Limits (%)			USCS	PE
				LL	PI	LS		
Langa borrow area	MTP 7	0.5 – 2.1	Clayey silt <i>Clayey(11) gravelly(15)</i> <i>Silty(29) sand(45)</i>	47	21	8.5	CL	Low to Medium
	MTP 13	1.2 – 4.0	Shale <i>Clayey(9) silty(23)</i> <i>Gravelly(29) sand(39)</i>	42	15	5.5	ML	Low
	MTP 18	0.4 – 1.1	Clayey silt <i>Gravelly(14) clayey(20)</i> <i>Silty(31) sand(35)</i>	48	15	6.5	ML	Low to Medium
	TPO 2	0.6.2.6	Clayey silt <i>Gravelly (12) silty (36) clay (50)</i>	57	27	12	MH	Low to medium
Legend	LL		=	Liquid Limit				
	PI		=	Plasticity Index				
	LS		=	Linear Shrinkage				
	PE		=	Potential Expansiveness				
	USCS		=	Unified Soil Classification System				

The above samples comply with the specification for impervious core material in terms of the Atterberg Limits. However, the permeabilities are likely to be too high.

The results of other tests on samples from the tunnel outlet portal are summarised in **Table 5.6**. Some of these tests were done for the tunnel investigation and are of limited use for the dam materials investigation.

Table 5.6: Summary of other laboratory test results

Test pit number, depth and material type	TPO2 0.6 – 2.6 m Clayey silt colluvium	TPO1 0.6 – 4.6 m Residual and highly weathered shale	MTP7 0.5 – 2.1 m Clayey silt colluvium	MTP13 0.2 – 4.0 m Highly weathered shale
Mod. AASHTO Density (kg/m ³)	1881	-	-	-
OMC (%)	16.4	-	-	-
Chemical Dispersivity	Non- dispersive	-	-	-
Double Hydrometer Dispersivity (%)	-	-	12	10
Shear box Φ (degrees)	-	33	-	-
Shear box cohesion (kPa)	-	8	-	-
Flexible wall permeability (m/s)	-	2×10^{-10}	-	-

5.3 LABORATORY TESTS ON ROCK SAMPLES

Only limited laboratory testing was undertaken since results from similar materials are available from recent investigations at the conveyance tunnel, the Smithfield Dam and the Zalu Dam near Lusikisiki.

5.3.1 Unconfined compressive strength and E-Modulus

Core samples of slightly weathered and unweathered shale and dolerite from drilling along the conveyance tunnel were submitted to Rocklab for various tests. Some of these results are relevant for tunnel spoil materials earmarked for possible use as embankment fill (rockfill). The relevant results are given in **Table 5.7**.

Table 5.7: Summary of laboratory tests on slightly weathered and unweathered shale and dolerite

BH No.	DEPTH (m)	ROCK TYPE	UCS range (MPa)	TANGENT E MODULUS RANGE (GPa)	BRAZILIAN TENSILE STRENGTH RANGE (MPa)	DENSITY (kg/m ³)
2	5.95 – 12.0	Slightly weathered indurated shale	166 - 228	32.8 - 34.8	14.7 - 18.2	2660
3	27.0 – 40.0	Slightly weathered indurated shale	213 - 243	36.1 - 38.4	37 - 48.5	2680
5	387.0-397.0	Unweathered dolerite	212 - 349	44.7 - 63.6	31.3 - 41.6	2720

The above strengths and E-moduli are well above the required values of about 50 MPa – 100 MPa for UCS and 15 GPa for E-modulus of rockfill. It must however be remembered that the shale is prone to rapid deterioration and that these values are only applicable for the unslaked material.

Samples of material from the TBM excavation are not available for testing, but from previous experience it is anticipated that the material will be in the form of flaky shards of rock with average maximum size of about 100 mm and with properties of a G5 gravel. It is possible to compact these materials in a rockfill embankment to achieve high density and shear strength.

5.3.2 Tests on slightly weathered and moderately weathered shale

Core samples of slightly weathered and moderately weathered shale from the drilling at the Langa Dam site were submitted to Geostrada for crushing, grading to minus 53 mm, Atterberg Limits and ACV (wet and dry) tests. The results are summarised in **Table 5.8**.

Table 5.8: Summary of laboratory test on crushed slightly weathered and moderately weathered shale

SAMPLE TYPE	Moderately weathered	Slightly weathered
PROPERTY		
-19 mm (%)	68	81
-4.75 mm (%)	18	24
- 2.36mm (%)	12	14
-0.425 mm (%)	6	5
-0.075 mm (%)	4	2
GM	2.04	2.70
LL (%)	30	24
PI (%)	8	6
LS (%)	4.5	2.5
ACV Dry (%)	33.3	23.9
ACV Wet (%)	44.2	28.4
Dry/Wet Ratio (%)	75	84

5.3.3 Exposure tests on slightly weathered and moderately weathered shale

The results of **Table 5.8** are very similar to the results obtained from the testing of the Smithfield Dam site samples. The Smithfield Dam site results on exposure tests are therefore considered relevant, and are described below.

Core samples of unweathered and moderately weathered shale from the drilling at the Smithfield Dam site were submitted to exposure and other durability tests.

Unweathered to moderately weathered shale can be subdivided into two types, namely (i) rock that is prone to slaking (carbonaceous shale) and (ii) rock that is indurated and relatively durable. The following core samples were taken for laboratory testing:

- ◆ MW: Moderately weathered shale (not prone to slaking);
- ◆ MWS: Moderately weathered shale prone to slaking;
- ◆ SW: Slightly weathered shale (not prone to slaking); and
- ◆ SWS: Slightly weathered shale prone to slaking.

Each of the above samples was split into two parts. The one part (Part 1) was crushed to minus 19 mm and the other part (Part B) was placed outside for a period of 3 weeks where it was exposed to the atmosphere and was sprayed with water every second day. It was then crushed to a size of minus 19 mm.

Both sets of samples (Part 1 and Part 2) were then graded and subjected to Atterberg Limit tests. ACV tests (Wet and Dry) were done on the Part 1 samples.

The results of the laboratory tests appear in Annexure B, and summaries are given in **Table 5.9** and **Table 5.10**.

Table 5.9: Summary of laboratory tests on slightly weathered shale

SAMPLE No PROPERTY	SW Part 1 Crushed	SW Part 2 Exposed	SWS Part 1 Crushed	SWS Part 2 Exposed
-19 mm (%)	100	69	100	82
-4.75 mm (%)	46	15	54	31
- 2mm (%)	21	7	26	13
-0.425 mm (%)	7	3	10	5
-0.075 mm (%)	2	2	4	3
GM	2.7	2.88	2.6	2.79
LL (%)	NP ¹	NP	20	20
PI (%)	NP	NP	3	5
LS (%)	NP	NP	1.5	1.5
ACV Dry (%)	26.7	NT ²	35.3	NT
ACV Wet (%)	29.5	NT	46.2	NT
Dry/Wet Ratio (%)	91	NT	76	NT

¹ Non Plastic

² Not Tested

Table 5.10: Summary of laboratory tests on moderately weathered shale

SAMPLE No PROPERTY	MW Part 1 crushed	MW Part 2 exposed	MWS Part 1 crushed	MWS Part 2 exposed
-19 mm (%)	100	80	100	89
-4.75 mm (%)	48	18	41	34
- 2mm (%)	25	8	17	12
-0.425 mm (%)	9	4	7	4
-0.075 mm (%)	4	3	2	3
GM	2.62	2.85	2.74	2.81
LL (%)	NP	NP	NP	NP
PI (%)	NP	NP	NP	NP
LS (%)	NP	NP	NP	NP
ACV Dry (%)	33.5	NT	38.3	NT
ACV Wet (%)	42	NT	47.4	NT
Dry/Wet Ratio (%)	80	NT	81	NT

¹ Non Plastic

² Not Tested

The results of the grading before and after exposure are not as expected since the percentage fines (-0.425 mm and -2.0 mm) decreased after the samples were exposed to the atmosphere. This is ascribed to differences in the crushing of Part I and Part II samples.

From the above results it appears that slightly weathered shale (that is prone to slaking) has a clay mineral content large enough to give some plasticity (PI = 3% – 6%).

The effect of short-term (3 weeks) exposure on the grading of the crushed shale does not seem to be dramatic (GM = 2.6 – 2.88).

The reduction in strength (ACV) after wetting varies between 24% for the slightly weathered shale that is prone to slaking to about 9% for the slightly weathered shale that is not prone to slaking. The latter type of shale meets the ACV specification for concrete aggregate. For the moderately weathered shale, the reduction in ACV after wetting is about 20 %.

The overall result of the durability testing is reassuring in that it appears that the indurated shale (visually not prone to slaking) is strong, most of the decrease in

strength takes place within a short period (days rather than weeks), and that all slightly weathered and unweathered shale can be considered suitable as hard rockfill, provided that it is protected by an outer shell of durable rock.

5.3.4 Tests on highly and moderately weathered shale

These materials were not tested during the current investigation, but similar materials were tested during the investigation for the Zalu Dam site near Lusikisiki.

The samples were subjected to primary crushing to the minus 25 mm size and subjected to grading, Atterberg, Aggregate Crushing Value (ACV), Standard Proctor and consolidated undrained triaxial testing.

Since it is not known to what extent the weathered shale will break up during quarrying, transport, compaction and consolidation in a dam embankment, it was decided, for the sake of conservatism, to conduct the triaxial tests on the minus D_{10} fraction. However, after the primary crushing (to minus 25 mm) the minus D_{10} fraction of the highly weathered and moderately weathered shale produced too little material and it was then decided to crush the entire sample to minus 0.425 mm for the triaxial testing. The samples were compacted to 95% of Standard Proctor density and the moisture content adjusted to about 20% before testing. The results are shown in **Table 5.11**.

Table 5.11: Summary of laboratory tests on crushed rock cores

Sample Origin	Highly weathered shale	Moderately weathered shale
Laboratory Number	2/4971	2/4972
Grading description (after crushing to minus 25 mm)	Silty (11%) sandy (34%) gravel (51%)	Sandy (22%) gravel (78%)
LL (%)	27	Non plastic
PI (%)	7	Non plastic
LS (%)	2,5	1.5
PE	Low	Low
ACV (%)	39,9	29,2
Standard Proctor MDD (kg/m ³)	1960	2049
Standard Proctor OMC (%)	13,4	10,3
Cohesion (effective) (kPa)	0	13
Friction angle (effective) (degrees)	35	35

5.4 AVAILABLE VOLUMES OF VARIOUS MATERIALS

The proposed borrow area in the dam basin has a very thin cover of soil above weathered shale and it was decided to abandon the idea of a borrow area and to investigate the rock quarry in the same area. The estimated volumes of the above materials are given in **Table 5.12**.

Table 5.12: Estimated volumes of embankment materials from borrow areas, tunnel spoil and the tunnel outlet portal

Type of material	Required (x 1000 m ³) Percentages available are given in brackets.			Available (x 1000 m ³)			
	For CFR Dam	For CCR Dam	For zoned embankment	Tunnel spoil (outlet section)	Portal excavation	Spillway approach	Quarry
Overburden for spoil: Organic topsoil	0	0	0	0	8	15	20
Impervious core	0	250 (0%)	350 (0%)	0	0	0	0
Semi-pervious fill: Residual silty clayey sand and sandy silty clay	0	0	1 020 (90%)	0	230	35	120
Semi-pervious fill: Highly weathered shale					70	280	180
Soft rockfill: Moderately weathered shale	1000 (191%)	910 (210%)	280 (682%)	0	50	20	350
Hard rockfill: Unweathered shale and dolerite				250	40	0	1 200

5.5 MATERIAL PARAMETERS FOR DESIGN

Based on the information from the drilling and laboratory testing, the various types of material available from all the sources can be described as follows:

- ◆ Residual clayey gravelly silty sand and highly to completely weathered shale comply with the specification for semi-pervious earthfill.
- ◆ Moderately weathered shales are generally medium strong rocks in situ, but are prone to rapid slaking upon exposure to the atmosphere. This shale material can be considered as soft rockfill, but must be covered by durable (dolerite) rock outer zones.
- ◆ Unweathered shale and dolerite (mixture from tunnel excavation and quarry) are suitable as hard rockfill but must be covered by durable (dolerite) rock outer zones.

The estimated average properties of the above types of materials are given in **Table 5.13**.

Table 5.13: Estimated material parameters for design

Material type	Properties of compacted material						
	n/p = non-plastic n/a = not applicable n/t = not tested est = estimates based on other projects						
	Liquid Limit (%)	Plasticity Index (%)	Density (kg/m ³)	OMC (%)	Permeability (m/s)	Cohesion (kPa)	Phi (°)
Semi-pervious fill: Residual silty clayey sand and sandy silty clay	47	18	1730	16	$4 \times 10^{-6*}$	n/t	n/t
Semi-pervious fill: Highly weathered shale	27	7	1960	13.4	$2,7 \times 10^{-3*}$ $2 \times 10^{-10**}$	8***	33***
Soft rockfill: Moderately weathered shale	n/p	n/p	2049	10.3	$1 \times 10^{-1*}$	0 (est)	35 (est)
Hard rockfill: Slightly weathered and unweathered shale, non-slaking	n/p	n/p	2100 (est)	n/a	n/t	0 (est)	38 (est)
Hard rockfill: Slightly weathered and unweathered shale, slaking	20	5	2100 (est)	n/t	n/t	0 (est)	36 (est)
Hard rockfill : Slightly weathered and unweathered dolerite	n/p	n/p	2200 (est)	n/a	n/t	0 (est)	40 (est)

* Permeability based on Hazen's equation on D_{10} of samples crushed to minus 25 mm.

** Permeability from flexible wall permeates

*** Shear box test results

From **Table 5.12** and **Table 5.13** it appears that none of the available materials qualify as impervious fill. The residual silty clayey sand qualifies as impervious material in terms of the Atterberg Limits, but its permeability is likely to be too high and can therefore best be used in semi-pervious zones.

The available quantity of semi-pervious material is not quite sufficient to provide twice the required volume for a zoned embankment dam.

A considerable volume of soft rockfill will have to be removed from the quarry in order to reach the hard rockfill. This material can be used in certain zones of any of the alternative embankment dams.

There is sufficient hard rockfill for construction of a CFR or ECR Dam. For any of these dam types, durable dolerite may have to be imported from a commercial quarry (Pietermaritzburg) to serve as protective layer above the shale or dolerite shale mixture. Some or all of this dolerite might be obtained from the quarry, but will have to be further investigated during the design stage.

Due to the absence of impervious core material, consideration will have to be given to a Concrete Faced Rockfill or Earth Core Rockfill Dam with impervious core comprising a mixture of soil and bentonite. The Concrete Faced Rockfill option appears to be the more feasible, since the available soils contain too much clay to mix with bentonite.

6 GEOTECHNICAL INVESTIGATIONS

Geotechnical investigations were conducted along the proposed dam centre line and along the proposed spillway return channel on the left flank.

The position of the centre line was selected where the width of the wetland was at a minimum and where rock outcrops were visible at surface on both sides of the river. For a dam with FSL at 919 masl, this meant that both flanks run in an upstream direction to make best use of the topography (see **Figure A5.1** included in **Annexure A**).

From a topographic point of view, a side spillway could be positioned on either flank, but the drilling results showed very deep weathering on the right flank and it was proposed to position the spillway on the left flank (**Figure A5.1** included in **Annexure A**).

The investigations comprised seismic refraction surveys, test pitting and rotary core drilling along the dam centre line and drilling for the spillway chute on the left flank.

6.1 SEISMIC REFRACTION SURVEYS

Seismic refraction surveys by Open Ground Resources were conducted along the following lines (*Report no P WMA 11/U10/00/3312/3/2/2: Supporting document 2: Seismic refraction investigation at the proposed uMkhomazi Water Project Phase 1*):

- ◆ Centre line left flank (Line G1-G2 = 115 m);
- ◆ Centre line river section (Line G2A-G3A = 115 m); and
- ◆ Centre line right flank (Line G3B-G4 = 235 m).

The positions of the seismic lines are shown on **Figure A5.1** included in **Annexure A**.

Due to the presence of cultivated lands on the upper left flank, seismic surveys could not be conducted there.

The 3 500 m/s seismic velocity line usually represents slightly weathered, medium to closely jointed dolerite, suitable as foundation for a concrete dam. Lines depicting

this velocity have been drawn on sections containing the results of boreholes along the centre line (**Figure A6.1** included in **Annexure A**).

Seismic line G1-G2 along the lower left flank overestimates the depth to sound rock dolerite by about 7 m at Borehole NM 1 and by about 4 m at Borehole NM 2. This might be due to the thick layer of shale above the dolerite in this area.

Seismic line G2A-G3A in the river section and lower right flank shows a deep seismic low to the left of Borehole NM 5 and this is interpreted as weathering associated with a suspected fault that displaces the dolerite sill by about 8 m in this area.

Seismic line G3B-G4 along the right flank shows the 3 500 m/s seismic line to be very deep (>30 m) along the lower part of the flank and then rises abruptly near section chainage 600 m, probably as a result of the dolerite sill that becomes unweathered at that location.

6.2 CORE DRILLING AND WATER TESTING

A total of ten cored boreholes with Lugeon water testing were drilled to investigate the anomalies revealed by the seismic refraction survey and to provide information on founding conditions and the need for grouting. The positions of the boreholes are shown on **Figure A5.1** included in **Annexure A**.

On the left flank only Borehole NM 9 could be drilled near the centre line due to the presence of cultivated lands and environmental restrictions. Borehole NM 10 was drilled near the left flank tributary to investigate conditions for the proposed spillway chute.

Boreholes NM 1 – NM 3 were drilled in the river section and Boreholes NM 4 – NM 7 along the right flank. Borehole NM 8 was drilled closer to the right flank tributary to investigate conditions for the proposed side spillway. A summary of the borehole results is given in **Table 6.1**.

Table 6.1: Summary of boreholes results at the dam site

BH No.	TYPE OF MATERIAL/DEGREE OF WEATHERING					
	Organic soil = O, Sandy clay = SC, Gravel in clay = GC, Gravel in sand = GS Shale = S; Indurated shale = I, Dolerite = D					
	TRANSPORTED SOIL	RESIDUAL SOIL/ COMPLETELY WEATHERED	HIGHLY	MODERATELY	SLIGHTLY	UNWEATHERED
LAYER THICKNESS (m)						
NM 1	0.0 - 0.5 (O)	0.5 – 1.57 (S)	2.15 – 2.39(S) 2.79 – 3.1 (S) 4.3 – 4.37 (S) 5.29 – 5.63(S) 5.87 – 5.95(S) 7.14 – 7.35(S) 8.61 – 9.12(S) 10.2–10.30(S)	1.57 – 2.15 (S) 2.39 – 2.79(S) 3.1 – 4.3 (S) 4.37 – 5.29 (S) 5.63 – 5.87 (S) 5.95 – 7.14(S) 7.35 – 8.61(S) 9.12 – 10.2(S) 10.30– 10.6(S)	10.6– 13.6(S) 13.6 – 20.0(D) 20.0– 25.16(I)	
NM 2	0.0 – 0.5 (O)	0.5 – 3.2(S)	5.0 – 6.1 (S)	3.2 – 5.0(S) 6.1 – 7.0 (S) 7.0 – 8.2(D)		8.2 – 13.56(D) 13.56 – 20.0(S)
NM 3	0.0 – 2.3(GC)		2.3 – 3.36(D)	3.36 – 4.42(D)	4.42 20.0 (S)	
NM 4	0.0 – 0.2 (O)	0.2 – 1.67(S)	1.67 – 2.67(S)	2.67 – 4.6(S)	4.6 – 20.0(S)	
NM 5	0.0 – 0.24 (O) 0.24 – 3.29 (SC)	3.29 – 5.13 (S)	5.13 – 7.1(S)	7.1 – 10.12 (S)	10.1-11.53(S)	11.53-25.27(S)
NM 6	0.0 – 0.5 (O)	0.5 – 9.76 (S) 9.76 – 17.3 (D)	17.3–18.2(D)	18.2-18.53(D) 18.53-19.6(S)	19.6 – 25.6(S)	
NM 7	0.0 – 0.2(O)	0.2 – 1.32 (S) 14.1-18.5(D)	1.32 – 5.5(S) 12.85–14.1(S) 18.5-20.2(D)	5.5 – 12.85(S) 20.2-23.0(D)	23.0-25.0(S)	
NM8	0.0 – 0.9 (O)	0.9 – 4.0 (S)	4.0 – 7.75(S) 19.6 – 20.0(S)	7.75 – 19.6(S)		
NM9	0.0 – 0.25(O)	0.25-1.7(S)	1.7-3.1(S) 4.2-5.14(S) 6.25-8.73(S)	3.1-4.2(S) 5.14-6.25(S) 8.73-9.30(S)	9.3-12.0(S)	12.0-20.11(S)
NM10		0.9 – 1.5(S) 5.14-5.28(S)	0.0 – 0.9(S) 1.5-5.14(S)		5.28-7.4(S)	7.4-20.02(S)

Water pressure tests were conducted by using single packers in sections of 3 m length and maximum water pressures of about $15 \times D$ for packers set in soil and $22 \times D$ for packers set in rock (where D is the depth of the packer below ground surface). Each test section was subjected to five (ascending and descending) water pressures (each for a period of 10 minutes), and the corresponding water losses were measured. The Lugeon value for each increment of water pressure was calculated as follows:

$$\text{Lugeon} = (1000 \times V)/(T \times L \times P)$$

Where: V = Volume of water pumped in litres

T = Time of water pumped in minutes

L = Length of test section in metres

P = Pumping pressure in kPa

For each test section, five Lugeon values (one for each pressure increment) were calculated, and the most appropriate Lugeon value was selected from the flow pattern (laminar, turbulent, dilation, blockage or wash-out) according to the guidelines produced by *Houlsby (1976)*.

The results of the water pressure tests are presented in **Table 6.2**.

Table 6.2: Summary of water pressure test results

BH No.	Depth untested	LUGEON VALUES (values <0.1 Lugeon not given))		
		0.1 -1	1.1 – 4 (actual Lugeons)	>4 (actual Lugeons)
		Depth in m	Depth in m	Depth in m
NM 1	0 – 2 23-25.16	5-11 14-20	11-14 (1.2) 20-23	2-5 (5.6)
NM 2	0-2	2-5 11-14 17-20	14-17 (1.5)	-
NM 3	0-2	-	-	-
NM 4	0-2	-	-	-
NM 5	0-2 23-25.27	2-5 8-11 14-23	5-8 (1.7) 11-14 (1.1)	-
NM 6	0-2 23-26.6	2-5 8-11 14-23	5-8 (1.7) 11-14 (1.1)	-
NM 7	0-2 23-25	5-8 14-20	2-5 (1.2) 11-14 (2) 20-23 (1.4)	-
NM 8	0-2	-	-	-
NM 9	0-2	2-5 8-11	11-14 (1.6)	14 – 20 (TOTAL)

All boreholes along the dam centre line were equipped with standpipe piezometers. The water level readings are given in **Table 6.3**.

Table 6.3: Water rest levels in boreholes

BH No	Date completed	Date measured	Water level (m)	Water level Elevation (masl)
NM 1	2013-04-03	2103-03-04 2013-04-15	14.3 dry	880.5
NM 2	2013-04-08	2013-04-08 2013-04-15	6.5 dry	881.8
NM 3	2013-04-05	2013-04-15	dry	
NM 4	2013-03-23	2013-04-15	dry	
NM 5	2013-04-05	2013-04-05 2013-04-15	9.85 dry	881.5
NM 6	2013-03-22	3013-03-22 2013-04-15	13.2 dry	895.0
NM 7	2013-03-23	2013-03-23 2013-04-15	10.78 dry	901.8
NM 8	2013-04-15	2013-04-15	dry	

It is very unlikely that boreholes drilled within the wetland (Boreholes NM 2 and NM 3) can be dry at any time. This unfortunately puts a question mark on all the water level measurements that were done by the drilling contractor. Further piezometer readings and investigations into the probable cause for this anomaly will have to be done.

6.2.1 Discussion of drilling results

The results of the seismic survey, the drilling and the interpretation of the geology are shown on **Figure A6.1** included in **Annexure A**.

Most of the left flank (section chainage 0 – 250 m) is occupied by horizontally bedded shale under a thin (<0.3 m) cover of transported soil. A 7 m thick horizontal dolerite sill was encountered in the river section, and is expected to continue at depth under the left flank.

The shale is completely weathered to a depth of about 2 m and moderately weathered with layers of highly weathered shale to about 10 m. Deeper down the shale is slightly weathered or unweathered. The shale is thinly bedded, hence the borehole cores show moderate to low RQD values.

The river section (section chainage 250 m – 320 m) is underlain by shale, while between chainages 320 m and 480 m the underlying horizontal dolerite sill is covered only by a thin (2 m) layer of transported soil. A fault that intersects the centre line displaces the dolerite sill by about 8 m so that the dolerite occurs at a higher level on the right flank.

The shale is completely weathered to a depth of 2 m - 3 m and moderately weathered with layers of highly weathered shale to between 7 m and 10 m. Deeper down the shale is slightly weathered or unweathered. The dolerite below the shale is highly and moderately weathered to about 2 m after which it is slightly weathered.

Weathering conditions along the fault zone are unknown, but according to the seismic results, poor rock conditions might occur to a depth of 20 m.

The right flank (section chainage 480 m – 660 m) is occupied by horizontally bedded shale under a thin layer (<0.3 m) of transported soil. The horizontal dolerite sub-outcrops (outcrop covered by colluvium) between elevations 888 masl and 898 masl and it thins to about 4 m deeper into the flank.

In Borehole NM 6 the shale and the dolerite are completely weathered to 18 m depth, while in Borehole 7 the shale is completely weathered to the dolerite contact at about 18 m and the dolerite below is moderately weathered to its base at 23 m.

6.2.2 Founding conditions for alternative dam types

a) Earth embankment shells

The shells of an earth embankment are typically founded on material with low organic content, low compressibility and with shear strength similar to the dam wall material. This means that a 0.6 m – 1.5 m thick layer of organic topsoil and loose transported soil has to be removed along the centre line and that founding will take place on stiff transported sandy clay or weak completely weathered shale or weak residual dolerite.

b) Core trench

The clay core of an earthfill or rockfill dam is normally founded on material that is either sufficiently impervious or can be rendered impervious by means of grouting. These depths vary between 3.1 m to 5.0 m along the centre line (see **Figure A6.2** included in **Annexure A**).

c) Rockfill embankment shells

The shells of a rockfill embankment are typically founded on material with low organic content, low compressibility and with shear strength similar to the dam wall material. Along most of the centre line between 1.6 m and 5.3 m of colluvium and residual soil/completely weathered shale has to be removed. However in the area of Borehole NM 6 on the right flank, weak completely weathered shale and dolerite extend to a depth of over 17 m (see **Figure A6.3** included in **Annexure A**). This excavation will yield a considerable volume of material, some of which might be suitable as semi-pervious earthfill. The volume and properties of this material must be further investigated during the design stage.

d) Plinth for concrete faced rockfill

In the case of a concrete faced rockfill (CFR) dam, founding of the plinth will require material with either low permeability or good groutability. The depths vary between 5 m and 17.5 m (see **Figure A6.4** included in **Annexure A**).

e) Concrete gravity

A concrete gravity dam is normally founded on good quality rock with a minimum rock mass rating (RMR) of 50, giving it an E-value of at least 10 GPa and with shear strength parameters along the most critically orientated discontinuities of $C = 250$ kPa and $\phi = 34$ degrees.

Due to the presence of closely spaced continuous weak bedding planes in the highly and moderately weathered shale, and to some extent also in the slightly weathered and unweathered shale, the above requirement for shear strength are only marginally met in slightly weathered and unweathered shale. This means that excavation depths for a concrete dam will extend to between 5 m and 8.5 m in the river section and up to 23 m along a section of the right flank. (see **Figure A6.3** included in **Annexure A**).

For concrete structures where shear strength is not critical (e.g. spillway chute), founding can take place on moderately weathered shale at considerably shallower depths. The recommended excavation depths at borehole positions are listed in **Table 6.4**.

Table 6.4: Recommended excavation depths at the various borehole positions

BH No.	ELEVATION (masl)	EXCAVATION DEPTHS IN METRES (VERTICAL)				
		Earth shells	Rock shells	Core	Concrete dam	Plinth
NM9	916.31	1.0	2.3	3.1	10.0	5.0
NM1	894.68	0.8	1.6	5.0	12.0	5.0
NM2	888.36	1.0	3.5	3.5	8.5	6.2
NM3	882.03	1.5	3.0	5.5	6.0	5.0
NM4	886.90	1.0	2.6	2.6	5.0	3.0
NM5	891.31	1.0	5.3	5.3	11.0	6.0
NM6	908.24	0.6	17.3	5.0	20.0	17.5
NM7	912.61	0.6	3.0	6.0	23.0	8.0
NM8	919.00	1.0	7.6	5.0	n/a	7.6
NM10	n/a	0.5	2.0	5.5	7.0	5.5

f) Grouting

In most of the boreholes along the centre line water losses of less than 4 Lugeon units were recorded. The only exceptions are Boreholes NM 1 and NM 6 where 5.6 Lugeons and 17 Lugeons respectively were measured between 2 m and 5 m and in Borehole NM 9 where total water loss occurred below 14 m depth. There are no indications in the core that high water losses might be encountered in these intervals, and it is possible that the packers did not seal properly.

All the boreholes were reported to be dry a few days or weeks after drilling was completed. These results are considered incorrect.

For a dam of this height, it will be necessary to make provision for a grout curtain to a depth of about 66% of the water head along the centre line. Although grout penetration might be small except in local zones, the drilling, water test and grout records from a grouting operation is very important and can be considered the final stage of a geotechnical investigation when sub-surface information is obtained at close intervals below the footprint of the dam.

6.3 SPILLWAY CONTROL AND RETURN CHANNEL

The layout of the proposed spillway control structure and return channel (chute) is shown in **Figure A5.1** included in **Annexure A**.

Borehole NM 10 was drilled in the general area for a control structure. It shows an excavation depth of about 5.5 m for a concrete control structure and concrete lined chute. This condition is considered representative for the area where the control structure and chute is presently proposed.

7 RESERVOIR RIM STABILITY

7.1 RESERVOIR RIM STABILITY

Slopes around the reservoir rim are generally flatter than 16 degrees and are underlain by a shallow cover of soil, followed by horizontally bedded shale. Small scale slumping of the thin soil layer may occur from time to time due to fluctuating water levels, but the risk for large slope failures that might endanger the dam is considered negligible.

8 CONCLUSIONS

8.1 AVAILABLE INFORMATION

Information from published geological maps was used to describe the general geology of the area.

8.2 GENERAL GEOLOGY

The area around the site is underlain by rocks of the Pietermaritzburg Formation of the Ecca Group, comprising shales (mudrocks) with sub-ordinate sandstones. The sedimentary strata are essentially horizontal, and largely undisturbed. Regional dips of 3 – 5 degrees are recorded. A near-horizontal dolerite sill had intruded into the sedimentary strata and occurs below a cover of shale at the dam centre line and the quarry. A fault with a throw of about 8 m intersects the dam centre line.

8.3 SEISMIC REFRACTION SURVEYS

Seismic refraction surveys were conducted along the proposed dam centre line. Although the seismic velocities tended to over-estimate the depth of sound rock, they were useful in showing the presence of the dolerite sill below a cover of shale and also to identify the positions of a fault.

8.4 SEISMIC RISK ANALYSIS

A Probabilistic Seismic Hazard Analysis (PSHA) was conducted for the Smithfield and Langa sites by Dr A Kijko of the Natural Hazards Assessment Consultancy.

Results for the horizontal component of earthquake acceleration are as follows:

- ◆ Operating Basis Earthquake (Return period 144 years) =0.016 g.
- ◆ Maximum Design Earthquake (Return Period 475 years) =0.021 g.
- ◆ Maximum Credible Earthquake (MCE (Return period 10 000 years) =0.113 g.

8.5 MATERIALS INVESTIGATION

An extensive wetland in the dam basin, and cultivated lands on the left flank placed severe environmental restrictions on the digging of test pits and drilling of boreholes for the investigation of potential construction material sources.

Four potential sources for construction materials have been investigated, namely (i) spoil from the tunnel excavation, (ii) material excavated for the tunnel outlet portal, (iii) material excavated from the spillway approach area and (iv) material from a quarry located below FSL in the dam basin. The estimated volumes available from these sources in relation to the required volumes are shown in **Table 8.1**.

Table 8.1: Estimated volume of embankment materials from borrow areas, tunnel spoil and the tunnel outlet portal

Type of material	Required (x 1000 m ³) Percentage of available materials in brackets			Available (x 1000 m ³)			
	For CFR Dam	For CCR Dam	For zoned embankment	Tunnel spoil (outlet section)	Portal excavation	Spillway approach	Quarry
Overburden for spoil: Organic topsoil	0	0	0	0	8	15	20
Impervious core:	0	250 (0%)	350 (0%)	0	0	0	0
Semi-pervious fill: Residual silty clayey sand and sandy silty clay	0	0	1 020 (90%)	0	230	35	120
Semi-pervious fill: Highly weathered shale					70	280	180
Soft rockfill: Moderately weathered shale	1200 (124%)	900 (165%)		0	50	20	350
Hard rockfill: Unweathered shale and dolerite			280 (532%)	250	40	0	1 200

It appears that none of the available materials qualifies as impervious fill and that the available quantity of semi-pervious material is not quite sufficient to provide twice the required volume for a zoned embankment dam.

A considerable volume of soft rockfill (weathered shale) will have to be removed from the quarry in order to reach the hard shale and dolerite rockfill. This soft material can be used in certain zones of any of the alternative embankment dam types.

There is sufficient hard rockfill for construction of a CFR or ECR Dam. For any of these dam types, durable dolerite may have to be imported from a commercial quarry (Pietermaritzburg) to serve as protective layer above the shale or dolerite shale mixture. Some or all of this dolerite might be obtained from the quarry.

Due to the absence of impervious core material, consideration will have to be given to a Concrete Faced Rockfill Dam or an Earth Core Rockfill Dam with impervious core comprising a mixture of soil and bentonite. The Concrete Faced Rockfill option appears to be the more feasible, since the available soils contain too much clay to be mixed with bentonite.

8.6 GEOTECHNICAL INVESTIGATION

Seismic surveys and core drilling between elevations 900 masl and 919 masl along the left flank were restricted due to the presence of cultivated lands. Although there is a gap of about 250 m between boreholes on this flank, the geology is fairly homogeneous and the interpretation of founding conditions should be reasonably accurate.

Founding conditions for all types of dams are unfavourable as a result of deep weathering, especially along the right flank. This will involve in moderate to very deep excavations for rockfill shell and the plinth of a CFR dam and very deep excavations for a concrete gravity dam

For the *shells of an earth embankment* 0.6 m – 1.5 m organic topsoil and loose transported soil has to be removed along the centre line and founding will take place on stiff transported sandy clay or weak completely weathered shale or weak residual dolerite.

For the *shells of a rockfill embankment* between 1.6 m and 5.3 m of colluvium and residual soil/completely weathered shale has to be removed along most parts of the

centre line. However in an area on the right flank, weak completely weathered shale and dolerite extend to a depth of over 17 m.

For the *core of an embankment dam* the depth of excavation will vary between 3 m to 5 m along the centre line. The depth for the *plinth of a concrete faced rockfill dam* will in many sections be only slightly deeper than for the core trench, except in an area on the right flank where it is much deeper.

Excavation depths for a *concrete gravity dam* will extend between 5 m and 8.5 m in the river section and up to 23 m along a section of the right flank.

It will be necessary to make provision for a grout curtain to a depth of about 66% of the water head along the centre line.

A spillway control structure and concrete lined return channel can be founded on moderately weathered shale at an average depth of about 5.5 m. A stilling basin and apron will have to be provided at the end of the chute.

8.7 STABILITY OF RESERVOIR RIM

Slopes around the reservoir rim are generally flatter than 16 degrees and are underlain by a shallow cover of soil, followed by horizontally bedded shale. The risk for slope failures that might endanger the dam wall is considered negligible.

As a result of environmental restrictions on the positioning of seismic lines, test pits and boreholes, this investigation was limited. Hence, additional investigations for the design stage are recommended.

9 RECOMMENDATIONS

It is recommended that the following additional materials and geotechnical investigations be conducted during the design stage:

- ◆ Test pitting in the spillway approach area, together with soil sampling and laboratory testing to determine the properties of material to be excavated. These tests should include grading, Atterberg Limits, Standard Proctor Compaction, permeability, triaxial shear strength and dispersivity.
- ◆ Additional test pitting in the tunnel outlet portal area, together with soil sampling and laboratory testing to determine the properties of material to be excavated. These tests should include grading, Atterberg Limits, Standard Proctor Compaction, permeability, triaxial shear strength and dispersivity.
- ◆ Additional rotary core drilling in the quarry area to determine the extent of the dolerite sill and its potential use for concrete aggregate, rip-rap and filters.
- ◆ Additional rotary core drilling, water testing and SPT testing along the dam centre line to provide information on founding conditions along the left flank, the suspected fault zone on the lower right flank and the area of deep weathering on the right flank.
- ◆ Additional drilling, soil sampling and testing in the area of Borehole NM 6 to determine the properties and volume of potential impervious soil from the dam excavation.
- ◆ Additional rotary core drilling at the spillway control structure, return channel and stilling basin to provide information on founding conditions.
- ◆ Further piezometer readings at existing boreholes and investigations to explain the anomalous water level observations.

10 REFERENCES


Badenhorst, D. (1988). *Die ontwerp van grond- en rotsvuldamsstrukture; Unpublished dissertation for Masters Degree in Engineering*. Pretoria, South Africa: University of Pretoria.


Houlsby, A. (1976). *Routine interpretation of the Lugeon water test*. *Quart. Jnl. Engng. Geol.*, 9(4), 303-313. Pretoria, South Africa.

SAIEG-AEG-SAICE (Geotechnical Division). (1990). *Guidelines for soil and rock logging: Geoterminology Workshop*. Pretoria, South Africa: SAIEG-AEG-SAICE (Geotechnical Division).

Annexure A

Figures





GEOLOGICAL LEGEND

AGE	SUPERGROUP	GROUP	FORMATION	SYMBOL	LITHOLOGY
Jurassic				Jd	Dolerite
Permian	Karoo Supergroup	Beaufort Group	Andelaide (Pa)	Pa/Pes	Siltstone; fine grained sandstone; subordinate mudrock (Pa)/ Dark grey shale often carbonaceous; siltstone; medium to coarse grained sandstone; subordinate thin conglomerate
			Estcourt (Pes)		
		Ecca Group	Volkruist	Pvo	Dark blue grey shale; subordinate thin sandstone
			Vryheid	Pv	Medium to coarse grained sandstone with thin grit beds; subordinate grey shale and siltstone; sporadic coal
		Pietermaritzburg	Pp	Dark grey shale; siltstone; subordinate sandstone	
Carboniferous			Dwyka	C-Pd	Diamictite; subordinate varved shale and boulder shale


Project Name :
**uMkhomazi Water Project Phase 1: Module 1:
 Technical Feasibility Study: Raw Water (uMWP1-1/RW)
 Regional Geology Map**


Legend

- Existing Dams
- Proposed Dams
- Pressure tunnels to Baynesfield area (option B)
- Raw Water Pipeline Infrastructure

FIGURE A4.1

Drawn: LC Gallagher
 Checked: G Rabodiba
 Date: 2013-07-29
 Map Ref: P:\GIS\Water\umkhomazi_Geotechnical.map
 View Ref: Regional Geology Map
 Project No: J01763





Test pits
Coordinates list - Lat Long

MTP04	- Y - 67849
	X - 3296898
MTP05	- Y - 68039
	X - 3297099
MTP07	- Y - 68251
	X - 3297273
MTP08	- Y - 68228
	X - 3297607
MTP09	- Y - 68170
	X - 3297743
MTP10	- Y - 68040
	X - 3297829
MTP11	- Y - 67964
	X - 3297696
MTP12	- Y - 67870
	X - 3297729
MTP13	- Y - 67870
	X - 3297600
MTP14	- Y - 67849
	X - 3297510
MPT15	- Y - 67994
	X - 3297304
MTP16	- Y - 67803
	X - 3297335
MTP18	- Y - 67883
	X - 3297883

BH	Y	X	Z
NQ1	-125249.445	3298328.576	918.431
NQ2	-125341.516	3298146.686	909.826
NQ3	-125453.850	3297975.284	900.292

Borehole	X	Y	Height
NM1	-125595.338	3297338.564	894.686
NM2	-125625.143	3297326.444	888.362
NM3	-125672.084	3297332.197	882.029
NM4	-125700.914	3297379.638	886.896
NM5	-125735.854	3297372.024	891.309
NM6	-125823.200	3297408.093	908.239
NM7	-125855.854	3297437.009	912.606
NM8	-125976.923	3297416.905	918.999
NM9	-125351.076	3297377.864	916.316
NM10	-125224.410	3297164.243	897.106

Seismic lines		X
G1G2+00	67831.57	3296853
G2AG3A+00	67731.57	3296805
G3BG4+00	67691.72	3296851

Project Name : **uMkhomazi Water Project Phase 1: Module 1: Technical Feasibility Study: Raw Water (uMWP1-1/RW)\ Langa Dam Site - Plan showing proposed layout of structure, seismic lines, sections, test pits and boreholes**

Legend

- 5 m Contours
- 920 contour
- Langa Balancing Dam Layout
- Main Rivers
- Borehole Positions
- Test Pits
- Quarry
- Approach Areas
- Spillway chute
- Sections
- Seismic Lines

FIGURE A5.1

Drawn: LC Gallagher
 Checked: D van der Merwe
 Date: 2013-07-30
 Map Ref: G:\GIS\Water\uMkhomazi_WG31.map
 View Ref: Proposed Layout of Structure
 Project No: J01763



Project Name :

**uMkhomazi Water Project Phase 1: Module 1:
Technical Feasibility Study: Raw Water (uMWP1-1/RW)
Proposed tunnel outlet portal excavation**




Legend

- 5 m Contours
- Tunnel Exit Portal Test Pits
- New Proposed Conveyance Structure

FIGURE A5.2

Drawn: LC Gallagher
 Checked: D van der Merwe
 Date: 2013-07-29
 Map Ref: G:\GIS\Water\uMkhomazi_WG31.map
 View Ref: Proposed tunnel Outlet Portal excavation
 Project No: J01763




ELEVATION (masl)

ELEVATION (masl)

Not to be scaled

SECTION LEGEND	
	GROUND SURFACE LINE
	SOIL/ROCK CONTACT
	WEATHERED ROCK/HARD ROCK CONTACT
	DOLERITE /SHALE CONTACT
	SUSPECTED FAULT
	QUARRY BOUNDARY


SECTION LEGEND			
REC	W	T	
C	R	SM	T
REC = CORE RECOVERY (C) AND RQD (R)			
W = DEGREE OF WEATHERING, T= MATERIAL TYPE			
CORE RECOVERY AND RQD 95-100%			
CORE RECOVERY AND RQD 75-94%			
CORE RECOVERY AND RQD 50-74%			
CORE RECOVERY AND RQD 26-49%			
CORE RECOVERY AND RQD 0-25%			
UNWEATHERED ROCK			
SLIGHTLY WEATHERED ROCK			
MODERATELY WEATHERED ROCK			
HIGHLY WEATHERED ROCK			
COMPLETELY WEATHERED ROCK			
RESIDUAL AND TRANSPORTED SOILS			
ORGANIC TOPSOIL			
CLAYEY SILTY SAND			
CLAYER SILTY SAND WITH BOULDERS AND GRAVEL			
SHALE			
INDURATED SHALE			
DOLERITE			



Not to be scaled

SECTION LEGEND	
	GROUND SURFACE LINE
	SOIL/ROCK CONTACT
	WEATHERED ROCK/HARD ROCK CONTACT
	QUARRY BOUNDARY

SECTION LEGEND			
REC	W		
C	R	SM	T
REC = CORE RECOVERY (C) AND RQD (R)			
W = DEGREE OF WEATHERING, T= MATERIAL TYPE			
			CORE RECOVERY AND RQD 95-100%
			CORE RECOVERY AND RQD 75-94%
			CORE RECOVERY AND RQD 50-74%
			CORE RECOVERY AND RQD 26-49%
			CORE RECOVERY AND RQD 0-25%
			UNWEATHERED ROCK
			SLIGHTLY WEATHERED ROCK
			MODERATELY WEATHERED ROCK
			HIGHLY WEATHERED ROCK
			COMPLETELY WEATHERED ROCK
			RESIDUAL AND TRANSPORTED SOILS
			ORGANIC TOPSOIL
			CLAYEY SILTY SAND
			CLAYEY SILTY SAND WITH BOULDERS AND GRAVEL
			SHALE
			INDURATED SHALE
			DOLERITE




ELEVATION (masl)

ELEVATION (masl)

Not to be scaled

SECTION LEGEND	
	GROUND SURFACE LINE
	SOIL/ROCK CONTACT
	DOLERITE /SHALE CONTACT
	SUSPECTED FAULT
	3 500m/s SEISMIC LINE


SECTION LEGEND			
REC	W	REC = CORE RECOVERY (C) AND RQD (R)	
C	R	SM	T



Not to be scaled

SECTION LEGEND	
	GROUND SURFACE LINE
	SUSPECTED FAULT
	EXCAVATION LINE FOR CORE TRENCH
	EXCAVATION LINE FOR CONCRETE CHUTE

SECTION LEGEND				
REC	W	REC = CORE RECOVERY (C) AND RQD (R) W = DEGREE OF WEATHERING, T= MATERIAL TYPE		
C	R	SM	T	
				CORE RECOVERY AND RQD 95-100%
				CORE RECOVERY AND RQD 75-94%
				CORE RECOVERY AND RQD 50-74%
				CORE RECOVERY AND RQD 26-49%
				CORE RECOVERY AND RQD 0-25%
				UNWEATHERED ROCK
				SLIGHTLY WEATHERED ROCK
				MODERATELY WEATHERED ROCK
				HIGHLY WEATHERED ROCK
				COMPLETELY WEATHERED ROCK
				RESIDUAL AND TRANSPORTED SOILS
				ORGANIC TOPSOIL
				CLAYEY SILTY SAND
				CLAYEY SILTY SAND WITH BOULDERS AND GRAVEL
				SHALE
				INDURATED SHALE
				DOLERITE




ELEVATION (masl)

ELEVATION (masl)

Not to be scaled

SECTION LEGEND	
	GROUND SURFACE LINE
	EXCAVATION LINE FOR ROCKFILL SHELLS
	SUSPECTED FAULT

SECTION LEGEND			
REC	W		
C	R	S	T
REC = CORE RECOVERY (C) AND RQD (R)			
W = DEGREE OF WEATHERING, T= MATERIAL TYPE			
CORE RECOVERY AND RQD 95-100%			
CORE RECOVERY AND RQD 75-94%			
CORE RECOVERY AND RQD 50-74%			
CORE RECOVERY AND RQD 26-49%			
CORE RECOVERY AND RQD 0-25%			
UNWEATHERED ROCK			
SLIGHTLY WEATHERED ROCK			
MODERATELY WEATHERED ROCK			
HIGHLY WEATHERED ROCK			
COMPLETELY WEATHERED ROCK			
RESIDUAL AND TRANSPORTED SOILS			
ORGANIC TOPSOIL			
CLAYEY SILTY SAND			
CLAYER SILTY SAND WITH BOULDERS AND GRAVEL			
SHALE			
INDURATED SHALE			
DOLERITE			



ELEVATION (masl)

ELEVATION (masl)

Not to be scaled


SECTION LEGEND	
	GROUND SURFACE LINE
	SUSPECTED FAULT
	EXCAVATION LINE FOR PLINTH

SECTION LEGEND			
REC	W		
C	R	SM	T
REC = CORE RECOVERY (C) AND RQD (R)			
W = DEGREE OF WEATHERING, T= MATERIAL TYPE			
			CORE RECOVERY AND RQD 95-100%
			CORE RECOVERY AND RQD 75-94%
			CORE RECOVERY AND RQD 50-74%
			CORE RECOVERY AND RQD 26-49%
			CORE RECOVERY AND RQD 0-25%
			UNWEATHERED ROCK
			SLIGHTLY WEATHERED ROCK
			MODERATELY WEATHERED ROCK
			HIGHLY WEATHERED ROCK
			COMPLETELY WEATHERED ROCK
			RESIDUAL AND TRANSPORTED SOILS
			ORGANIC TOPSOIL
			CLAYEY SILTY SAND
			CLAYEY SILTY SAND WITH BOULDERS AND GRAVEL
			SHALE
			INDURATED SHALE
			DOLERITE

Annexure B

Test pit profiles


***Langa Dam centre line
(MTP1, MTP2, MTP4)***



CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 12/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
 X-COORD : X3296981
 Y-COORD : 31 Y0067498




NOTES

- 1) No groundwater seepage encountered.
- 2) Sidewalls stable.
- 3) No samples taken.
- 4) Difficult excavation at 4.5m.

CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 12/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
 X-COORD : X3296922
 Y-COORD : 31 Y0067547



NOTES

- 1) No groundwater seepage encountered.
- 2) Sidewalls stable.
- 3) Bulk and disturbed samples taken 1.0--2.6m.
- 4) Difficult excavation at 2.6m.


CONTRACTOR : Geomechanics
MACHINE : 20 Tonne Excavator
DRILLED BY :
PROFILED BY : G.Rabodiba
TYPE SET BY : G.Rabodiba
SETUP FILE : STANDARD.SET

INCLINATION :
DIAM : Trench
DATE :
DATE : 13/02/2013
DATE : 03/06/2013 14:29
TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
X-COORD : X3296898
Y-COORD : 31 Y0067849

HOLE No: MTP 4


Borrow area
(MTP5, MTP7-MTP18)



CONTRACTOR : Geomechanics
MACHINE : 20 Tonne Excavator
DRILLED BY :
PROFILED BY : G.Rabodiba
TYPE SET BY : G.Rabodiba
SETUP FILE : STANDARD.SET

INCLINATION :
DIAM : Trench
DATE :
DATE : 13/02/2013
DATE : 03/06/2013 14:29
TEXT : ..eaMTPTestpitprofiles.txt


ELEVATION :
X-COORD : X3297099
Y-COORD : 31 Y0068039



CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 13/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt


ELEVATION :
 X-COORD : X3297273
 Y-COORD : 31 Y0068251



CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 12/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
 X-COORD : X3297600
 Y-COORD : 31 Y0068100



NOTES


- 1) No groundwater seepage encountered.
- 2) Sidewalls stable.
- 3) No samples taken.
- 4) Difficult excavation at 3.5m.

CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 12/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
 X-COORD : X3297800
 Y-COORD : 31 Y0068169


Scale
 1:10



CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 12/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
 X-COORD : X3297829
 Y-COORD : 31 Y0068000



NOTES


- 1) No groundwater seepage encountered.
- 2) Sidewalls stable.
- 3) Disturbed samples taken at 0.5--1.2m and 1.2--3.5m.
- 4) Difficult excavation at 3.5m.

CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 12/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
 X-COORD : X3297696
 Y-COORD : 31 Y0067950

Scale
 1:10



0.00

Moist brown soft SILT with scattered and roots. TRANSPORTED.

0.20

Khaki brown highly weathered to moderately weathered thinly bedded with lenses of reddish brown clay infill (200mm) soft rock to medium hard rock SHALE with lenses of grey hard rock shale at 1.2m to 1.4m.

2.00


NOTES

- 1) No groundwater seepage encountered.
- 2) Sidewalls stable.
- 3) No samples taken.
- 4) Difficult excavation at 2.0m.

CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 12/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt


ELEVATION :
 X-COORD : X3297815
 Y-COORD : 31 Y0067886



CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 12/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
 X-COORD : X32975634
 Y-COORD : 31 Y0067865




NOTES

- 1) No groundwater seepage encountered.
- 2) Sidewalls stable.
- 3) No samples taken.
- 4) Difficult excavation at 2.4m.

CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 12/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
 X-COORD : X3297509
 Y-COORD : 31 Y0067849




NOTES

- 1) No groundwater seepage encountered.
- 2) Sidewalls stable.
- 3) Bulk and disturbed samples taken at 0.5--3.5m.
- 4) Difficult excavation at 3.5m.

CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 13/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
 X-COORD : X3297310
 Y-COORD : 31 Y0067986




NOTES

- 1) No groundwater seepage encountered.
- 2) Sidewalls stable.
- 3) No samples taken.
- 4) Difficult excavation at 2.4m.

CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 12/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
 X-COORD : X3297335
 Y-COORD : 31 Y0067803



NOTES


- 1) No groundwater seepage encountered.
- 2) Sidewalls stable.
- 3) Disturbed samples taken 0.4--1.1m and 1.1--3.8.
- 4) Difficult excavation at 3.8m.

CONTRACTOR : Geomechanics
 MACHINE : 20 Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 13/02/2013
 DATE : 03/06/2013 14:29
 TEXT : ..eaMTPTestpitprofiles.txt

ELEVATION :
 X-COORD : X3297081
 Y-COORD : 31 Y0067883

***Tunnel outlet portal
(TP01-TP04)***




NOTES

- 1) No groundwater seepage encountered.
- 2) Sidewalls stable.
- 3) Bulk, disturbed samples taken 0.6--4.6m and undisturbed sample taken at 3.4m.
- 4) Excavated to refusal at 4.6m.

CONTRACTOR : Geomechanics
 MACHINE : 20Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 11/02/2013
 DATE : 18/06/2013 12:30
 TEXT : ..\TunnelPortalsOutlet.txt

ELEVATION :
 X-COORD : X3295236
 Y-COORD : 31 Y0067415




NOTES

- 1) Groundwater seepage encountered at 3.0m.
- 2) Sidewalls unstable.
- 3) Disturbed samples taken 0.6--2.6m and 2.6--5.0m.
- 4) Excavated to maximum reach of machine.

CONTRACTOR : Geomechanics
 MACHINE : 20Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 11/02/2013
 DATE : 18/06/2013 12:30
 TEXT : ..\TunnelPortalsOutlet.txt

ELEVATION :
 X-COORD : X3295219
 Y-COORD : 31 Y0067425




NOTES

- 1) Groundwater seepage encountered at 1.0m.
- 2) Sidewalls unstable.
- 3) No samples taken.
- 4) Excavated to refusal at 4.6m on highly weathered soft rock shale.

CONTRACTOR : Geomechanics
 MACHINE : 20Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 11/02/2013
 DATE : 18/06/2013 12:30
 TEXT : ..\TunnelPortalsOutlet.txt

ELEVATION :
 X-COORD : X3295191
 Y-COORD : 31 Y0067456



CONTRACTOR : Geomechanics
 MACHINE : 20Tonne Excavator
 DRILLED BY :
 PROFILED BY : G.Rabodiba
 TYPE SET BY : G.Rabodiba
 SETUP FILE : STANDARD.SET

INCLINATION :
 DIAM : Trench
 DATE :
 DATE : 13/02/2013
 DATE : 18/06/2013 12:30
 TEXT : ..\TunnelPortalsOutlet.txt

ELEVATION :
 X-COORD : X3295175
 Y-COORD : 31 Y0067405

Laboratory test results

***Foundation indicator tests
(borrow area)***



T0023




FOUNDATION INDICATOR TEST RESULTS - REP COM 7


Client: Geomechanics	Source/Location:	Job No: 2013-C-184
Project Name: J01763: uMkhomazi Samples	Layer:	Sample No: 3/1361
Project No:	Lane:	Date: 2013/03/27
Hole/TP No: MTP7	Stabilizing Agent:	Test Method: TMH1 A1, A5 & MT1
Depth:	Section:	Client Ref No:
Description: Upper New Mbalingwe Dam	Chainage:	GPS X:
Additional Info:	Offset:	GPS Y:

SIEVE ANALYSIS				ATTEBERG LIMITS		SOIL CLASSIFICATION	
Sieve (mm)	% Passing	Sieve (mm)	% Passing				
75.0	100	0.425	71	Liquid Limit (%)	47	% Gravel	15
63.0	100	0.250	70	Plastic Limit (%)	26	% Sand	45
53.0	100	0.150	69	Plasticity Index (%)	21	% Silt	29
37.5	100	0.075	68	Weighted PI (%)	15	% Clay	11
26.5	100	0.060	40	Linear Shrinkage (%)	8.5	Activity	1.9
19.0	100	0.050	38	Grading Modulus	0.76	Unified Classification	CL
13.2	100	0.020	30	Uniformity coefficient	35	TRB Classification	A - 7 - 6
9.5	100	0.005	18	Coefficient of curvature	3.4		
4.75	96	0.002	11	Remarks:			
2.00	85						


PARTICLE SIZE DISTRIBUTION



POTENTIAL EXPANSIVENESS
Van der Merwe's Activity Chart



CASAGRANDE 'A' LINE





T0023




FOUNDATION INDICATOR TEST RESULTS - REP COM 7


Client: Geomechanics	Source/Location:	Job No: 2013-C-184
Project Name: J01763: uMkhomazi Samples	Layer:	Sample No: 3/1362
Project No:	Lane:	Date: 2013/03/27
Hole/TP No: MTP13	Stabilizing Agent:	Test Method: TMH1 A1, A5 & MT1
Depth:	Section:	Client Ref No:
Description: Upper New Mbalingwe Dam	Chainage:	GPS X:
Additional Info:	Offset:	GPS Y:

SIEVE ANALYSIS				ATTERBERG LIMITS		SOIL CLASSIFICATION	
Sieve (mm)	% Passing	Sieve (mm)	% Passing				
75.0	100	0.425	61	Liquid Limit (%)	42	% Gravel	29
63.0	100	0.250	60	Plastic Limit (%)	27	% Sand	39
53.0	100	0.150	59	Plasticity Index (%)	15	% Silt	23
37.5	100	0.075	58	Weighted PI (%)	9	% Clay	9
26.5	100	0.060	32	Linear Shrinkage (%)	5.5	Activity	1.7
19.0	96	0.050	31	Grading Modulus	1.10	Unified Classification	ML or OL
13.2	91	0.020	28	Uniformity coefficient	105	TRB Classification	A - 7 - 6
9.5	86	0.005	17	Coefficient of curvature	3.0		
4.75	79	0.002	9	Remarks:			
2.00	71						


PARTICLE SIZE DISTRIBUTION



POTENTIAL EXPANSIVENESS
Van der Merwe's Activity Chart



CASAGRANDE 'A' LINE





T0023




FOUNDATION INDICATOR TEST RESULTS - REP COM 7


Client: Geomechanics	Source/Location:	Job No: 2013-C-184
Project Name: J01763: uMkhomazi Samples	Layer:	Sample No: 3/1363
Project No:	Lane:	Date: 2013/03/27
Hole/TP No: MTP18	Stabilizing Agent:	Test Method: TMH1 A1, A5 & MT1
Depth: 0.4 - 1.1	Section:	Client Ref No:
Description: Upper New Mbalingwe Dam	Chainage:	GPS X:
Additional Info:	Offset:	GPS Y:

SIEVE ANALYSIS				ATTEBERG LIMITS		SOIL CLASSIFICATION	
Sieve (mm)	% Passing	Sieve (mm)	% Passing				
75.0	100	0.425	77	Liquid Limit (%)	48	% Gravel	14
63.0	100	0.250	76	Plastic Limit (%)	33	% Sand	35
53.0	100	0.150	75	Plasticity Index (%)	15	% Silt	31
37.5	100	0.075	60	Weighted PI (%)	12	% Clay	20
26.5	100	0.060	51	Linear Shrinkage (%)	6.5	Activity	0.8
19.0	100	0.050	49	Grading Modulus	0.77	Unified Classification	ML or OL
13.2	100	0.020	44	Uniformity coefficient	38	TRB Classification	A - 7 - 5
9.5	99	0.005	32	Coefficient of curvature	0.1		
4.75	97	0.002	20	Remarks:			
2.00	86						


PARTICLE SIZE DISTRIBUTION



POTENTIAL EXPANSIVENESS
Van der Merwe's Activity Chart



CASAGRANDE 'A' LINE



***Double hydrometer tests
(borrow area)***



Double Hydrometer Test Result

ASTM
D4221

Client Geomechanics

Project J01763: uMkhomazi: Smithfield Dam


Job no 2013-C-395

Sample no TP A10 + A17 + A19

Depth (m) -

Date 10/05/2013

Lab no 3/2838



Dispersion:

14%



Double Hydrometer Test Result

ASTM
D4221

Client Geomechanics

Project J01763: uMkhomazi: Smithfield Dam


Job no 2013-C-395

Sample no TP A15 + A22 + B9

Depth (m) -

Date 10/05/2013

Lab no 3/2839



Dispersion: 32%

***Various test results
(tunnel outlet portal)***



T0023

GEOSTRADA

engineering materials laboratory



SUMMARY OF TEST RESULTS ON SOILS - REP COM 2

Client: Aecom **Project:** uMkhomazi Water Project Phase 1: Module 1: Technical Feasibility Study **Project Number:** J01763 **Job No:** 2013-C-746 **Date:** 30/07/2013

Sample No	Hole No / TP No	Depth (mm)	Description	Percentage Passing Sieve (mm) - TMH1 A1, A5, MT1																	% Gravel > 2.00 mm	% Sand 2.00 - 0.060 mm	% Silt 0.060-0.002 mm	% Clay < 0.002mm	Atterberg Limits (TMH1 A2-A4) < 0.425 mm			Maximum Dry Density (kg/m³) & OMC (%) (TMH1 A7)	CBR (Modified AASHTO) TMH1 A8								
				Sieve Analysis																					LL	PI	LS		% Swell	90%	93%	95%	97%	98%	100%		
				53.0	37.5	26.5	19.0	13.2	9.5	4.75	2.00	0.425	0.250	0.150	0.075	0.060	0.050	0.020	0.005	0.002																GM	
3/5439	TPE1	50 - 500	Clayey Silt with cobbles					100	99	95	81	57	52	49	47	43	42	38	29	24	1.15	19	38	19	24	40	19	7.5	1795	10.8	0.1	15	24	32	42	48	63
3/5442	TPO2	60 - 260	Clayey Silt with cobbles			100	95	95	93	90	88	87	87	86	86	84	73	60	50	0.39	12	2	36	50	57	27	12.0	1881	16.4	0.5	3.1	4.7	6.2	8.4	10	13	
3/5443	BH2	175 - 225	Clayey Sand with gravel & cobbles						100	99	92	88	87	87	86	85	78	68	62	0.33	8	6	24	62	51	25	9.5										
3/5444	BH7	350 - 400	Sandy Clay								100	99	98	98	96	94	91	77	73	67	0.05	0	6	27	67	58	23	12.5									

Remarks: * Sample flocculated

Everything possible is done to ensure that tests are representative and are performed accurately, and that reports and conclusions are quoted correctly. Geostrada or its officials can in no way be held liable for consequential damage or loss due to any error in carrying out the tests, nor for any erroneous statement or opinion contained in a report based on such tests. If a test report is published or reproduced by the client, it will be done in full, without any omission.




FOUNDATION INDICATOR TEST RESULTS - REP COM 7


Client: Aecom	Source/Location:	Job No: 2013-C-746
Project Name: uMkhomazi Water Project Phase 1: Module 1: Technical Feasibility Study	Layer:	Sample No: 3/5442
Project No: J01763	Lane:	Date: 30/07/2013
Hole/TP No: TPO2	Stabilizing Agent:	Test Method: TMH1 A1, A5 & MT1
Depth (mm): 60 - 260	Section:	Client Ref No:
Description: Clayey Silt with cobbles	Chainage:	GPS X:
Additional Info:	Offset:	GPS Y:

SIEVE ANALYSIS				ATTERBERG LIMITS		SOIL CLASSIFICATION	
Sieve (mm)	% Passing	Sieve (mm)	% Passing				
75.0	100	0.425	87	Liquid Limit (%)	57	% Gravel	12
63.0	100	0.250	87	Plastic Limit (%)	30	% Sand	2
53.0	100	0.150	87	Plasticity Index (%)	27	% Silt	36
37.5	100	0.075	86	Weighted PI (%)	23	% Clay	50
26.5	100	0.060	86	Linear Shrinkage (%)	12.0	Activity	0.5
19.0	95	0.050	84	Grading Modulus	0.39	Unified Classification	MH or OH
13.2	95	0.020	73	Uniformity coefficient	3	TRB Classification	A - 7 - 5
9.5	93	0.005	60	Coefficient of curvature	0.4		
4.75	90	0.002	50	Remarks:			
2.00	88						


PARTICLE SIZE DISTRIBUTION



POTENTIAL EXPANSIVENESS Van der Merwe's Activity Chart



CASAGRANDE 'A' LINE



SOIL ANALYSIS REPORT




TEL: 088 303 2967

FAX: 086 683 7781

COMPANY: Geostrada
 ADDRESS: 993 Park street
 Hatfield
 CODE: 0083
 TEL NO: 012 432 0500

NAME: uMkhomazi
 YOUR REF: 2013-C-746
 EMAIL: gerriej@geostrada.co.za
 FAX: -
 Job NO: 10199
 DATE: 30/07/2013

Lab No	Ref No	Position	Depth(mm)	pH (H ₂ O)	Conductivity	Na	Mg	CEC	ESP	EMgP	Na	Ca	Mg	SAR
					mS/m	me/100gsoil (cmol+)/kg	me/100gsoil (cmol+)/kg	cmol(+)/kg			me/l	me/l	me/l	
4253	3/5439	TPE 1	50 - 500	6.88	3.24	0.16	5.32	12.42	0.01	0.43	0.24	0.80	3.57	0.17
4254	3/5442	TPO 2	60 - 260	6.63	2.46	0.42	6.95	13.99	0.03	0.5	0.25	0.15	0.29	0.53



 N REEDERS



SHEAR TESTS: BOX SHEAR


KH Head

Client Aecom	Project uMkhomazi Water Project Phase 1: Module 1: Technical Feasibility Study	
Sample no TPO1	Depth (m) 0.06 - 0.45	Date 31/07/2013
Lab no 3/5441	Job no 2013-C-746	

Test Information		
Test Type	-	Slow Drained, saturated
Sample Condition	-	Remoulded to estimated OMC
Normal Stresses	kPa	50, 100, 150
Rate of Strain	mm/min	0.0460



Initial Sample Parameters	Unit	Test 1	Test 2	Test 3	Remarks
Moisture Content	%	28.5	28.5	28.5	Complete test specimen
Dry Density	Kg/m ³	1601	1601	1601	
Void Ratio	-	0.711	0.710	0.710	
Degree of Saturation	%	110.0	109.9	109.9	
Relative Density (SG)	-	2.738			Determined

Final Sample Parameters	Unit	Test 1	Test 2	Test 3	Remarks
Moisture Content	%	35.5	34.5	34.5	
Normal Stress	kPa	50	100	150	
Shear Stress	kPa	41	75	107	
Residual Stress	kPa	Not Tested	Not Tested	Not Tested	
Angle of Internal Friction	Deg.	33			Peak
Cohesion	kPa	8			Peak



Everything possible is done to ensure that tests are representative and are performed accurately, and that reports and conclusions are quoted correctly. Geostrada or its officials can in no way be held liable for consequential damage or loss due to any error made in carrying out the tests, nor for any erroneous statement or opinion contained in a report based on such tests. If a test report is published or reproduced by the client, it will be done in full, without any omission.

Client Aecom	Project uMkhomazi Water Project Phase 1: Module 1: Technical Feasibility Study	
Sample no TPO1	Depth (m) 0.06 - 0.45	Date 31/07/2013
Lab no 3/5441	Job no 2013-C-746	





Flexible Wall Permeability Test

**BS 1377
Part 6**

Client Aecom	Project uMkhomazi Water Project Phase 1: Module 1: Technical Feasibility Study	
Sample no TPO1	Depth (m) 0.06 - 0.45	Date 31/07/2013
Lab no 3/5441	Job no 2013-C-746	

Initial Sample Parameters		
Sample Condition	-	Remoulded to estimated OMC
MDD	kg / m ³	-
OMC	%	-
Consolidation Pressure	kPa	100
Pressure Difference	kPa	10

Test Information			
Moisture Content	Before	%	27.3
	After	%	30.8
Dry Density		Kg/m ³	1529
Initial Void Ratio		-	0.790
Relative Density (SG)		-	2.738 - Determined
Final B Parameter		-	0.97
Co-efficient of Permeability	Min.	m/s	1.7E-10
	Max.	m/s	2.5E-10
	Ave.	m/s	2.0E-10

***Tests on slightly and moderately
weathered shale
(quarry area)***



PROPERTIES OF AGGREGATE - REP AGG 3

Client: Geomechanics

Project Name: uMkhomazi: 2nd Batch Rock Core Testing

Job no : 2013-C-508

Project No: -

Date : 16-05-2013

Sample No	Description	Client Ref No	Sieve Analysis - Percentage Passing Sieve (TMH1 B4)																	FM	ACV (Dry) (%)	ACV (Wet) (%)	Atterberg Limits (TMH 1 A2 - A4)								
			(-0.075mm)																				LL	PI	LS						
			75.0 mm	63.0 mm	53.0 mm	37.5 mm	26.5 mm	19.0 mm	13.2 mm	9.5 mm	6.7 mm	4.75 mm	3.35 mm	2.36 mm	1.18 mm	0.600 mm	0.425 mm	0.300 mm	0.150 mm										0.075 mm		
3/3720	Slightly Weathered Shale					100	97	81	55	40	30	24	18	14	9	6	5	4	3	2.0	2.70	23.9	28.4	24	6	2.5					
3/3721	Moderately Weathered Shale				100	97	89	68	43	31	23	18	15	12	9	6	6	5	4	4.0	2.04	33.3	44.2	30	8	4.5					
																						Test Method	TMH1 B13	TMH1 B1	TMH1 B2						

Remarks:

Everything possible is done to ensure that tests are representative and are performed accurately, and that reports and conclusions are quoted correctly. Geostrada or its officials can in no way be held liable for consequential damage or loss due to any error in carrying out the tests, nor for any erroneous statement or opinion contained in a report based on such tests. If a test report is published or reproduced by the client, it will be done in full, without any omission.

***Aggregate tests on slightly and
moderately weathered shale
(Smithfield quarries)***



SUMMARY OF TEST RESULTS ON SOILS - REP COM 2

Client: Geomechanics
Project Name: uMkhomazi: Rock Core Testing
Project Number: -

Job No: 2013-C-317
Date: 08/05/2013

Sample No	Sample Ref.	Additional Info	Percentage Passing Sieve (mm) - TMH1 A1 & A5												Atterberg Limits (TMH1 A2-A4)			
			Sieve Analysis												< 0.425 mm			
			75.0	63.0	53.0	37.5	26.5	19.0	13.2	9.5	4.75	2.00	0.425	0.075	GM	LL	PI	LS
3/2186	Completely Weathered	As received						100	99	91	61	36	21	16	2.27	31	12	6.0
		After Weathering				100	98	89	72	57	35	20	11	6	2.63	27	7	3.5
3/2187	Highly Weathered	As received						100	92	81	46	26	12	6	2.56	28	7	3.5
		After Weathering				100	98	84	61	44	22	12	6	4	2.78		NP	0
3/2188	Moderately weathered	As received						100	93	81	48	25	9	4	2.62		NP	0.0
		After Weathering				100	97	80	53	39	18	8	4	3	2.85		NP	0.0
3/2189	Moderately weathered - Slaked	As received						100	85	70	41	17	7	2	2.74		NP	0.0
		After Weathering					100	89	72	58	34	12	4	3	2.81		NP	0.0
3/2190	Slightly weathered	As received						100	90	79	46	21	7	2	2.70		NP	0.0
		After Weathering				100	88	69	41	27	15	7	3	2	2.88		NP	0.0
3/2191	Slightly weathered - Slaked	As received						100	94	85	54	26	10	4	2.60	20	3	1.5
		After Weathering				100	98	82	62	52	31	13	5	3	2.79	20	5	2.5


Remarks:

Everything possible is done to ensure that tests are representative and are performed accurately, and that reports and conclusions are quoted correctly. Geostrada or its officials can in no way be held liable for consequential damage or loss due to any error in carrying out the tests, nor for any erroneous statement or opinion contained in a report based on such tests. If a test report is published or reproduced by the client, it will be done in full, without any omission.

AGGREGATE AND SAND SIEVE ANALYSIS TEST RESULTS - REP AGG 10


Client: Geomechanics	Project Name: uMkhomazi: Rock Core Testing	Job No: 2013-C-317	Date: 08/03/2013
Sample Ref.: Moderately weathered - Slaked	Sample No.: 3/2189		

SIEVE ANALYSIS			
As received		After weathering	
Sieve (mm)	% Passing	Sieve (mm)	% Passing
53.0	100	53.0	100
37.5	100	37.5	100
26.5	100	26.5	100
19.0	100	19.0	89
13.2	85	13.2	72
9.5	70	9.5	58
4.75	41	4.75	34
2.00	17	2.00	12
0.425	7	0.425	4
0.075	2	0.075	3
GM	2.74	GM	2.81




Sample Ref.: Slightly Weathered	Sample No.: 3/2190		
--	---------------------------	--	--

SIEVE ANALYSIS			
Sieve (mm)	% Passing	Sieve (mm)	% Passing
53.0	100	53.0	100
37.5	100	37.5	100
26.5	100	26.5	88
19.0	100	19.0	69
13.2	90	13.2	41
9.5	79	9.5	27
4.75	46	4.75	15
2.00	21	2.00	7
0.425	7	0.425	3
0.075	2	0.075	2
GM	2.70	GM	2.88



Sample Ref.: Slightly Weathered - Slaked	Sample No.: 3/2191		
---	---------------------------	--	--

SIEVE ANALYSIS			
Sieve (mm)	% Passing	Sieve (mm)	% Passing
53.0	100	53.0	100
37.5	100	37.5	100
26.5	100	26.5	98
19.0	100	19.0	82
13.2	94	13.2	62
9.5	85	9.5	52
4.75	54	4.75	31
2.00	26	2.00	13
0.425	10	0.425	5
0.075	4	0.075	3
GM	2.60	GM	2.79



Everything possible is done to ensure that tests are representative and are performed accurately, and that reports and conclusions are quoted correctly. Geostrada or its officials can in no way be held liable for consequential damage or loss due to any error made in carrying out the tests, nor for any erroneous statement or opinion contained in a report based on such tests. If a test report is published or reproduced by the client, it will be done in full, without any omission.

Annexure C

Driller's Journals

DAILY DRILLING REPORT

No. 35766



28 Central Road, Sunnyside, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 696
www.geogroup.co.za

23/03/2013	Contract Name: UMKHOMAZI	Rig No: p205	Machine Start Hour: 01050
Weather: HOT	Client:	Rig Type: ywe	Machine End Hour: 01052
Contract No: J01763	BH-no: NM 1	Inclination: VERTICAL	Pump Type: MONO
Water Used 400L	Kilometers water Carted	Direction: 90°	Diesel Received: 30L

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^(deg) **Direction:** Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWR/B/ISIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0.00	0.85	0.85	0.85	-	NXC	-							CR650	90%	Brown	Slow	S	-	NXC	0.85	
0.85	1.57	0.72	0.45	0.27	NXC	-							CR650	90%	creamy	Slow	S	-	NXC	1.57	
1.57	2.79	1.22	0.26	0.36	NWD4	-							CR650	90%	creamy	Slow	WR	-	OLD	2.79	

WE WENT TO WORK BY 7H00 AND WE DO CLEARING THE BUSH AND THEN SET UP THE RIG WE START OUR TASK BY 11H30 AFTER WE HAVE BURRICATING AND DISKING SUMPS.

JAN MATHANGA
LUCKY MALILANGA

Borehole complete? Yes No Core boxes: 1 of _____ Corewriter Name: **LAWRENCE NEVARDI** Signature: _____

Water level: _____ m Time: _____ am Water level: _____ m Time: _____ pm Supervisor Name: **A Pooysa** Signature: _____

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 35767



28 Central Road, Sunningdale, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 25/03/2013	Contract Name: UMKHOMAZI	Rig No: p205	Machine Start Hour: 01/05/2
Weather: Cloudy	Client:	Inclination: VERTICAL	Rig Type: 7WE
Contract No: J01763	BH-no: NM1	Direction: 90°	Machine End Hour: 01/05/8
Water Used 2600 L	Kilometers water Carted	Pump Type: Mono	Diesel Received:

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^(deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
2.79	4.37	1.58	1.56	0.02	NWD4	+							CR650	90%	creamy slow	WRL	-	OLD	OLD		
4.37	5.00	0.63	0.59	0.04	NWD4	-							CR650	90%	creamy slow	WRL	-	OLD	11		
5.00	5.87	0.87	0.91	+0.04	NWD4	-							CR650	90%	creamy slow	WRL	-	OLD	11		
5.87	7.35	1.48	1.26	0.22	NWD4	-							CR650	90%	creamy slow	WRL	-	OLD	11		
7.35	8.00	0.65	0.63	0.02	NWD4	-							CR650	90%	creamy slow	WRL	-	OLD	11		
8.00	8.87	0.87	0.58	0.29	NWD4	1.50							CR650	90%	creamy slow	WRL	-	OLD	11		
8.87	10.28	1.41	1.20	0.21	NWD4	1.50							CR650	90%	Grey fast	WRL	-	OLD	11		
10.28	11.00	0.72	0.71	0.01	NWD4	1.50							CR650	90%	Grey fast	WRL	-	OLD	11		
11.00	11.83	0.83	0.84	+0.01	NWD4	1.50							CR650	90%	Grey fast	WRL	-	OLD	11		
11.83	13.35	1.52	1.50	0.02	NWD4	1.50							CR650	90%	Grey fast	WRL	-	OLD	11		
13.35	14.00	0.65	0.65	-	NWD4	1.50							CR650	90%	Grey fast	WRL	-	OLD	11		
3 PACKERS HAS BEEN DONE 2-5 AND 5-8 ALSO 8-11																					

Borehole complete? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Core boxes: 2 of	Corewriter Name: LAURENCE NEVARI	Signature: <i>[Signature]</i>
Water level: m Time: am	Water level: m Time: pm	Supervisor Name: A P...	Signature: <i>[Signature]</i>

Instruction by Geologist	
Equipment replaced:	
Equipment lost:	

DAILY DRILLING REPORT

No. 35768



28 Central Road, Surrey A/H, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 26/03/2019	Contract Name: UM K HOMAZI	Rig No: P205	Machine Start Hour: 01058
Weather: Rain	Client:	Inclination: VERTICAL	Rig Type: YWE
Contract No: 501763	BH-no: NM1	Direction:	Machine End Hour: 01059
Water Used	Kilometers water Carted	Pump Type: manu	Diesel Received: 26L

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^{deg(°)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWRB /SIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
WE WENT TO WORK AND WE HAVE JUST DO PACKER IMMEDIATELY when we start put rocks down to hole rain came heavily and we off by 10H02 TO THE CAMP WAITING TO go for holiday																					

Borehole complete? Yes No Core boxes: 2 of _____ Corewriter Name: LAWRENCE NEVARI Signature: *[Signature]*

Water level: _____ m Time: _____ am Water level: _____ m Time: _____ pm Supervisor Name: A Preegan Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 35769



28 Central Road, Sunnyside AH, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 03/04/2015		Contract Name: UMKHOMAZI		Rig No: P205	Machine Start Hour: 01058
Weather: RAIN		Client:	Inclination: VERTICAL	Rig Type: YWE	Machine End Hour: 01058
Contract No: J01763		BH-no: NMI	Direction: 910	Pump Type: Mono	Diesel Received:
Water Used		Kilometers water Carted			

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^(deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWR/B IS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
WE DIDN'T WANT TO WORK BECAUSE OF HEAVY RAIN WE GET INSTRUCTION FROM MR ANDRIES OUR Manager																					
																		Jan Maphanga Lucky Mavilang			

Borehole complete? Yes No Core boxes: 2 of _____ Corewriter Name: LAWRENCE NEVALI Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: ABOUYSA Signature: *[Signature]*

Instruction by Geologist	
Equipment replaced:	
Equipment lost:	

DAILY DRILLING REPORT

No. 35770



28 Central Road, Surrey's A/M, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 85 143 6632
Fax: 086 6633 696
www.geogroup.co.za

Date: 04/04/2013	Contract Name: Baynes field	Rig No: P205	Machine Start Hour: 01058
Weather: COOL	Client:	Inclination: VERTICAL	Rig Type: JWE
Contract No: J01763	BH-no: NMI	Direction: 90°	Pump Type: MOME
Water Used: 2100 L	Kilometers water Carted:		Diesel Received:

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^{deg/45} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWR/BS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
14.00	14.87	0.87	0.68	0.19	NWD4	1.50								CR650	80%	Grey	fast	FR	-	OLD	OLD
14.87	17.00	2.13	2.07	0.06	TNW	1.50								CR650	80%	Grey	fast	FR	-	OLD	11
17.00	20.00	3.00	3.01	10.01	TNW	1.50								CR650	80%	Grey	fast	FR	-	OLD	11
21.00	23.00	3.00	2.98	0.02	TNW	1.50								CR650	80%	Grey	fast	FR	-	OLD	11
23.00	23.74	0.74	0.72	0.02	TNW	1.50								CR650	80%	Grey	fast	FR	-	OLD	11
WE HAVE DONE							3 PACKERS						14-17 AND 17-20 AND								
ALSO							20-23														

*Jam Maphanga
Lucky Mabitaba*

Borehole complete? Yes No Core boxes: 4 of Corewriter Name: LAWRENCE NEVARI Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: A Bonyer Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 35771

Date: 03/04/2013	Contract Name: Baynes field	Rig No: P205	Machine Start Hour: 0106k
Weather: COOL	Client:	Inclination: VERTICAL	Rig Type: JWE
Contract No: J01763	BH-no: NM1	Direction: 90°	Machine End Hour: 0106.7
Water Used: 200L	Kilometers water Carted:	Pump Type: Mono	Diesel Received: —



28 Central Road, Sunnyside, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 696
 www.geogroup.co.za

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^{deg(45)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWR/BS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
23.74	25.16	1.42	1.41	0.01	TNW	1.50							CMSO	80%	Grey	fast	FR	—	010	0.10	
WE Complete bore hole by 08H57 and WE ALSO pull out casing close sumps clean the site. WE USE TRACTOR TO NEW SITE FOR 1,2 KM																					

Borehole complete? Yes No Core boxes: 4 of 4 Corewriter Name: LAWRENCE NEVARI Signature: *[Signature]*

Water level: 14.20m Time: 09H00am Water level: 14.20m Time: 09H pm Supervisor Name: A ROYSE Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 38139



28 Central Road, Sunnyside, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 03 April 2013	Contract Name: <i>Beynes field</i>		Rig No: <i>P0167</i>	Machine Start Hour: <i>11/7</i>
Weather: <i>rainning</i>	Client:	Inclination: <i>Vertical</i>	Rig Type: <i>gwc</i>	Machine End Hour: <i>11/7</i>
Contract No: <i>701673</i>	BH-no:	Direction: <i>90°</i>	Pump Type: <i>None</i>	Diesel Received:
Water Used	Kilometers water Carted			

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLHC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^{deg(45)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters	
							0.075	0.150	0.225	0.300	0.375	0.450										

Borehole complete? Yes No Core boxes: *01* of Corewriter Name: *Terrance Galwane* Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: *A ROYSE* Signature: *[Signature]*

Instruction by Geologist _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 38140



28 Central Road, Sunnyside A/H, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 66 143 6632
 Fax: 086 6633 696
 www.geogroup.co.za

Date: <i>04 April 2013</i>	Contract Name: <i>Beynes Field</i>	Rig No: <i>90167</i>	Machine Start Hour: <i>---</i>
Weather: <i>Warmer</i>	Client: <i>Beynes Field</i>	Inclination: <i>Vertical</i>	Machine End Hour: <i>---</i>
Contract No: <i>Jo1763</i>	BH-no: <i>M112</i>	Direction: <i>90°</i>	Pump Type: <i>None</i>
Water Used <i>1000L</i>	Kilometers water Carted		

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^{deg/deg} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /SIG	Rock type	BIT NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
<i>4.50</i>	<i>5.00</i>	<i>0.50</i>	<i>0.35</i>	<i>-0.15</i>	<i>MWD4</i>	<i>0.00</i>								<i>CR650</i>	<i>40%</i>	<i>Brown flow</i>					
<i>5.00</i>	<i>6.50</i>	<i>1.50</i>	<i>0.78</i>	<i>-0.72</i>	<i>MWD4</i>	<i>4.50</i>								<i>CR650</i>	<i>38%</i>	<i>Black flow</i>					
<i>6.50</i>	<i>8.00</i>	<i>1.50</i>	<i>1.30</i>	<i>-0.20</i>	<i>MWD4</i>	<i>4.50</i>								<i>CR650</i>	<i>30%</i>	<i>Black flow</i>					
<i>from morning waiting for water until at 11H42</i>																					
<i>We've done few perfect test today.</i>																					

Borehole complete? Yes No Core boxes: *01* of Corewriter Name: *Terrance Salemane* Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: *A Proyer* Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. **38141**



28 Central Road, Sunnyside AH, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: <i>05 April 2013</i>	Contract Name: <i>Boynes Field</i>	Rig No: <i>P0167</i>	Machine Start Hour: <i>N/A</i>
Weather: <i>Wormer</i>	Client:	Inclination: <i>Vertical</i>	Machine End Hour: <i>N/A</i>
Contract No: <i>701763</i>	BH-no: <i>MMD</i>	Direction: <i>90°</i>	Pump Type: <i>None</i>
Water Used <i>10000</i>	Kilometers water Carted		

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^{deg(45)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
<i>8.00</i>	<i>9.50</i>	<i>1.50</i>	<i>1.20</i>	<i>-0.30</i>	<i>NWD4</i>	<i>4.50</i>							<i>CR650</i>	<i>30%</i>	<i>Black</i>	<i>slow</i>					
<i>9.50</i>	<i>11.00</i>	<i>1.50</i>	<i>1.35</i>	<i>-0.15</i>	<i>MWD4</i>	<i>4.50</i>							<i>CR650</i>	<i>15%</i>	<i>Black</i>	<i>slow</i>					
<i>11.00</i>	<i>14.00</i>	<i>3.00</i>	<i>2.70</i>	<i>-0.30</i>	<i>THW</i>	<i>4.50</i>							<i>CR650</i>	<i>30%</i>	<i>Black</i>	<i>slow</i>					
<i>14.00</i>																					

Two permeability test done today.

Borehole complete? Yes No Core boxes: *02* of Corewriter Name: *Terrence Salemane* Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: *A Booyse* Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 38142



28 Central Road, Sunnyside, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 696
www.geogroup.co.za

Date: 06/April/2013	Contract Name: <i>Reynoo field</i>	Rig No: <i>P0167</i>	Machine Start Hour: <i>11A</i>
Weather: <i>Warmer</i>	Client:	Rig Type: <i>gwe</i>	Machine End Hour: <i>11A</i>
Contract No: <i>J01763</i>	BH-no: <i>1112</i>	Pump Type: <i>Mono</i>	Diesel Received:
Water Used: <i>1000L</i>	Kilometers water Carted:		

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^{092/451} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
<i>14.00</i>	<i>17.00</i>	<i>3.00</i>	<i>3.00</i>	<i>—</i>	<i>THW</i>	<i>4.50</i>							<i>Cruso oil</i>	<i>0%</i>	<i>Bad</i>	<i>Flow</i>					
<i>17.00</i>					<i>TNW</i>	<i>4.50</i>															
<i>We stopped by Mono pump which was pumping on bad conditions from 10H33 to 11H36 logging 14H00.</i>																					

Borehole complete? Yes No Core boxes: *02* of Corewriter Name: *Leorance Galamane* Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: *[Signature]* Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 38143



GEOGROUP
 28 Central Road, Sunnyside A/H, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 08 April 2013	Contract Name: <i>Feynes Field</i>	Rig No: P0167	Machine Start Hour: —
Weather: <i>Warmer</i>	Client:	Inclination: <i>Vertical</i>	Machine End Hour: —
Contract No: <i>J01763</i>	BH-no: <i>MM2</i>	Direction: <i>90°</i>	Pump Type: <i>Moro</i>
Water Used: <i>1000L</i>	Kilometers water Carted:		Diesel Received: <i>20L</i>

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^(deg) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
<i>17.00</i>	<i>20.00</i>	<i>3.00</i>	<i>2.95</i>	<i>0.05</i>	<i>THW</i>	<i>4.50</i>							<i>CR650</i>	<i>0%</i>	<i>Black</i>	<i>Flow</i>	<i>FB</i>		<i>075</i>	<i>075</i>	
<i>Due packages lost</i>																					

Borehole complete? Yes No Core boxes: *02* of *03* Corewriter Name: *Tessanne Salamane* Signature: *Tessanne Salamane*

Water level: *06.50* m Time: *04:50* am Water level: m Time: pm Supervisor Name: *A. Kuyubon* Signature: *A. Kuyubon*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 39761



28 Central Road, Sunnyside A/H, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 66 143 6632
Fax: 066 6633 896
www.geogroup.co.za

Date: 25-03-13	Contract Name: Baynes field	Rig No: 168	Machine Start Hour: 227.8
Weather: Changing	Client:	Inclination: Vertical	Machine End Hour:
Contract No: 501763	BH-no: NM 3	Direction: 90°	Pump Type:
Water Used: 1000L	Kilometers water Carted:		Diesel Received: 25L

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0.00	0.90	0.90	0.45	-0.45	HXC	0.00							CR2650	75%	Brown	Slow					
0.90	1.50	0.60	Core was		"	"							"	"	Grey	"					
1.50	3.00	1.50	0.95	-0.55	NWD4	0.00							"	"	"	"					
3.00	4.50	1.50	1.35	-0.15	"	"							"	"	Black	fast					
4.50	5.00	0.50	0.50	-	"	"							"	"	"	"				Pentam 15HIS - 16H05	
Setup, we waiting for truck as from 08:00 until 12:00 then we move 100m to next Hole. We start to Drill at 13:20																					

Borehole complete? Yes No Core boxes: 1 of _____ Corewriter Name: Ndifelegi Signature: _____

Water level: _____ m Time: _____ am Water level: _____ m Time: _____ pm Supervisor Name: A. Kooze Signature: _____

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 39762



GEORGROUP
 28 Central Road, Sunnyside A/H, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 26-03-13	Contract Name: Bayness Field	Rig No: 168	Machine Start Hour: 231
Weather: Raining	Client:	Inclination: Vertical	Rig Type: ywc
Contract No: J01763	BH-no: Nm3	Direction: 90°	Pump Type:
Water Used	Kilometers water Carted		Diesel Received:

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^{deg(45)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWRB /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
5.00	6.50	1.50	1.50	-	MWD4	3.50								CR650	75%	Black	fast				
6.50	8.00	1.50	1.45	0.05	"	"								"	"	"	"				

Borehole complete? Yes No Core boxes: 1 of _____ Corewriter Name: Ndifemi Signature: _____

Water level: m Time: am Water level: m Time: pm Supervisor Name: A. Brooyen Signature: _____

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 39763



28 Central Road, Sunnyside, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 03-04-13	Contract Name: Bayness field	Rig No: 168	Machine Start Hour:
Weather: Raining	Client:	Inclination: Vertical	Machine End Hour:
Contract No: J01763	BH-no: HM3	Direction: 90°	Pump Type:
Water Used	Kilometers water Carted		Diesel Received:

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS																							
Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN																							
Inclination: Horizontal, Vertical, inclined (deg) Direction: Compass reading (or from Geologist)																							
Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /SIG	Rock type	Bit NO.	Accum bit meters		
							0.075	0.150	0.225	0.300	0.375	0.450											
			We didn't manage to go to site																				
Borehole complete? Yes <input type="checkbox"/> No <input type="checkbox"/>			Core boxes: of		Corewriter Name: Ndifeda			Signature: [Signature]															
Water level: m Time: am			Water level: m Time: pm		Supervisor Name: A. Poyson			Signature: [Signature]															
Instruction by Geologist																							
Equipment replaced:																							
Equipment lost:																							

DAILY DRILLING REPORT

No. 39764



GEORGROUP
 28 Central Road, Sunnyside, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 04-04-13	Contract Name: Bayens field	Rig No: 168	Machine Start Hour: 232.9
Weather: Hot	Client:	Inclination: Vertical	Machine End Hour:
Contract No: 501763	BH-no: Nm 3	Direction: 90°	Pump Type:
Water Used	Kilometers water Carted		Diesel Received: 20L

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg. (NWD4) TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal/ (Vertical) / Inclined Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWRB /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
8.00	9.50	1.50	1.55	0.05	Nwd4	4.50							calso	75%	Black	fast	Perice	13H00 -	13H55		
9.50	11.00	1.50	1.50	-	"	"							"	"	"	"	Perice	14.11 55 -	15H50		
WE waiting for water & the key as from 08H00 until 12H30 & WE start to Drill at 14H05																					
																		Leonard mphaphu			
																		Lizwi Siwela			

Borehole complete? Yes No Core boxes: 2 of Corewriter Name: Ndifela ni Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: A. Prooyen Signature: *[Signature]*

Instruction by Geologist	
Equipment replaced:	
Equipment lost:	

DAILY DRILLING REPORT

No. 39765



GEORUP
 28 Central Road, Sunnyside A/H, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 696
 www.geogroup.co.za

Date: 05-04-13	Contract Name: Baynias field	Rig No: 168	Machine Start Hour: 235.4
Weather: Hot	Client:	Inclination: Vertical	Machine End Hour:
Contract No: J01763	BH-no: HM3	Direction: 90°	Pump Type:
Water Used	Kilometers water Carted		Diesel Received:

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: **NWD4**/TNW/ NQ/ HLMC etc Drilling Response: **FAST**/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal **Vertical** Inclined ^{deg(°)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWRB /SIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
11.00	12.50	1.50	1.50	-	NWD4	4.50							CR650	75%	Black	Fast					
12.50	14.00	1.50	1.50	-	"	"							"	"	"	"	Parice	8H4S	- 09H40		
14.00	15.50	1.50	1.50	-	"	"							"	"	"	"					
15.50	17.00	1.50	1.50	-	NWD4	4.50							"	"	"	"	Perker	10H30	- 11H25		
17.00	18.50	1.50	1.50	-	"	"							"	"	Black	"					
18.50	20.00	1.50	1.50	-	"	"							CR650	75%	"	Fast	Perice	13H00	- 13H55		
END OF BH HM3 Depth 20.00 We move the rig to next position.																					

Borehole complete? **Yes** No Core boxes: **3** of **3** Corewriter Name: **H. Dipertini** Signature: *[Signature]*

Water level: m Time: **am 09:00** Water level: m Time: **pm** Supervisor Name: **A. Prayogo** Signature: *[Signature]*

Instruction by Geologist	
Equipment replaced:	
Equipment lost:	

DAILY DRILLING REPORT

No. 39757



GEOGROUP
 28 Central Road, Sunnyside A/H, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 20-03-13	Contract Name: mkhoma2i	Rig No: 168	Machine Start Hour:
Weather: Hot	Client:	Inclination: Vertical	Machine End Hour:
Contract No: 501763	BH-no: NW 4	Direction: 90°	Pump Type:
Water Used	Kilometers water Carted		Diesel Received:

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^(deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWRB /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
We waiting for the truck to load the rig as from other until 12H00, then we load & Drive 36km to site, wa offroad & Setup.																					
																		Lizwi Siwela Leonard Mphahlele			

Borehole complete? Yes No Core boxes: of Corewriter Name: Adifeigni Signature:

Water level: m Time: am Water level: m Time: pm Supervisor Name: A ROYSEK Signature:

Instruction by Geologist	
Equipment replaced:	
Equipment lost:	

DAILY DRILLING REPORT

No. 39758



GEOGROUP
 28 Central Road, Sunnyside AA, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 696
 www.geogroup.co.za

Date: 21-03-13	Contract Name: Michomazi	Rig No: 168	Machine Start Hour: 21H
Weather: Hot	Client:	Inclination: Vertical	Machine End Hour:
Contract No: J01763	BH-no: M34	Direction: 90°	Pump Type:
Water Used 1000L	Kilometers water Carted		Diesel Received: 20L

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4 TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^(deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B IS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0,00	0,90	0,90	0,45	-0,45	Mxc	0,00								CR650	90%	Brown	Slow				
0,90	1,50	0,60	0,50	-0,10	"	"							"	"	"	"					
1,50	2,37	0,87	0,55	-0,32	NWD4	0,00							"	"	"	"					
2,37	3,50	1,13	1,00	-0,13	"	"							"	"	"	"					
3,50	5,00	1,50	1,35	-0,15	"	"							CR650	90°	Brown	Slow	Parker 14H45 - 15H40				
5,00	6,50	1,50	1,50	-	NWD4	1,50							"	"	Grey	fast					
we waiting for water as from 08H00 until 12H00, then we start to drill at 12H30																					

Borehole complete? Yes No Core boxes: 1 of Corewriter Name: Ndiferani Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: A. Booyana Signature: *[Signature]*

Instruction by Geologist: _____
 Equipment replaced: _____
 Equipment lost: _____

DAILY DRILLING REPORT

No. 39759



28 Central Road, Sunnyside AAH, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 22-03-13	Contract Name: MKHOMAZI	Rig No: 168	Machine Start Hour: 2145
Weather: HOT	Client:	Inclination: Vertical	Machine End Hour:
Contract No: J01763	BH-no: HBH	Direction: 90°	Pump Type:
Water Used	Kilometers water Carted		Diesel Received:

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWRB IS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
6.50	8.00	1.50	1.50	-	NWD4	1.50							CR6SD	75%	Black	fast	Parker	09H10	10H05		
8.00	9.50	1.50	1.45	-0.05	"	"							"	"	"	"	"	"	"		
9.50	11.00	1.50	1.50	*	"	"							"	"	"	"	Parker	12H40	13H35		
11.00	12.50	1.50	1.50	'	"	"							"	"	"	"	"	"	"		
12.50	14.00	1.50	1.45	-0.05	NWD4	1.50							"	"	"	"	Parker	14H30	15H25		
14.00	15.50	1.50	1.45	-0.05	"	"							"	"	"	"	"	"	"		

Borehole complete? Yes No Core boxes: 3 of _____ Corewriter Name: Ndiforani Signature: [Signature]

Water level: m Time: am Water level: m Time: pm Supervisor Name: A. Booysse Signature: [Signature]

Instruction by Geologist _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 39760



28 Central Road, Sunnyside, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 23-03-13	Contract Name: Mkhomazi	Rig No: 168	Machine Start Hour: 224.9
Weather: HOT	Client:	Inclination: Vertical	Machine End Hour:
Contract No: J01763	BH-no: NWH	Direction: 90°	Pump Type:
Water Used 10082	Kilometers water Carted		Diesel Received: 28L

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^{deg(45)} **Direction:** Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWR/B IS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
15.50	17.00	1.50	1.50	-	NWD4	1.50								CR650	NO water return	Black	Fast	Parker 10H60	-	10H55	
17.00	18.50	1.50	1.47	0.03	"	"							"	"	"	"	"	"	"	"	
18.50	20.00	1.50	1.50		"	"							"	"	"	"	"	Parker 12H60	-		
			END OF DEPTH		BIT NWH		20.00														
																Lizwi	Siweia				
																Leonard	mphephu				

Borehole complete? Yes No Core boxes: 3 of 3 Corewriter Name: M. Diferani Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: A. Prayisa Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. **42510**



28 Central Road, Sunnella AH, Lanseria
PO Box 66063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 21 MARCH 2013	Contract Name: BAYMES FIELD	Rig No: P207	Machine Start Hour: 011934
Weather: HOT	Client:	Inclination: 90°	Machine End Hour:
Contract No: Jo1763	BH-no: MM 5	Direction: VERTICAL	Pump Type: MONO
Water Used 200L	Kilometers water Carted		Diesel Received: 2.5L

Nature of Core Classification: FR-FRESH	WR-WEATHERED	B-BOULDERS	S-SOILS	G-GRAVELS
Legend	Run length: Depth to - Depth from = Run length	Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc		Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN
Inclination:	Horizontal, Vertical, Inclined ^{60/45}		Direction: Compass reading (or from Geologist)	

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0.00	0.90	0.90	0.90	—	MxL	—							CB650	100%	RED	FAST	S	Soil	OLD	OLD	
0.90	1.80	0.90	0.90	—	MxL	—							CB650	100%	RED	FAST	S	Soil	OLD	OLD	
1.80	3.22	1.42	1.00	-0.42	MWDY	—							CB650	100%	RED	FAST	S	Soil	OLD	OLD	
3.22	4.37	1.15	1.00	-0.15	MWDY	—							CB650	100%	RED	FAST	S	Soil	OLD	OLD	
4.37	5.00	0.63	0.90	+0.27	MWDY	—							CB650	100%	RED	FAST	S	Soil	OLD	OLD	
WE DID PACKER AT 2-5 M FROM 15H30 TO 16H30																					
WE MOVE THE RODS FROM HOLE BIT 5 TO HMS WITH BALKIES FROM 8H00 TO 16H30 AFTER THE WE SETUP FROM 10H00 TO 13H00 BECAUSE WE MOVE STAFF BY HAND FOR TOM, WE WAIT FOR WATER 13H00 TO 13H30, WE START TO DRILL UNTIL 14H40 WE WAIT FOR ROCKS																					
THAPELO, LOWKEMLE WILSON																					

Borehole complete? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Core boxes: 1 of 	Corewriter Name: THAPELO MOELA	Signature:
Water level: m Time: am	Water level: m Time: pm	Supervisor Name: AMDIEN BOOYSEN	Signature:

Instruction by Geologist	
Equipment replaced:	
Equipment lost:	

DAILY DRILLING REPORT

No. 42511



GEORGROUP
 28 Central Road, Sunnella A/H, Lanseria
 PO Box 66063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 22-03-2013	Contract Name: BAYMES FIELD	Rig No: P207	Machine Start Hour: 011934
Weather: Hot	Client:	Inclination: 90°	Machine End Hour:
Contract No: 501763	BH-no: MMS	Direction: VERTICAL	Pump Type: MARO
Water Used 750L	Kilometers water Carted		

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^(°) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
5.00	5.67	0.67	0.67	—	MWD4	3.00								CLBSO	GREY	SLOW	WR	Rock	OLD	OLD	
5.67	7.27	1.60	1.60	—	MWD4	3.00								CLBSO	GREY	SLOW	WR	Rock	OLD	OLD	
7.27	8.00	0.73	0.50	-0.23	MWD4	3.00								CLBSO	GREY	SLOW	WR	Rock	OLD	OLD	
4WE DSD PATER AT 5-8 M OM 11H00 TO 12H00																					
8.00	9.07	1.07	1.07	—	MWD4	3.00								CLBSO	GREY	SLOW	WR	Rock	OLD	OLD	
9.07	10.37	1.30	1.17	-0.13	MWD4	3.00								CLBSO	BLACK	SLOW	WR	Rock	OLD	OLD	
10.37	11.00	0.63	0.56	-0.07	MWD4	3.00								CLBSO	BLACK	SLOW	WR	Rock	OLD	OLD	
WE STOP AT 14H00 BECAUSE MACHINE WAS HOT TO 16H00																					
THAPELO WILSON LOWFEMLE																					

Borehole complete? Yes No Core boxes: **2** of Corewriter Name: **THAPELO MUELA** Signature: *[Signature]*

Water level: m Time: am pm Water level: m Time: pm Supervisor Name: **ANDRÉS ROYSEM** Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 42512



28 Central Road, Sunnyside A/H, Lanseria
PO Box 66063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 696
www.geogroup.co.za

Date: 23-03-2013	Contract Name: BAYNES FIELD	Rig No: P207	Machine Start Hour: 011934
Weather: HOT	Client:	Inclination: 90°	Rig Type: YWE
Contract No: J01763	BH-no: MMS	Direction: VERTICAL	Pump Type: M2000
Water Used: 250L	Kilometers water Carted:		Diesel Received: 28L

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^(60°±5) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
11.00	11.45	0.45	0.45	-	MWD4	9.00								90%	BLACK	SLOW	WR	ROCK	OLD	OLD	
WE DRILL FOR CASINGS FROM 3.00 TO 9.00 AFTER THERE WE WASH THE HOLE																					
THAPelo WILSON LOWRENCE																					

Borehole complete? Yes No Core boxes: 2 of _____ Corewriter Name: THAPelo MBELE Signature:

Water level: _____ m Time: _____ am Water level: _____ m Time: _____ pm Supervisor Name: ANDRIES BOUYSEN Signature:

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 42513



28 Central Road, Sunnyside A/H, Lanseria
PO Box 66063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 25-03-2013	Contract Name: BAYMES FIELD	Rig No: P207	Machine Start Hour: 011934
Weather: Cloudy	Client:	Inclination: 90°	Rig Type: YWE 1390
Contract No: J01763	BH-no: NMS	Direction: VERTICAL	Pump Type: Mono
Water Used: 750L	Kilometers water Carted		
		Machine End Hour:	Diesel Received: 25L

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, inclined (°) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B IS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
11.45	11.53	0.08	0.08	-	MWD4	9.00								CR650	BLACK	SLOW	WR	Rock	CR0	0.00	
11.53	11.77	0.24	0.21	-0.03	TMW	9.00								CR650	BLACK	SLOW	WR	Rock	AC3060	35.69	
11.77	14.00	2.23	1.88	-0.35	TMW	9.00								CR650	BLACK	SLOW	WR	Rock	AC3060	37.92	
WE	DIA	PACKER	AT	11 - 14 M																	
14.00	14.77	0.77	1.12	-0.35	TMW	9.00								CR650	BLACK	SLOW	WR	Rock	AC3060	38.69	
14.77	17.00	2.23	2.00	-0.23	TMW	9.00								CR650	BLACK	SLOW	WR	Rock	AC3060	40.92	
OH	23-03-2013	WE	DIA	PACKER	AT	8-11 M															
WE	WAIT FOR WATER	FROM 12H30 TO 14H30																			

Borehole complete? Yes No Core boxes: 3 of Corewriter Name: THAPELA NDELA Signature:

Water level: m Time: am Water level: m Time: pm Supervisor Name: ANDRIES BOUYSEN Signature:

Instruction by Geologist: _____

Equipment replaced: TMW CORE - SPRING x1

Equipment lost: _____

DAILY DRILLING REPORT

No. **42514**



28 Central Road, Sunnyside A/H, Lanseria
PO Box 66063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 26-03-2013	Contract Name: BAYMEB FIELD	Rig No: P207	Machine Start Hour: 01934
Weather: Rain	Client:	Inclination: 90°	Machine End Hour:
Contract No: J01763	BH-no: MMS	Direction: VER	Pump Type: MANO
Water Used	Kilometers water Carted		Diesel Received: 30L

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^{deg(45)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters	
							0.075	0.150	0.225	0.300	0.375	0.450										

RAIN ON RAIN GAUGE 10mm

**WE WAIT FOR WATER FROM 8:10 TO 10:00
11:00 TO 17:00 M WATER RETURN IS 50%**

Thapelo Wilson LOISELLE

Borehole complete? Yes No Core boxes: **3** of Corewriter Name: **THAPELO INDELA** Signature: **[Signature]**

Water level: m Time: am Water level: m Time: pm Supervisor Name: **AMALIES BOUYSEM** Signature: **[Signature]**

Instruction by Geologist:
Equipment replaced:
Equipment lost:

DAILY DRILLING REPORT

No. 42515



28 Central Road, Sunnyside A/H, Lanseria
PO Box 65063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 03-04-2013	Contract Name: BAYMES FIELD	Rig No: P207	Machine Start Hour:
Weather: RAINY	Client:	Inclination: 90°	Machine End Hour:
Contract No: 501763	BH-no: HMS	Direction: VERTICAL	Pump Type: manual Diesel Received: —
Water Used	Kilometers water Carted		

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (°) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /SIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
WE DID NOT GO TO WORK BECAUSE OF RAIN																					
Thapelo Molea Wilson Lawrence																					

Borehole complete? Yes No Core boxes: 3 of Corewriter Name: Thapelo Molea Signature: [Signature]

Water level: — m Time: am Water level: — m Time: pm Supervisor Name: ANDRIES BOUYSEM Signature: [Signature]

Instruction by Geologist: _____
Equipment replaced: _____
Equipment lost: _____

DAILY DRILLING REPORT

No. 42516



28 Central Road, Sunningdale, Lanseria
PO Box 66063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 04-04-2013	Contract Name: BAYMESFIELD	Rig No: P207	Machine Start Hour: 071934
Weather: CDD	Client:	Inclination: 90°	Machine End Hour:
Contract No: J01763	BH-no: HMS	Direction: VERTICAL	Pump Type: Mono
Water Used 750 L	Kilometers water Carted		Diesel Received: —

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ⁶⁰⁻⁹⁰ Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B/IS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
17.00	17.77	0.77	0.80	+0.03	TMW	9.00							CL650	NO WATER RETURN	BLACK	SLOW	FR	Rock	AC3060	41.69	
17.77	19.17	1.40	1.40	—	TMW	9.00							CL650	NO WATER RETURN	BLACK	SLOW	WR	Rock	AC3060	43.09	
19.17	20.00	0.83	0.83	—	TMW	9.00							CL650	NO WATER RETURN	BLACK	SLOW	WR	Rock	AC3060	43.92	
WE DID NOT GET WATER AT 17-20M																					
WE GET WATER AT 10H00																					
RAIN 10M RAIN CHANGE 38MM																					
WE DID NOT GET WATER AT 14-17M																					

Thapelo
Wilson
Lawrence

Borehole complete? Yes No Core boxes: 3 of Corewriter Name: Thapelo Mordy Signature:

Water level: m Time: am Water level: m Time: pm Supervisor Name: ANNIES BOOYSEN Signature:

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 42517



28 Central Road, Sunnyside A/H, Lanseria
PO Box 66063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 05-04-2013	Contract Name: BAYMES FIELD	Rig No: P207	Machine Start Hour: 011934
Weather: COOL	Client:	Inclination: 90°	Machine End Hour: 011734
Contract No: 50 1763	BH-no: MM 5	Direction: VERTICAL	Diesel Received: 16L
Water Used 500L	Kilometers water Carted		

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^{deg(45)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /SIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
20.00	20.70	0.70	0.70	-	TMW	9.00								WATER	0%	BLACK	SLOW	WR	Rock	AC3060	44.62
20.70	21.62	0.92	0.92	-	TMW	9.00								WATER	0%	BLACK	SLOW	WR	Rock	AC3060	45.54
21.62	23.00	1.38	1.38	-	TMW	9.00								WATER	0%	BLACK	SLOW	WR	Rock	AC3060	46.92
23.00	23.77	0.77	0.55	-0.22	TMW	9.00								WATER	0%	BLACK	SLOW	WR	Rock	AC3060	47.69
23.77	25.27	1.50	1.72	+0.22	TMW	9.00								WATER	0%	BLACK	SLOW	WR	Rock	AC3060	49.19
EOPH																					
WE FINISH AT 13H30, WE PULL CASINGS OUT, CLOSE THE SUMPS AND MOVE THE STAFF BY HANDS TO THE ROAD FOR 12M UNTIL 15H00, WE WAIT FOR TRUCK UNTIL 17H00																					

Thapelo
WILSON
LOWENGE

Borehole complete? Yes No Core boxes: 4 of 4 Corewriter Name: Thapelo Moeta Signature: *[Signature]*

Water level: m Time: am Water level: 9.85 m Time: 13H30 pm Supervisor Name: ANDRIE BOOYSEN Signature: *[Signature]*

Instruction by Geologist: _____
 Equipment replaced: _____
 Equipment lost: _____

DAILY DRILLING REPORT

No. 35763



23 Central Road, Suurte AH, Lanseria
PO Box 69963, Bryanston, 2021
Phone: +27 88 143 6632
Fax: 088 6633 896
www.geogroup.co.za

Date: 20/03/2018	Contract Name: UMPHOMAZI	Rig No: P205	Machine Start Hour: 01032
Weather: Cloudy	Client:	Inclination: VERTICAL	Machine End Hour: 01036
Contract No: J01763	BH-no: NM 6	Direction: 90°	Diesel Received: 30L
Water Used	Kilometers water Carted		

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^(deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0.00	0.85	0.85	0.79	0.06	NXC	-							CR650	90%	Brown	slow	S	-	NXC	0.85	
0.85	1.65	0.80	0.76	0.04	NXC	-							CR650	90%	creamy	slow	WR	-	NXC	1.65	
1.65	2.87	1.22	1.04	0.18	NWD4	-							CR650	90%	creamy	slow	WR	-	OLD	OLD	
2.87	4.34	1.47	1.15	0.32	NWD4	-							CR650	90%	creamy	slow	WR	-	OLD	11	
4.34	5.00	0.66	0.64	0.02	NWD4	-							CR650	90%	creamy	slow	WR	-	OLD	11	
5.00	5.87	0.87	0.75	0.12	NWD4	-							CR650	90%	creamy	slow	WR	-	OLD	11	
5.87	7.37	1.50	1.39	0.11	NWD4	1.50							CR650	90%	creamy	slow	WR	-	OLD	11	
7.37	8.00	0.63	0.61	0.02	NWD4	1.50															

WE WENT TO NEW SITE by 7H00 and it take 84.3km
FROM OLD SITE TO NEW SITE WE START OUR TASK by 11H40
WE ALSO DONE 2 PACKER (1) 2-5 from 13H10 TO 14H00 AND Stage
(2) by 15H00 TO 15H50.
Jan Mafanga
Lucky Mabasa

Borehole complete? Yes No Core boxes: 2 of _____ Corewriter Name: LAWRENCE NEVANI Signature: _____
Water level: m Time: am Water level: m Time: pm Supervisor Name: A Poyser Signature: _____

Instruction by Geologist: _____
Equipment replaced: _____
Equipment lost: _____

DAILY DRILLING REPORT

No. 35764

Date: 21/03/2013	Contract Name: UMLKHOMATI	Rig No: P205	Machine Start Hour: 01036
Weather: Cool	Client:	Inclination: VERTICAL	Machine End Hour: 01044
Contract No: J01763	BH-no: NMB	Direction: 90°	Pump Type: Mono Diesel Received: 30L
Water Used 1800	Kilometers water Carted		



28 Central Road, Sunnyside, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 88 143 6632
Fax: 088 6633 896
www.geogroup.co.za

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
8.00	8.87	0.87	0.46	0.41	NWD4	1.50							CR650	90%	creamy slow	WTR	-	OLD	0.87		
8.87	10.37	1.50	1.43	0.07	NWD4	1.50							CR650	90%	creamy slow	S	-	OLD	1.1		
10.37	11.00	0.63	0.64	0.01	NWD4	1.50							CR650	90%	creamy slow	S	-	OLD	1.1		
11.00	11.27	0.27	0.27	-	NWD4	1.50							CR650	90%	creamy slow	S	-	OLD	1.1		
11.27	12.77	1.50	1.36	0.14	NWD4	1.50							CR650	90%	creamy slow	S	-	OLD	1.1		
12.77	13.01	0.24	0.23	0.01	NWD4	1.50							CR650	90%	creamy slow	S	-	OLD	1.1		
13.01	14.00	0.99	0.65	0.34	NWD4	1.50							CR650	90%	creamy slow	S	-	OLD	1.1		
14.00	14.98	0.98	0.98	-	NWD4	1.50							CR650	90%	creamy slow	S	-	OLD	1.1		
14.98	15.50	0.52	0.38	0.14	NWD4	1.50							CR650	90%	creamy slow	S	-	OLD	1.1		
15.50	17.00	1.50	0.90	0.60	NWD4	1.50							CR650	90%	creamy slow	S	-	OLD	1.1		

WE HAVE DONE 3 PACKERS 8-11 by 8H00 TO 8H50 and 11-14 by 12H30 TO 13H20 and 14-17 by 14H00 TO 14H50

Jan Maphanga
Lucky Mabinondo

Borehole complete? Yes No Core boxes: 3 of _____ Corewriter Name: LAWRENCE NEIRAI Signature: _____

Water level: _____ m Time: _____ am Water level: _____ m Time: _____ pm Supervisor Name: A. Boeyse Signature: _____

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 35765



28 Central Road, Sunningdale, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 22/03/2013	Contract Name: UMPHOMAZI	Rig No: P205	Machine Start Hour: 01044
Weather: HOT	Client:	Rig Type: JWE	Machine End Hour: 01050
Contract No: 501763	BH-no: NMB	Inclination: VERTICAL	Pump Type: Mono
Water Used: 1700L	Kilometers water Carted:	Direction: 90°	Diesel Received:

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
17.00	17.84	0.84	0.42	0.42	NWD4	1.50							CR650	90%	Creamy	slow	WR	-	OLD	OLD	
17.84	19.34	1.50	1.53	+0.03	NWD4	1.50							CR650	80%	Grey	slow	WR	-	OLD	11	
19.34	20.00	0.66	0.62	0.04	NWD4	1.50							CR650	80%	Grey	fast	FR	-	OLD	11	
20.00	20.87	0.87	0.93	+0.06	NWD4	1.50							CR650	80%	Grey	fast	FR	-	OLD	11	
20.87	22.37	1.50	1.07	0.43	NWD4	1.50							CR650	80%	Grey	fast	FR	-	OLD	11	
22.37	23.00	0.63	0.69	+0.06	NWD4	1.50							CR650	80%	Grey	fast	FR	-	OLD	11	
23.00	23.87	0.87	0.74	0.13	NWD4	1.50							CR650	80%	Grey	fast	FR	-	OLD	11	
23.87	25.06	1.19	1.19	-	NWD4	1.50							CR650	80%	Grey	fast	FR	-	OLD	11	

WE HAVE DONE 2 PACKERS 17-20 by OTTOS TO OTTOS AND OTHER ONE WHICH IS THE LAST ONE 20-23 by OTTOS TO OTTOS, WE COMPLETE BORE HOLE AND WE CLEAN SITE, WE MOVE TO NEW HOLE 900 METERS FROM THE OLD SITE.

Jan Maphang
Lucy Maphang

Borehole complete? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	Core boxes: 4 of 4	Corewriter Name: LAWRENCE NEVARI	Signature: <i>[Signature]</i>
Water level: m Time: am	Water level: 13.20m Time: 13H20pm	Supervisor Name: A. P. ...	Signature: <i>[Signature]</i>

Instruction by Geologist	
Equipment replaced:	
Equipment lost:	

DAILY DRILLING REPORT

No. 38132



28 Central Road, Sunnyside AH, Lanseria
 PO Box 69063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 19/03/13	Contract Name: Baynes Field	Rig No: P0167	Machine Start Hour:
Weather: Cloudy	Client:	Inclination:	Machine End Hour:
Contract No: 1763	BH-no: MM7	Direction:	Pump Type: Mono
Water Used /	Kilometers water Carted		Diesel Received: 22L

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^{deg(45)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWRB /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									

Land.
 from 07:00 loading the rig and the equipment to the new site and wait for the transport until lat 11:00 and set up the rig until lat 14:00

Borehole complete?	Yes	No	<input checked="" type="checkbox"/>	Core boxes: — of —	Corewriter Name: Terrance Salomone	Signature:			
Water level:	m	Time:	am	Water level:	m	Time:	pm	Supervisor Name: A Pooysa	Signature:
Instruction by Geologist									
Equipment replaced:									
Equipment lost:									

DAILY DRILLING REPORT

No. 38133



28 Central Road, Sunnyside A/H, Lanseria
PO Box 69063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: <i>20 March 2013</i>	Contract Name: <i>Beynes field</i>	Rig No: <i>PO17</i>	Machine Start Hour:
Weather: <i>Cloudy</i>	Client:	Inclination: <i>Vertical</i>	Machine End Hour:
Contract No: <i>201763</i>	BH-no: <i>MM7</i>	Direction: <i>90°</i>	Pump Type: <i>New</i>
Water Used <i>1000L</i>	Kilometers water Carted		Diesel Received:

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^(deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /SIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0.00	1.50	1.50	1.50	-0.00	N2C	0.00							CR650	99%	Brown	slow					
1.50	2.80	1.30	1.40	+0.10	MWD4	0.00							CR650	98%	Brown	slow					
2.80	4.30	1.50	1.40	-0.10	MWD4	0.00							CR650	90%	Brown to life	slow					
4.30	5.00	0.70	0.60	-0.10	MWD4	0.00							CR650	90%	Brown to life	slow					
5.00	6.00	1.00	1.02	+0.02	MWD4	0.00							CR650		White to life	slow					

We start drilling at 10:45.
We've done one perfor today.

Borehole complete? Yes No Core boxes: of Corewriter Name: *Terrance Lemaire* Signature: *Terrance Lemaire*

Water level: m Time: am Water level: m Time: pm Supervisor Name: *A. Rooyen* Signature: *A. Rooyen*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 38134



28 Central Road, Sunnyside A/H, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: <i>22 March 2008</i>	Contract Name: <i>Reynes Field</i>	Rig No: <i>P0167</i>	Machine Start Hour: <i>11:00</i>
Weather: <i>Hot</i>	Client:	Inclination: <i>Vertical</i>	Machine End Hour: <i>11:00</i>
Contract No: <i>J01763</i>	BH-no: <i>MM7</i>	Direction: <i>90°</i>	Pump Type: <i>Mob</i>
Water Used <i>1000L</i>	Kilometers water Carted		Diesel Received:

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^(deg) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /SIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
6.00	7.50	1.50	1.27	-0.23	MWD4	0.00							CR650	97%	cream white	slow	WR	-	AC3162	1.50	
7.50	8.00	0.50	0.51	+0.01	MWD4	0.00							CR650	99%	cream white	slow	WR	-	AC3288	0.50	
8.00	9.50	1.50	1.27	-0.23	MWD4	0.00							CR650	97%	cream white	slow	WR	-	AC3162	1.50	
9.50	11.00	1.50	0.90	-0.60	MWD4	0.00							CR650	60%	cream white	slow	WR	-	AC3288	1.50	
11.00	12.50	1.50	1.18	-0.32	MWD4	0.00							CR650	32%	cream white	slow	WR	-	AC3162	1.50	
12.50																					

We wait for water since from 08409 to 10452 and wait for start machine until 11410.

Borehole complete? Yes No Core boxes: of Corewriter Name: *Terrance Salameine* Signature: *T Salameine*

Water level: m Time: am Water level: m Time: pm Supervisor Name: *A Pooysen* Signature: *A Pooysen*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 38135



28 Central Road, Sunnyside A/H, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 22/03/13	Contract Name: <i>Reynes field</i>	Rig No: P0167	Machine Start Hour: <i>M/working</i>
Weather: <i>HOT</i>	Client:	Inclination: <i>Vertical</i>	Machine End Hour: <i>11</i>
Contract No: <i>201763</i>	BH-no: <i>M17</i>	Direction: <i>90°</i>	Pump Type: <i>Mow</i>
Water Used <i>1000L</i>	Kilometers water Carted		Diesel Received:

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /SIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
12.50	14.00	1.50	1.15	-0.25	<i>HWD4</i>	1.50							<i>CR650</i>	<i>75%</i>	<i>cream white</i>	<i>slow</i>	<i>WR</i>	<i>—</i>	<i>AC</i>	<i>31.62</i>	<i>1.50</i>
14.00	15.50	1.50	1.06	-0.44	<i>HWD4</i>	1.50							<i>CR650</i>	<i>36%</i>	<i>cream white</i>	<i>slow</i>	<i>WR</i>	<i>—</i>	<i>AC</i>	<i>32.86</i>	<i>1.50</i>
15.50	17.00	1.50	1.15	-0.86	<i>HWD4</i>	1.50							<i>CR650</i>	<i>36%</i>	<i>cream white</i>	<i>slow</i>	<i>G</i>	<i>—</i>	<i>AC</i>	<i>31.62</i>	<i>1.50</i>
17.00	18.50	1.50	0.85	-0.65	<i>HWD4</i>	1.50							<i>CR650</i>	<i>65%</i>	<i>cream white</i>	<i>slow</i>	<i>G</i>	<i>—</i>	<i>AC</i>	<i>32.86</i>	<i>1.50</i>
18.50	20.00	1.50	1.03	-0.47	<i>HWD4</i>	1.50							<i>CR650</i>	<i>47%</i>	<i>cream white</i>	<i>slow</i>	<i>G</i>	<i>—</i>	<i>AC</i>	<i>31.62</i>	<i>1.50</i>
20.00					<i>HWD4</i>	1.50							<i>CR650</i>		<i>cream white</i>	<i>slow</i>		<i>—</i>	<i>AC</i>	<i>32.86</i>	<i>1.50</i>

We've done two perforators yesterday and today we've done three perforators.

Borehole complete? Yes No Core boxes: *03* of Corewriter Name: *Terrance Salemane* Signature: *[Signature]*

Water level: m Time: am pm Supervisor Name: *A. Propper* Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 38136



GEOGROUP
 28 Central Road, Sunnyside A/H, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: <u>23 / March / 2013</u>	Contract Name: <u>Feynos field</u>	Rig No: <u>90/67</u>	Machine Start Hour:
Weather: <u>14.07</u>	Client:	Inclination: <u>Vertical</u>	Machine End Hour:
Contract No: <u>301763</u>	BH-no: <u>NM7</u>	Direction: <u>90</u>	Diesel Received: <u>25</u>
Water Used <u>1000L</u>	Kilometers water Carted		

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ⁵⁰⁽⁴⁵⁾ Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWRB /SIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
20.00	21.50	1.50	1.20	0.30	NWD4	1.50							CR650	30%	Black	Slow	WR	—	31.62	7.50	
21.50	23.00	1.50	1.46	0.04	NWD4	1.50							CR650	46%	Black	Slow	WR	—	32.86	7.50	
23.00	24.50	1.50	1.32	0.18	NWD4	1.50							CR650	33%	Black	Slow	WR	✓	31.62	1.50	
24.50	25.00	0.50	0.58	0.08	NWD4	1.50							CR650	99%	Black	Slow	WR	✓	32.86	0.150	

Borehole complete? Yes No Core boxes: 03 of Corewriter Name: Terrance Salemone Signature: [Signature]

Water level: 10.78 m Time: 11:28 am Water level: m Time: pm Supervisor Name: A Brooyse Signature: [Signature]

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 39770



GEORGROUP
28 Central Road, Sunnyside A/H, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 696
www.geogroup.co.za

Date: 11-04-13	Contract Name: Baynesfield	Rig No: 167	Machine Start Hour:
Weather: Cloudy	Client:	Inclination: Vertical	Machine End Hour:
Contract No: J01763	BH-no: Nm 8	Direction: 90°	Pump Type:
Water Used	Kilometers water Carted		Diesel Received: 15L

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg.) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWR/B IS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0,00	1.50	1.50	1.35	-0,15	NXC	0,00								CP650	75%	Brown	Slow				
1.50	1.95	SPT No 1					2	2	3	3	3	3	=45								
1.95	3.00	1.05	1.00	-0,05	NWD4	0,00							"	"	"	"					
3.00	3.45	SPT No 2					2	4	4	4	4	5	=45								
3.45	4.50	1.05	0,90	-0,15	NWD4	0,00							CP650	75%	Brown	Slow					
We waiting for water as from 09H00 until 13H50 Start to drill at 14.15 we																					

Borehole complete? Yes No Core boxes: 1 of _____ Corewriter Name: Ndlovu Signature:

Water level: _____ m Time: _____ am Water level: _____ m Time: _____ pm Supervisor Name: A Rooyen Signature:

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 39771



GEORGROUP
 28 Central Road, Sunnyside AM, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 12-04-13	Contract Name: Baynass field	Rig No: 167	Machine Start Hour:
Weather: Cold	Client:	Inclination: Vertical	Machine End Hour:
Contract No: J01763	BH-no: HMB	Direction: 90°	Pump Type:
Water Used	Kilometers water Carted		Diesel Received: 20h

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal Vertical Inclined ^(deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWR/B /S/G	Rock type	Bit NO.	Accum bit meters		
							0.075	0.150	0.225	0.300	0.375	0.450											
4.50	4.95		SPT3				6	6	7	7	8	8	= 45										
4.95	6.00	1.05	1.05	-	NWD4	1.50								CRbso	Howalt return	Brown	Slow					11H30	
6.00	6.45		SPT4				2	3	4	4	5	7	= 45										
6.45	7.50	1.05	1.00	-0,05	NWD4	1.50								"	"	"	"						
7.50	7.65		SPT5	Refuse			9	...		25			Refuse										
7.65	9.00	1.35	1.30	-0,05	HWD4	6.00								CRbso	Howalt return	Brown	fast					12H50	
9.00	10.50	1.50	1.50	-	"	"								"	"	"	"					15H10	
																							16H00

Liwi Siwaka
 Leonard mphaphu

Borehole complete? Yes No Core boxes: 2 of Corewriter Name: H. D. Feignis Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: A. Prooyser Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 39772



GEOGROUP
 28 Central Road, Sunnyside A/H, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 13-04-13	Contract Name: Bayness field	Rig No: 167	Machine Start Hour:
Weather: Changing	Client:	Inclination: Vertical	Machine End Hour:
Contract No: J01763	BH-no: HMB	Direction: 90°	Pump Type: mono
Water Used	Kilometers water Carted		Diesel Received:

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^(deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
10.50	12.00	1.50	1.00	-0.50	MWD4	6.00							CR650	No water return	Brown	Fast					
12.00	13.50	1.50	1.05	-0.45	"	"							"	"	Black	"	Perce	09110	- 10105		
13.50	15.00	1.50	1.25	-0.25	MWD4	6.00							"	"	Brown	"					
15.00	16.50	1.50	1.50	-	"	"							"	"	"	"	Perce	111400	- 11165		

Borehole complete? Yes No Core boxes: 3 of Corewriter Name: Ndifolani Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: A. Hoogen Signature: *[Signature]*

Instruction by Geologist

Equipment replaced:

Equipment lost:

DAILY DRILLING REPORT

No. 39773



28 Central Road, Sunnyside A/H, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 15-04-13	Contract Name: Bayness field	Rig No: 167	Machine Start Hour:
Weather: HOT	Client:	Inclination: Vertical	Machine End Hour:
Contract No: JO1763	BH-no: Nm8	Direction: 90°	Pump Type: mono
Water Used	Kilometers water Carted		Diesel Received:

Nature of Core Classification: **FR-FRESH** **WR-WEATHERED** **B-BOULDERS** **S-SOILS** **G-GRAVELS**

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWR/B /SIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
16.50	18.00	1.50	1.40	-0.10	NWD4	6.00								0.00	Brown	Fast					
18.00	19.50	1.50	1.50	-	"	"							"	"	"	"	Perker 10H30 - 11-25				
19.50	20.00	0.50	0.50	-	NWD4	6.00							"	"	"	"					
			END of DEPTH		B.# Nm8	20.00															
WE SETUP OF B.H HQ2 & waiting for water as from 13H40 until 14H30 we start to drill at 14H40.																					

Borehole complete? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Core boxes: 3 of 3	Corewriter Name: Ndifrejan	Signature:
Water level: m Time: am	Water level: m Time: pm	Supervisor Name: A Kanyana	Signature:
Instruction by Geologist			
Equipment replaced:			
Equipment lost:			

DAILY DRILLING REPORT

No. 35772

Date: 05/04/2013	Contract Name: Baynes field	Rig No: P205	Machine Start Hour: 01066
Weather: COOL	Client:	Inclination: VERTICAL	Machine End Hour: 01067
Contract No: J01763	BH-no: NM 9	Direction: 90°	Pump Type: MONO Diesel Received:
Water Used	Kilometers water Carted		



GEOGROUP
 28 Central Road, Surrey Park, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^{deg(45)} **Direction:** Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWR/B IS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
WE ARRIVE AT NEW SITE AND WE HAVE SOME SET UPS DIGGING OF SUMS ONLY WAITING TO START DRILLING TOMORROW																					

Borehole complete? Yes No Core boxes: _____ of _____ Corewriter Name: LAWRENCE NEVANI Signature: *[Signature]*

Water level: _____ m Time: _____ am Water level: _____ m Time: _____ pm Supervisor Name: A ROYSEL Signature: *[Signature]*

Instruction by Geologist	
Equipment replaced:	
Equipment lost:	

DAILY DRILLING REPORT

No. 35773



28 Central Road, Suurvela A/H, Lanseria
PO Box 69063, Bryanston, 2021
Phone: +27 85 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 06/04/2013		Contract Name: Baynes field		Rig No: P205	Machine Start Hour: 01067
Weather: HOT		Client:		Rig Type: TWE	Machine End Hour: 01070
Contract No: 101763		BH-no: NM9		Inclination: VERTICAL	Pump Type: Mono
Water Used: 600 L		Kilometers water Carted:		Direction: 90°	Diesel Received:

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^(deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWRB /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0.00	0.85	0.85	0.85	-	NXC									CR650	90%	Brown	Slow	Soil	-	NXC	0.85
0.85	1.70	0.85	0.78	0.07	NXC									CR650	90%	creamy	slow	S	-	NXC	1.70
1.70	2.72	1.02	1.08	+0.06	NWD4									CR650	90%	creamy	slow	WR	-	OLD	11
2.72	4.22	1.50	1.50	-	NWD4									CR650	90%	creamy	slow	WR	-	OLD	11
4.22	5.00	0.78	0.40	0.38	NWD4									CR650	90%	creamy	slow	WR	-	OLD	11
														CR650	90%	creamy	slow	WR	-		
WE WERE WAITING FOR WATER AND WE START DRILLING BY 11H05																					

Jan Maphanga
Lucy Maphanga

Borehole complete? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Core boxes: 1 of	Corewriter Name: LAWRENCE NEVARI	Signature: <i>[Signature]</i>
Water level: m Time: am	Water level: m Time: pm	Supervisor Name:	Signature:

Instruction by Geologist
Equipment replaced:
Equipment lost:

DAILY DRILLING REPORT

No. 35774

Date: 08/04/2013		Contract Name: BAYNES FIELD		Rig No: P205	Machine Start Hour: 01070
Weather: HOT		Client:	Inclination: VERTICAL	Rig Type: JWE	Machine End Hour: 01077
Contract No: J01763		BH-no: NM 9	Direction: 90	Pump Type: Mono	Diesel Received:
Water Used: 2800L		Kilometers water Carted:			



28 Central Road, Sunnyside, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B/IS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
5.00	5.73	0.73	0.83	+0.10	NWD4	1.50							CR650	80%	creamy	slow	WR	-	OLD	OLD	
5.73	7.23	1.50	0.80	0.70	NWD4	1.50							CR650	80%	creamy	slow	WR	-	OLD	"	
7.23	8.00	0.77	0.53	0.24	NWD4	1.50							CR650	80%	creamy	fast	WR	-	OLD	"	
8.00	8.73	0.73	0.90	+0.17	NWD4	1.50							CR650	80%	creamy	fast	WR	-	OLD	"	
8.73	10.23	1.50	1.52	+0.02	NWD4	1.50							CR650	80%	grey	fast	WR	-	OLD	"	
10.23	11.00	0.77	0.63	0.14	NWD4	1.50							CR650	80%	grey	fast	WR	-	OLD	"	
11.00	11.73	0.73	0.81	+0.08	NWD4	1.50							CR650	80%	grey	fast	WR	-	OLD	"	
11.73	13.23	1.50	1.47	0.03	NWD4	1.50							CR650	80%	grey	fast	FR	-	"	"	
13.23	14.00	0.77	0.69	0.08	NWD4	1.50							CR650	80%	grey	fast	FR	-	"	"	
<p>WE HAVE SOME 4 PACKERS 2-5 and 5-8 and 8-11 and 11-14.</p>																					

Borehole complete? Yes No Core boxes: 2 of Corewriter Name: LAWRENCE NEVILL Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: A PEARSON Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 35775

Date: 09/04/2013	Contract Name: Baynes Field	Rig No: P205	Machine Start Hour: 01077
Weather: HOT	Client:	Inclination: VERTICAL	Rig Type: JWE
Contract No: J01763	BH-no: NM9	Direction: 90°	Pump Type: Mono
Water Used: 1000 L	Kilometers water Carted:		Diesel Received:



GEOGROUP
 28 Central Road, Sunnyside AVH, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 696
 www.geogroup.co.za

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^{deg(45)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
14.00	16.10	2.12	1.98	0.14	TNW	1.50							CR650	70%	Grey	fast	FR	-	1214	OLD	
16.10	17.00	0.88	0.66	0.22	TNW	1.50							CR650	70%	Grey	fast	FR	-	1214	OLD	
17.00	19.12	2.12	2.06	0.14	TNW	1.50							CR650	0%	Grey	fast	FR	-	1214	11	
19.12	20.11	0.99	0.93	0.06	TNW	1.50							CR650	0%	Grey	fast	FR	-	1214	11	

WE HAVE DONE 2 PACKER 14-17 WHERE THE WERE TOTAL WATER LOSS AND ALSO 17-20 WERE THE SAME. WE COMPLETE BORE HOLE AND WE MOVE TO THE NE BORE ONLY WANT TO DO SETUPS AND GO FURTHER WITH OUR TASK TOMMORROW WHICH IS 9 KM.

Jan Maphanga
 Lucky Mabilana

Borehole complete? Yes No Core boxes: 3 of 3 Corewriter Name: LAWRENCE NEVARI Signature: *[Signature]*

Water level: m Time: am Water level: 15.80m Time: 13:00pm Supervisor Name: A ROOYSEK Signature: *[Signature]*

Instruction by Geologist	
Equipment replaced:	
Equipment lost:	

DAILY DRILLING REPORT

No. 39766



GEOGROUP
 28 Central Road, Sunnyside AH, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 06-04-13	Contract Name: Baynes field	Rig No: 168	Machine Start Hour:
Weather: HOT	Client:	Inclination: Vertical	Machine End Hour:
Contract No: J01763	BH-no: HM10	Direction: 90	Diesel Received:
Water Used	Kilometers water Carted		

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^(deg/45) **Direction:** Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters	
							0.075	0.150	0.225	0.300	0.375	0.450										
			we	sample	as	from	08400						und	10400			1					
			for	water.													2					

Lizwi Siwala
Leonard Mphahlele

Borehole complete? Yes No Core boxes: of Corewriter Name: Ndiferani Signature:

Water level: m Time: am Water level: m Time: pm Supervisor Name: Signature:

Instruction by Geologist

Equipment replaced:

Equipment lost:

DAILY DRILLING REPORT

No. 39767



28 Central Road, Sunningdale, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 696
www.geogroup.co.za

Date: 08-24-13	Contract Name: Bayness field	Rig No: 168	Machine Start Hour: 240.7
Weather: HOT	Client:	Inclination: Vertical	Machine End Hour:
Contract No: J01763	BH-no: TM10	Direction: 90°	Pump Type:
Water Used	Kilometers water Carted		Diesel Received: 25L

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^{deg(45)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /SIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0.00	0.90	0.90	0.40	-0.50	Hxc	0.00							CR650	75%	Brown	Slow					
0.90	1.50	0.60	0.30	-0.30	"	"							"	"	"	"					
1.50	2.77	1.27	1.27	-	NWD4	1.50							"	"	"	"					
2.77	3.52	0.75	0.50	-0.25	"	"							"	"	"	Fast					
3.52	5.02	1.50	0.95	-0.55	"	"							CR650	75%	"	"					
5.02	6.52	1.50	1.15	-0.35	NWD4	1.50							"	"	Black	"					
6.52	8.02	1.50	1.40	-0.10	"	"							"	"	"	"					
8.02	11.02	3.00	2.80	-0.20	TNW	"							"	"	"	"					
We waiting for water as from 8H00 until 10H00 & we start to drill at 10H20																					
															Lizwi Siwela Leonard Mphahlele						

Borehole complete? Yes No Core boxes: 2 of Corewriter Name: M. Dizeani Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: A. Bayness Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 39768



GEORGROUP
 28 Central Road, Sunnella A/H, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 09-04-13	Contract Name: Baynass field	Rig No: 168	Machine Start Hour: 24.6
Weather: Hot	Client:	Inclination: Vertical	Machine End Hour:
Contract No: 501763	BH-no: Nm10	Direction: 90°	Pump Type:
Water Used	Kilometers water Carted		Diesel Received:

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^{deg/45} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters	
							0.075	0.150	0.225	0.300	0.375	0.450										
11.02	12.52	1.50	1.35	-0.15	TNW	1.50								CR650	75%	Black	Fast					
12.52	15.52	3.00	2.75	-0.25	"	"							"	"	"	"						
15.52	17.77	2.25	2.25	-	TNW	"							"	"	"	"						
17.77	18.52	0.75	0.75	-	NWD4	"							"	"	"	"						
18.52	20.02	1.50	1.50	-	"	"							"	"	"	"						
						END OF B.H Nm10																
						DEPTH 20.02																
																			Lizwi Siwera		Leonard Mphahle	

Borehole complete? Yes No Core boxes: 3 of 3 Corewriter Name: Ndiferani Signature:

Water level: m Time: am Water level: 5 m Time: 16H00 pm Supervisor Name: A Moya Signature:

Instruction by Geologist: _____
 Equipment replaced: _____
 Equipment lost: _____

DAILY DRILLING REPORT

No. 35779



28 Central Road, Sunnyside, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 66 143 6632
Fax: 066 6633 696
www.geogroup.co.za

Date: 13/04/2013	Contract Name: BAYNES FIELD	Rig No: P205	Machine Start Hour: 01092
Weather: COOL	Client:	Inclination: VERTICAL	Rig Type: TWE
Contract No: J01763	BH-no: NQ 1	Direction: 90°	Machine End Hour: 01096
Water Used: 900 L	Kilometers water Carted:	Pump Type: Mono	Diesel Received:

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0.00	0.85	0.85	0.82	0.03	NXC	-							CR650	90%	Brown	Slow	Soil	-	NXC	0.85	
0.85	1.31	0.46	0.49	0.03	NXC	-							CR650	90%	Creamy	Slow	Soil	-	NXC	1.31	
1.31	2.82	1.51	1.30	0.21	NWD4	1.50							CR650	90%	Creamy	Slow	WR	-	OLD	OLD	
2.82	4.32	1.50	1.36	0.14	NWD4	1.50							CR650	80%	Creamy	Slow	WR	-	OLD	11	
4.32	5.82	1.50	1.18	0.32	NWD4	1.50							CR650	80%	Creamy	Slow	WR	-	OLD	11	

WE WENT TO WORK by 7:00 AM WE MOVE our equipment
 we TO THE NEW BORE HOLE Doing Set ups and start drilling
 after we HAVE DONE PTA.

Lawrence Nene
 Sany Mabizana

Borehole complete? Yes No Core boxes: 1 of _____ Corewriter Name: LAWRENCE NENE Signature: *[Signature]*

Water level: _____ m Time: _____ am Water level: _____ m Time: _____ pm Supervisor Name: A. Kanyana Signature: *[Signature]*

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 35780

Date: 15/04/2013	Contract Name: Baynes Field	Rig No: P205	Machine Start Hour: 01096
Weather: HOT	Client:	Inclination: VERTICAL	Rig Type: TWE
Contract No: J01763	BH-no: NQ1	Direction: 90°	Machine End Hour: 01099
Water Used: 2800	Kilometers water Carted:	Pump Type: Mono	Diesel Received:



28 Central Road, Surrey Park, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^{deg(45)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWRB /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
5.82	7.32	1.50	1.20	0.30	NWD4	4.50								CR650	80%	creamy	Slow	WR	-	OLD	OLD
7.32	8.82	1.50	1.12	0.38	NWD4	4.50								CR650	80%	creamy	Slow	WR	-	OLD	"
8.82	10.32	1.50	1.31	0.19	NWD4	4.50								CR650	80%	creamy	fast	WR	-	OLD	"
10.32	11.82	1.50	1.30	0.20	NWD4	4.50								CR650	80%	grey	fast	WR	-	OLD	"
11.82	13.32	1.50	1.37	0.13	NWD4	4.50								CR650	80%	grey	fast	WR	-	OLD	"
13.32	14.82	1.50	1.58	0.08	NWD4	4.50								CR650	80%	grey	fast	WR	-	OLD	"
14.82	16.32	1.50	1.37	0.13	NWD4	4.50								CR650	80%	grey	fast	FR	-	OLD	"
16.32	16.82	0.50	0.44	0.06	TNW	4.50								CR650	80%	grey	fast	FR	-	OLD	"
16.82	18.32	1.50	1.45	0.05	NWD4	4.50								CR650	0%	grey	fast	FR	-	OLD	"
18.32	19.82	1.50	1.47	0.03	NWD4	4.50								CR650	0%	grey	fast	FR	-	OLD	"
19.82	20.19	0.37	0.47	0.10	NWD4	4.50								CR650	0%	grey	fast	FR	-	OLD	"
WE COMPLETE BORE HOT BY 15H05 WE ALSO RULL																					
OBT CASING WAITING TO LOAD TOMMOROW! Jam maphang																					
Lucky Mabilamba																					

Borehole complete? Yes No Core boxes: 3 of 3 Corewriter Name: LAWRENCE NEVARE Signature: [Signature]

Water level: m Time: am Water level: 18.20m Time: 15:20pm Supervisor Name: P. Brayson Signature: [Signature]

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 35781

Date: 16/04/2013	Contract Name: Baynes field	Rig No: p205	Machine Start Hour:
Weather: HOT	Client:	Inclination: VERTICAL	Machine End Hour:
Contract No: J01763	BH-no: NQ1	Direction: 90°	Pump Type: MONO
Water Used	Kilometers water Carted		



28 Central Road, Surrey Hills, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 86 143 6632
 Fax: 036 6633 696
 www.geogroup.co.za

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined^(deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FRWRB /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
WE WENT TO SITE AND WE LOAD THE RIG A OTHER EQUIPMENT TO THE CAMP BY 15H10																					

Borehole complete? Yes No Core boxes: 3 of 3 Corewriter Name: LAWRENCE NEVARI Signature:

Water level: m Time: am Water level: m Time: pm Supervisor Name: A BOOYISA Signature:

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 39774



28 Central Road, Sunnella A/H, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 15-04-13	Contract Name: Baynes field		Rig No: 168	Machine Start Hour:
Weather: Hot	Client:	Inclination: Vertical	Rig Type: ywe	Machine End Hour:
Contract No: 501763	BH-no: Na2	Direction: 90°	Pump Type: mono	Diesel Received:
Water Used	Kilometers water Carted			

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /SIG	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0,10	0,90	0,80	0,35	-0,55	Hxc	0,10								CR650	75%	Brown	SLOW				
0,90	1,50	0,60	0,40	-0,20	"	"							"	"	"	"					
1,50	2,07	0,57	0,35	-0,22	"	"							"	"	"	Fast					
2,07	3,57	1,50	1,45	-0,05	Nwd4	1,50							"	75%	"	"					

Lizwi Siwela
Leonard mpephul

Borehole complete? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Core boxes: 1 of	Corewriter Name: Adiferanji	Signature:
Water level: m Time: am	Water level: m Time: pm	Supervisor Name: A Rooyen	Signature:
Instruction by Geologist			
Equipment replaced:			
Equipment lost:			

DAILY DRILLING REPORT

No. 39775



28 Central Road, Sunnyside A7H, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 896
www.geogroup.co.za

Date: 16-04-13	Contract Name: Bayness field	Rig No: 168	Machine Start Hour:
Weather: HUE	Client:	Inclination: Vertical	Machine End Hour:
Contract No: J01763	BH-no: HQ2	Direction: 900	Pump Type:
Water Used	Kilometers water Carted		Diesel Received: 20L

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
3.57	5.07	1.50	1.50	-	Hwd4	1.50							CR650	75%	Brown	fast					
5.07	6.57	1.50	1.50	-	"	"							"	"	"	"					
6.57	8.07	1.50	1.05	-0.45	"	"							"	"	"	"					
8.07	9.57	1.50	1.20	-0.30	Hwd4	1.50							"	75%	"	"					
9.57	11.07	1.50	1.30	-0.20	"	"							"	"	Black	"					
11.07	12.57	1.50	1.50	-	"	"							"	"	"	"					
12.57	14.07	1.50	1.45	-0.05	"	"							CR650	75%	Black	fast					
14.07	15.57	1.50	1.50	-	Hwd4	1.50							"	"	"	"					
15.57	17.07	1.50	1.50	-	"	"							CR650	Howater return	Black	fast					
17.07	18.57	1.50	1.25	-0.25	"	"							"	"	"	"					
18.57	20.07	1.50	1.60	+0.10	"	"							"	"	"	"					
END OF B.H HQ2																					
DEPTH 20.07																					

Borehole complete? Yes No Core boxes: 3 of 3 Corewriter Name: Hiferan' Signature: _____

Water level: m Time: am Water level: 7.9 m Time: 13.35pm Supervisor Name: A Bayness Signature: _____

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 35776



GEORGROUP
 28 Central Road, Sunnyside AH, Lanseria
 PO Box 68063, Bryanston, 2021
 Phone: +27 88 143 6632
 Fax: 086 6633 896
 www.geogroup.co.za

Date: 10/04/2013	Contract Name: Baynes field	Rig No: P205	Machine Start Hour: 01081
Weather: Rain	Client:	Inclination: Vertical	Machine End Hour: 0183
Contract No: J01763	BH-no: NQ3	Direction: 90°	Pump Type: Motor Diesel Received: 25
Water Used: 1000	Kilometers water Carted:		

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^(deg/45) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B IS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
<p style="font-size: large; font-family: cursive;"> WE DIDN'T START YET TO DRILL NEW BORE HOLE THAT MENTIONED ABOVE CAUSE OF HEAVY RAIN THERE WHERE RAIN THE WHOLE DAY WE GET INSTRUCTION NOT TO GO THERE ON SITE CAUSE THERE IS NO ACCESS TO GET IN. </p> <p style="font-size: small; text-align: right;"> San Maphanga Lucky Matshana </p>																					

Borehole complete? Yes No Core boxes: of Corewriter Name: LAWRENCE NEVARI Signature: *[Signature]*

Water level: m Time: am Water level: m Time: pm Supervisor Name: A PROYSEL Signature: *[Signature]*

Instruction by Geologist	
Equipment replaced:	
Equipment lost:	

DAILY DRILLING REPORT

No. 35777

Date: 11/04/2013	Contract Name: Baynes field	Rig No: P205	Machine Start Hour: 01081
Weather: Cool	Client:	Inclination: VERTICAL	Machine End Hour: 01089
Contract No: J01763	BH-no: N.Q.3	Direction: 90°	Pump Type: M.O.W.
Water Used: 1600	Kilometers water Carted:		Diesel Received:



28 Central Road, Sunnyside, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 696
www.geogroup.co.za

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NO/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined ^{deg(45)} Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B/IS/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
0.00	0.85	0.85	0.70	0.15	NJCC								CR650	90%	creamy slow	WR	-	NJCC	0.85		
0.85	1.40	0.55	0.50	0.03	NJCC								CR650	90%	creamy slow	WR	-	NJCC	1.40		
1.40	2.85	1.45	1.38	0.07	NWB4								CR650	90%	creamy slow	WR	-	OLD	OLD		
2.85	4.35	1.50	1.32	0.18	NWD4	1.50							CR650	90%	creamy slow	WR	-	OLD	11		
4.35	5.83	1.48	1.21	0.27	NWD4	4.50							CR650	80%	grey slow	WR	-	OLD	11		
5.83	7.35	1.52	1.56	+0.04	NWD4	4.50							CR650	80%	grey slow	WR	-	OLD	11		
7.35	8.85	1.50	1.35	0.15	NWD4	4.50							CR650	80%	grey slow	WR	-	OLD	11		
8.85	10.37	1.52	1.58	+0.06	NWD4	4.50							CR650	80%	grey slow	WR	-	OLD	11		
WE 10 H 45' DONE Set ups and start drilling by Jan Mathang Lucky Mabitaha																					

Borehole complete? Yes No Core boxes: 2 of Corewriter Name: LAWRENCE NENANI Signature: [Signature]

Water level: m Time: am Water level: m Time: pm Supervisor Name: A. BOYSE Signature: [Signature]

Instruction by Geologist: _____

Equipment replaced: _____

Equipment lost: _____

DAILY DRILLING REPORT

No. 35778



28 Central Road, Sunnyside/AH, Lanseria
PO Box 68063, Bryanston, 2021
Phone: +27 86 143 6632
Fax: 086 6633 696
www.geogroup.co.za

Date: 12/04/2013	Contract Name: BAYNES field	Rig No: P205	Machine Start Hour: 01089
Weather: Cloudy	Client:	Inclination: VERTICAL	Machine End Hour: 010912
Contract No: J01763	BH-no: NQ3	Direction: 90°	Pump Type: mono Diesel Received: 254
Water Used 2100L	Kilometers water Carted		

Nature of Core Classification: FR-FRESH WR-WEATHERED B-BOULDERS S-SOILS G-GRAVELS

Legend Run length: Depth to - Depth from = Run length Bit type eg.: NWD4/ TNW/ NQ/ HLMC etc Drilling Response: FAST/ SLOW/ EVEN/ UNEVEN

Inclination: Horizontal, Vertical, Inclined (deg) Direction: Compass reading (or from Geologist)

Depth from	Depth to	Run Length	Core Recovered	Core loss	Bit type	Casing Depth	SPT Blow Count						Sample recovered - SPT, Undisturbed	Drill fluid	Water return %	Colour	Drilling response	FR/WR/B /S/G	Rock type	Bit NO.	Accum bit meters
							0.075	0.150	0.225	0.300	0.375	0.450									
10.37	11.87	1.50	1.43	0.07	NWD4	4.50							CR650	80%	Grey	fast	FR	-	010	010	
11.87	14.76	2.89	2.95	0.06	TNW	4.50							CR650	80%	Grey	fast	FR	-	010	010	
14.76	17.76	3.00	2.97	0.03	TNW	4.50							CR650	80%	Grey	fast	FR	-	11	11	
17.76	20.18	2.42	2.56	0.14	TNW	4.50							CR650	80%	Grey	fast	FR	-	11	11	
WE WENT TO WORK BY 7H00 AM AND WE START DRILLING BY 09:40 BECAUSE THE WATER NO WATER WE ALSO COMPLETE BORE HOLES ONLY GOING TO REPAIR OUR EQUIPMENT TO THE NEW BOREHOLE MACHINES.																					

Jan Maphanga
Lucy Mkhizana

Borehole complete? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	Core boxes: 3 of 3	Corewriter Name: LAWRENCE NEVAM	Signature: <i>[Signature]</i>
--	--------------------	---------------------------------	-------------------------------

Water level: m Time: am	Water level: 12.0m Time: 15.10 pm	Supervisor Name: A Phisoa	Signature: <i>[Signature]</i>
-------------------------	-----------------------------------	---------------------------	-------------------------------

Instruction by Geologist	
Equipment replaced:	
Equipment lost:	

Water test results

FIELD DATA FROM LUGEON TESTS

Drillhole No: NM1 Inclination: 90° Test No: 1

Date of Test: 25/03/2013 Test Section from.....m to.....m

Packer Type: single Packer Pressure 12 kPa

Bottom of Casing:m Water Levelm

Base of Hole: 5 m Hole \varnothing at test level NWD 4 mm

Pressure gauge height above collar: 2.6 m

Details of test equipment:

Calibration Curve No:



GEOMECHANICS
 Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIRST STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		12	28	28	20	12	
Flowmeter Reading	10	1879,7	1881,0	1881,9	1882,9	1883,8	
Dipstick (Litres)		1881,0	1881,9	1882,9	1883,8	1885,0	
Water Intake (Litres)		2	0.9	0.1	0.9	1.2	
SECOND STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		30	30	10	50	30	
Flowmeter Reading	10	1885,0	1885,4	1886,2	1887,4	1887,8	
Dipstick (Litres)		1885,4	1886,2	1887,4	1887,8	1888,2	
Water Intake (Litres)		0.4	0.8	1.2	0.4	0.4	
THIRD STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		48	80	112	80	48	
Flowmeter Reading	10	1888,2	1888,7	1889,8	1893,2	1894,6	
Dipstick (Litres)		1888,7	1889,8	1893,2	1894,6	1895,1	
Water Intake (Litres)		0.5	1.1	3.4	1.4	0.5	
FOURTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							
FIFTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							
SIXTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							

FIELD DATA FROM LUGEON TESTS

Drillhole No: NM1 Inclinaton: 90° Test No: 4

Date of Test: 26/03/2013 Test Section from 1.1 m to 1.4 m

Packer Type: Single Packer Pressure 99 kPa

Bottom of Casing: 1.5 m Water Level m

Base of Hole: 1.4 m Hole \varnothing at test level TNW mm

Pressure gauge height above collar: 2.6 m

Details of test equipment:


Calibration Curve No:



GEOMECHANICS
 Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIRST STAGE							
Time	(Minutes)	18	10	10	10	10	Av Flow
Flowmeter	Reading	1895,1	1897,6	1902,6	1904,5	1904,5	q
Dipstick	(Litres)	1897,6	1902,0	1904,5	1904,5	1908,0	(Litres/Minute)
Water Intake	(Litres)	2.5	4.4	2.5	0	3.5	
SECOND STAGE							
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	1908,8	1911,7	1914,7	1919,4	1921,3	q
Dipstick	(Litres)	1911,7	1914,7	1919,4	1921,3	1923,0	(Litres/Minute)
Water Intake	(Litres)	2.9	3	4.7	1.9	1.7	
THIRD STAGE							
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	1923,0	1927,2	1932,7	1938,1	1942,9	q
Dipstick	(Litres)	1927,2	1932,7	1938,1	1942,9	1946,6	(Litres/Minute)
Water Intake	(Litres)	4.2	5.5	5.4	4.8	3.7	
FOURTH STAGE							
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	1946,6	1939,9	1942,3	1986,5	2000,5	q
Dipstick	(Litres)	1959,9	1972,3	1986,5	2000,5	2013,3	(Litres/Minute)
Water Intake	(Litres)	13.3	12.4	14.2	14	12.8	
FIFTH STAGE							
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						
SIXTH STAGE							
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						

FIELD DATA FROM LUGEON TESTS



Geotechnical & Civil Contractors
 33 Woburn Street, Chartwell
 P.O. Box 68063, Bryanston, 2021
 Tel: 460-0280 or 460-0202
 Fax: 460-0281
 Cell: 082 772 3910

HM2 Inclination: Vertical Test No: 1
 Date: 04 / April / 2013
 Test Section from m to m
 Packer Pressure kPa
 Water Level m
 Hole ① at test level mm
 Gauge height above collar: m
 Equipment:
 Core No:

2-5 m Gauge Pressure

Minutes)	12	20	28	20	12	Av Flow q (Litres/Minute)
Reading	6.8	5.5	3.0	4.0	2.0	
Press	5.5	3.0	4.0	2.0	0.5	
Litres	1.3	2.5	1.0	2.0	1.5	

5.8 m Gauge Pressure

Minutes)	30	50	70	50	30	Av Flow q (Litres/Minute)
Reading	0.5	2.4	1.9	1.8	2.0	
Press	2.4	1.9	1.8	2.0	1.0	
Litres	1.9	0.5	0.1	0.2	1.0	

05/04/2013 8-11 Gauge Pressure

Minutes)	72	128	176	128	72	Av Flow q (Litres/Minute)
Reading	1.0	1.5	0.5	0.5	1.6	
Press	1.5	0.5	0.5	1.6	0.5	
Litres	0.5	1.0	0.0	1.1	1.1	

11-14 m Gauge Pressure

Minutes)	99	176	242	176	99	Av Flow q (Litres/Minute)
Reading	0.5	10.8	14.8	20.6	18.8	
Press	10.8	14.6	20.6	18.8	9.8	
Litres	10.3	3.8	6.0	2.0	8.8	


11-12 m 03/04/2013 Gauge Pressure

Minutes)	126	224	224 300	224	226	Av Flow q (Litres/Minute)
Reading						
Press						
Litres						

12 Gauge Pressure

Minutes)						Av Flow q (Litres/Minute)
Reading						
Press						
Litres						

FIELD DATA FROM LUGEON TESTS



Geotechnical & Civil Contractors
 33 Woburn Street, Chartwell
 P.O. Box 68063, Bryanston, 2021
 Tel: 460-0280 or 460-0202
 Fax: 460-0281
 Cell: 082 772 3910

W 2 Inclination: Vertical Test No: 5

08/April/2003 Test Section fromm to.....m

Single Packer PressurekPa

4.50 m Water Levelm

..... m Hole ① at test level THWmm


..... gauge height above collar:m

..... test equipment:

..... Curve No:

STAGE 1						
Gauge Pressure						Av Flow q (Litres/Minute)
Time (Minutes)	128	224	308	224	126	
Reading	9.8	1.2	3.5	17.0	13.4	
Litres	1.2	3.5	17.0	13.4	7.6	
Water Make (Litres)	8.6	2.3	13.5	3.6	5.8	
STAGE 2						
Gauge Pressure						Av Flow q (Litres/Minute)
Time (Minutes)						
Reading						
Litres						
Water Make (Litres)						
STAGE 3						
Gauge Pressure						Av Flow q (Litres/Minute)
Time (Minutes)						
Reading						
Litres						
Water Make (Litres)						
STAGE 4						
Gauge Pressure						Av Flow q (Litres/Minute)
Time (Minutes)						
Reading						
Litres						
Water Make (Litres)						
STAGE 5						
Gauge Pressure						Av Flow q (Litres/Minute)
Time (Minutes)						
Reading						
Litres						
Water Make (Litres)						
STAGE 6						
Gauge Pressure						Av Flow q (Litres/Minute)
Time (Minutes)						
Reading						
Litres						
Water Make (Litres)						

FIELD DATA FROM LUGEON TESTS



Geotechnical & Civil Contractors
 33 Woburn Street, Chartwell
 P.O. Box 68063, Bryanston, 2021
 Tel: 460-0280 or 460-0202
 Fax: 460-0281
 Cell: 082 772 3910

Inclination: Vertical Test No: 1

2/14/2013
single

Test Section fromm to.....m
 Packer PressurekPa
 Water Levelm
 Hole Ø at test level 7.11.0.....mm

Height above collar:m

Equipment:

Curve No:

7-20m

Gauge Pressure						Av Flow q (Litres/Minute)
(Minutes)	<u>152</u>	<u>272</u>	<u>374</u>	<u>242</u>	<u>153</u>	
Reading	<u>7.6</u>	<u>8.9</u>	<u>3.8</u>	<u>11.8</u>	<u>16.0</u>	
(Litres)	<u>5.9</u>	<u>8.8</u>	<u>11.8</u>	<u>16.0</u>	<u>18.8</u>	
(Litres)	<u>1.7</u>	<u>0.1</u>	<u>3.0</u>	<u>5.8</u>	<u>2.8</u>	

Gauge Pressure						Av Flow q (Litres/Minute)
(Minutes)						
Reading						
(Litres)						
(Litres)						

Gauge Pressure						Av Flow q (Litres/Minute)
(Minutes)						
Reading						
(Litres)						
(Litres)						

Gauge Pressure						Av Flow q (Litres/Minute)
(Minutes)						
Reading						
(Litres)						
(Litres)						

Gauge Pressure						Av Flow q (Litres/Minute)
(Minutes)						
Reading						
(Litres)						
(Litres)						

Gauge Pressure						Av Flow q (Litres/Minute)
(Minutes)						
Reading						
(Litres)						
(Litres)						



GEOMECHANICS
 Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIELD DATA FROM LUGEON TESTS	
Drillhole No: <u>NM3</u>	Inclination: <u>Vertical</u> Test No:
Date of Test: <u>04-04-13</u>	Test Section from: <u>5.00</u> m to <u>8.00</u> m
Packer Type: <u>Single</u>	Packer Pressure <u>45</u> kPa
Bottom of Casing: <u>4.50</u> m	Water Level m
Base of Hole: <u>8</u> m	Hole \varnothing at test level <u>N.W.D.H</u> mm
Pressure gauge height above collar: <u>2.7</u> m	
Details of test equipment:	
Calibration Curve No:	

FIRST STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		80	110	80	45		
5m - 8m	45	10	10	10	10	10	
Flowmeter Reading		870	870	870	870	870	
Dipstick (Litres)		870	870	870	870	870	
Water Intake (Litres)		0	0	0	0	0	
SECOND STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		128	176	128	72		
8m - 11m	72	10	10	10	10	10	
Flowmeter Reading		870	870	870	870	870	
Dipstick (Litres)		870	870	870	870	870	
Water Intake (Litres)		0	0	0	0	0	
THIRD STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		176	242	176	99		
11m - 14m	99	10	10	10	10	10	
Flowmeter Reading		870	870	870	870	870	
Dipstick (Litres)		870	870	870	870	870	
Water Intake (Litres)		0	0	0	0	0	
FOURTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		224	308	224	126		
14m - 17m	126	10	10	10	10	10	
Flowmeter Reading		870	870	870	870	870	
Dipstick (Litres)		870	870	870	870	870	
Water Intake (Litres)		0	0	0	0	0	
FIFTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		272	374	272	153		
17m - 20m	153	10	10	10	10	10	
Flowmeter Reading		870	870	870	870	870	
Dipstick (Litres)		870	870	870	870	870	
Water Intake (Litres)		0	0	0	0	0	
SIXTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							

FIELD DATA FROM LUGEON TESTS

Drillhole No: HM3 Inclinaton: Vertical Test No: 1

Date of Test: 25-03-13 Test Section from 2 m to 5 m

Packer Type: Single Packer Pressure 12 kPa

Bottom of Casing: 0,00 m Water Level m

Base of Hole: 5 m Hole \varnothing at test level NWD4 mm

Pressure gauge height above collar: 2.7 m

Details of test equipment:

Calibration Curve No:



GEOMECHANICS
 Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIRST STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		12	20	28	20	12	
Flowmeter Reading		870	870	870	870	870	
Dipstick (Litres)		870	870	870	870	870	
Water Intake (Litres)		0	0	0	0	0	
SECOND STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							
THIRD STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							
FOURTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							
FIFTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							
SIXTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							



GEOMECHANICS
 Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

NM4 FIELD DATA FROM LUGEON TESTS	
Drillhole No: <u>NW 4</u>	Inclination: <u>Vertical</u> Test No: <u>1</u>
Date of Test: <u>21-03-13</u>	Test Section from <u>2</u> m to <u>5</u> m
Packer Type: <u>Single</u>	Packer Pressure <u>12</u> kPa
Bottom of Casing: <u>0,2</u> m	Water Level <u> </u> m
Base of Hole: <u>5</u> m	Hole \varnothing at test level <u>NW 4</u> mm
Pressure gauge height above collar: <u>2.70</u> m	
Details of test equipment: <u> </u>	
Calibration Curve No: <u> </u>	

FIRST STAGE							
		Gauge Pressure					
		12	20	28	20	12	
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	0	0	0	0	0	
COND STAGE							
		Gauge Pressure					
		30	50	70	50	30	
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	000	000	000	000	000	
THIRD STAGE							
		Gauge Pressure					
		48	80	112	80	48	
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	000	000	000	000	000	
FOURTH STAGE							
		Gauge Pressure					
		99	178	242	176	99	
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	000	000	000	000	000	
FIFTH STAGE							
		Gauge Pressure					
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						
SIXTH STAGE							
		Gauge Pressure					
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						

FIELD DATA FROM LUGEON TESTS

Drillhole No.: Hw04 Inclination: Vertical Test No: 5

Date of Test: 23-03-13 Test Section from 15 m to 17 m

Packer Type: Single Packer Pressure 126 kPa

Bottom of Casing: 1.50 m Water Level m

Base of Hole: 1.7 m Hole \varnothing at test level Hw04 mm

Pressure gauge height above collar: 2.70 m

Details of test equipment:

Calibration Curve No:



GEOMECHANICS
 Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIRST STAGE							
		126		Gauge Pressure		308	
		224		224		126	
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	0	0	0	0	0	
COND STAGE							
		153		Gauge Pressure		344	
		272		272		153	
Time	(Minutes)	870	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	000	000	000	000	000	
THIRD STAGE							
		Gauge Pressure					
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						
FOURTH STAGE							
		Gauge Pressure					
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						
FIFTH STAGE							
		Gauge Pressure					
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						
SIXTH STAGE							
		Gauge Pressure					
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						

FIELD DATA FROM LUGEON TESTS

Drillhole No: MM 5 Inclinaton: 90° Test No: 1

Date of Test: 21-03-2013 Test Section from 2 m to 5 m

Packer Type: SINGLE Packer Pressure: kPa

Bottom of Casing: m Water Level: 3.10 m

Base of Hole: 5 m Hole \varnothing at test level: 4WDY mm

Pressure gauge height above collar: m

Details of test equipment:

Calibration Curve No:



GEOMECHANICS
 Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIRST STAGE 2-5		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		12	20	28	20	12	
Flowmeter Reading		49.4	49.8	50.4	51.7	52.8	
Dipstick (Litres)		49.8	50.4	51.7	52.8	53.3	
Water Intake (Litres)		0.4	0.6	1.3	1.1	0.5	
SECOND STAGE 5-8		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		30	30	70	50	30	
Flowmeter Reading		59.6	63.4	68.1	72.3	73.4	
Dipstick (Litres)		63.4	68.1	72.3	73.4	74.9	
Water Intake (Litres)		3.8	4.7	4.2	1.1	1.5	
THIRD STAGE 8-11		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		48	80	91.2	80	48	
Flowmeter Reading		74.9	75.8	76.2	77.3	77.8	
Dipstick (Litres)		75.8	76.2	77.3	77.8	78.1	
Water Intake (Litres)		0.9	0.4	1.1	0.5	0.3	
FOURTH STAGE 11-14		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		99	99	242	60	99	
Flowmeter Reading		78.3	84.7	93.4	05.5	07.3	
Dipstick (Litres)		84.7	93.4	05.5	07.3	10.6	
Water Intake (Litres)		6.4	8.7	80.9	1.8	3.3	
FIFTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							
SIXTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							

FIELD DATA FROM LUGEON TESTS

Drillhole No: <u>JMS</u>	Inclination: <u>90°</u>	Test No: <u>5</u>
Date of Test: <u>04-04-2013</u>	Test Section from <u>14</u> m to <u>17</u> m	
Packer Type: <u>Single</u>	Packer Pressure	kPa
Bottom of Casing: <u>9.00</u> m	Water Level <u>12.30</u> m	
Base of Hole: <u>17.00</u> m	Hole \varnothing at test level <u>JMW</u> mm	
Pressure gauge height above collar:m		
Details of test equipment:		
Calibration Curve No:		

**GEOMECHANICS**

Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIRST STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)	126	224	308	84	126		
Flowmeter Reading	16.1	18.8	22.4	28.5	29.8		
Dipstick (Litres)	18.8	22.4	28.5	29.8	31.5		
Water Intake (Litres)	2.7	3.6	6.1	1.3	1.7		
SECOND STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)	153	272	374	102	153		
Flowmeter Reading	31.5	34.6	38.1	41.9	42.8		
Dipstick (Litres)	34.6	39.1	41.9	42.8	45.5		
Water Intake (Litres)	3.1	3.5	3.8	0.9	2.7		
THIRD STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							
FOURTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							
FIFTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							
SIXTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							

FIELD DATA FROM LUGEON TESTS

Drillhole No: MMS Inclination: 90°E Test No: 7

Date of Test: 05-04-2013 Test Section from 20 m to 23 m

Packer Type: Single Packer Pressure: kPa

Bottom of Casing: 9.00 m Water Level: 14.50 m

Base of Hole: 23.00 m Hole \varnothing at test level: TMW mm

Pressure gauge height above collar: m

Details of test equipment:

Calibration Curve No:



GEOMECHANICS

Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIRST STAGE <u>20 - 23</u>		Gauge Pressure					Av Flow q (Litres/Minute)
Time	(Minutes)	<u>180</u>	<u>320</u>	<u>440</u>	<u>120</u>	<u>180</u>	
Flowmeter	Reading	<u>45.5</u>	<u>46.1</u>	<u>49.3</u>	<u>54.5</u>	<u>54.7</u>	
Dipstick	(Litres)	<u>46.1</u>	<u>49.3</u>	<u>54.5</u>	<u>54.7</u>	<u>55.8</u>	
Water Intake	(Litres)	<u>0.6</u>	<u>3.2</u>	<u>5.2</u>	<u>0.2</u>	<u>1.1</u>	
SECOND STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time	(Minutes)						
Flowmeter	Reading						
Dipstick	(Litres)						
Water Intake	(Litres)						
THIRD STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time	(Minutes)						
Flowmeter	Reading						
Dipstick	(Litres)						
Water Intake	(Litres)						
FOURTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time	(Minutes)						
Flowmeter	Reading						
Dipstick	(Litres)						
Water Intake	(Litres)						
FIFTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time	(Minutes)						
Flowmeter	Reading						
Dipstick	(Litres)						
Water Intake	(Litres)						
SIXTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time	(Minutes)						
Flowmeter	Reading						
Dipstick	(Litres)						
Water Intake	(Litres)						

FIELD DATA FROM LUGEON TESTS

Drillhole No: NMB Inclination: 90 Test No: 1
 Date of Test: 20/03/2013 Test Section from 2 m to 5 m
 Packer Type: Single Packer Pressure 12 kPa
 Bottom of Casing: m Water Level m
 Base of Hole: 5 m Hole \varnothing at test level NMD4 mm
 Pressure gauge height above collar: 2.90 m
 Details of test equipment:
 Calibration Curve No:



GEOMECHANICS
 Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIRST STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		12	20	28	20	12	
Flowmeter Reading	1579,5	1591,9	1603,5	1617,5	1631,5		
Dipstick (Litres)	1591,9	1603,5	1617,5	1631,5	1645,9		
Water Intake (Litres)	12.4	11.6	14	14	14.4		
SECOND STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		30	30	50	30		
Flowmeter Reading	1645,9	1657,4	1663,4	1673,5	1679,9		
Dipstick (Litres)	1653,4	1663,4	1673,5	1679,9	1689,0		
Water Intake (Litres)	7.5	10	10.1	6.4	9.1		
THIRD STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		48	80	12	80	48	
Flowmeter Reading	1689,0	1709,2	1730,0	1751,4	1773,4		
Dipstick (Litres)	1709,2	1730,0	1751,4	1773,4	1795,4		
Water Intake (Litres)	20.2	20,8	21,4	22	22		
FOURTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		66	110	154	110	66	
Flowmeter Reading	1795,9	1798,0	1800,8	1803,7	1806,1		
Dipstick (Litres)	1798,0	1800,8	1803,7	1806,1	1807,4		
Water Intake (Litres)	2.6	2.8	2.9	2.14	1.3		
FIFTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)		84	140	196	140	84	
Flowmeter Reading	1807,4	1809,6	1813,3	1817,7	1820,2		
Dipstick (Litres)	1809,6	1813,3	1817,7	1820,2	1822,5		
Water Intake (Litres)	2.2	3.7	4.4	2.5	2.3		
SIXTH STAGE		Gauge Pressure					Av Flow q (Litres/Minute)
Time (Minutes)							
Flowmeter Reading							
Dipstick (Litres)							
Water Intake (Litres)							




GEOMECHANICS
 Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIELD DATA FROM LUGEON TESTS

Drillhole No: NM 6 Inclination: 90° Test No: 6
 Date of Test: 22/03/2013 Test Section from 17 m to 20 m
 Packer Type: Single Packer Pressure 102 kPa
 Bottom of Casing: 1.50 m Water Level m
 Base of Hole: 20 m Hole Ø at test level NWD 4 mm
 Pressure gauge height above collar: 2.9 m
 Details of test equipment:
 Calibration Curve No:

FIRST STAGE							
		17-20		102		Gauge Pressure 238	
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	1822,5	1824,4	1828,5	1834,7	1840,1	q
Dipstick	(Litres)	1824,4	1828,5	1834,7	1840,1	1844,1	(Litres/Minute)
Water Intake	(Litres)	1.9	4.1	6.2	5.4	4	
SECOND STAGE							
		20-23		180		Gauge Pressure 440	
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	1844,1	1848,9	1857,5	1867,0	1871,9	q
Dipstick	(Litres)	1848,9	1857,5	1867,0	1871,9	1878,2	(Litres/Minute)
Water Intake	(Litres)	4.8	8.6	9.5	4.9	6.3	
THIRD STAGE							
		Gauge Pressure					
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						
FOURTH STAGE							
		Gauge Pressure					
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						
FIFTH STAGE							
		Gauge Pressure					
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						
SIXTH STAGE							
		Gauge Pressure					
Time	(Minutes)						Av Flow
Flowmeter	Reading						q
Dipstick	(Litres)						(Litres/Minute)
Water Intake	(Litres)						

FIELD DATA FROM LUGEON TESTS



GEOMECHANICS

Geotechnical & Civil Contractors
 33 Woburn Street, Chartwell
 P.O. Box 68063, Bryanston, 2021
 Tel: 460-0280 or 460-0202
 Fax: 460-0281
 Cell: 082 772 3910

Hole No: MM7 Inclination: Vertical Test No: 1

Date of Test: 30/03/13 Test Section from 2.00 m to 5.00 m

Drill Type: Single Packer Pressure kPa

Depth of Casing: No Casing Water Level m

Depth of Hole: 23 meters m Hole Ø at test level NWA4 mm

Pressure gauge height above collar: m

Details of test equipment:

Operation Curve No:

STAGE ~~5-8~~ 2-5 Gauge Pressure

	(Minutes)	12	20	28	20	12	Av Flow q (Litres/Minute)
Water	Reading	188	0.2	2.0	3.0	3.0	
Flow	(Litres)	0.2	2.0	3.0	3.0	0.9	
Intake	(Litres)	18.6	1.8	1.0	0.0	2.9	

STAGE 21/03/2013 8-14 5-8 Gauge Pressure

	(Minutes)	30	50	70	50	30	Av Flow q (Litres/Minute)
Water	Reading	0.9	2.2	2.6	3.4	1.8	
Flow	(Litres)	2.2	2.6	3.4	1.8	1.5	
Intake	(Litres)	1.3	0.4	0.8	1.6	0.3	

STAGE 8-11 Gauge Pressure

	(Minutes)	72	128	176	128	72	Av Flow q (Litres/Minute)
Water	Reading	1.5	1.0	1.4	1.6	1.0	
Flow	(Litres)	1.0	1.4	1.6	1.0	1.0	
Intake	(Litres)	0.5	0.4	0.2	0.6	0.0	

STAGE 11-14 22/03/2013 Gauge Pressure

	(Minutes)	199	176	242	176	99	Av Flow q (Litres/Minute)
Water	Reading	1.0	9.8	7.8	20.5	18.9	
Flow	(Litres)	9.8	7.8	20.5	18.9	10.2	
Intake	(Litres)	8.8	2.0	12.7	1.6	8.7	


STAGE 14-17m Gauge Pressure

	(Minutes)	126	224	308	224	126	Av Flow q (Litres/Minute)
Water	Reading	18.4	9.8	14.9	17.0	13.4	
Flow	(Litres)	9.8	14.8	17.0	13.4	7.6	
Intake	(Litres)	9.1	5.1	2.1	3.6	6.058	

STAGE 17-20m Gauge Pressure

	(Minutes)	153	272	374	242	153	Av Flow q (Litres/Minute)
Water	Reading	13.4	5.9	8.5	11.5	6.9	
Flow	(Litres)	5.9	8.8	11.5	6.9	4.4	
Intake	(Litres)	7.5	2.9	2.7	4.6	2.5	

FIELD DATA FROM LUGEON TESTS



GEOMECHANICS
 Geotechnical & Civil Contractors
 33 Woburn Street, Chartwell
 P.O. Box 68063, Bryanston, 2021
 Tel: 460-0280 or 460-0202
 Fax: 460-0281
 Cell: 082 772 3910

Test No: YM7 Inclination: Vertical Test No: 1

Date of Test: 23/03/2013 Test Section from 20 m to 23 m

Type: Single Packer Pressure kPa

Length of Casing: 7.50 m Water Level m

Length of Hole: m Hole ϕ at test level NW14 mm

Gauge height above collar: m

Test equipment:

Curve No:

STAGE 20-23 m Gauge Pressure

(Minutes)	<u>180</u>	<u>300</u>	<u>440</u>	<u>300</u>	<u>180</u>	Av Flow q (Litres/Minute)
Reading	<u>13.4</u>	<u>10.8</u>	<u>16.2</u>	<u>20.3</u>	<u>14.2</u>	
(Litres)	<u>10.8</u>	<u>16.2</u>	<u>20.3</u>	<u>14.2</u>	<u>6.8</u>	
Probe (Litres)	<u>2.6</u>	<u>5.4</u>	<u>4.1</u>	<u>6.1</u>	<u>7.4</u>	

STAGE Gauge Pressure

(Minutes)						Av Flow q (Litres/Minute)
Reading						
(Litres)						
Probe (Litres)						

STAGE Gauge Pressure

(Minutes)						Av Flow q (Litres/Minute)
Reading						
(Litres)						
Probe (Litres)						

STAGE Gauge Pressure

(Minutes)						Av Flow q (Litres/Minute)
Reading						
(Litres)						
Probe (Litres)						

STAGE Gauge Pressure

(Minutes)						Av Flow q (Litres/Minute)
Reading						
(Litres)						
Probe (Litres)						

STAGE Gauge Pressure

(Minutes)						Av Flow q (Litres/Minute)
Reading						
(Litres)						
Probe (Litres)						



GEOMECHANICS

Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIELD DATA FROM LUGEON TESTS			
Drillhole No:	Mm 8	Inclination:	Vertical
Date of Test:	12-04-13	Test No:	1
Packer Type:	Single	Test Section from:	2 m to 49.5 m
Bottom of Casing:	0.00 m	Packer Pressure:	12 kPa
Base of Hole:	4.95 m	Water Level:	m
		Hole Ø at test level:	Mudat mm
Pressure gauge height above collar: 1.70 m			
Details of test equipment:			
Calibration Curve No:			

FIRST STAGE							
2 - 5m		12	Gauge Pressure			20	12
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	0	0	0	0	0	
SECOND STAGE							
5m - 7.65		30	Gauge Pressure			30	30
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	0	0	0	0	0	
THIRD STAGE							
7.65 - 10.50		45.90	Gauge Pressure			76.50	45.90
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	0	0	0	0	0	
FOURTH STAGE							
10.50 - 13.50		63	Gauge Pressure			147	63
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	0	0	0	0	0	
FIFTH STAGE							
13.50 - 16.50		121.50	Gauge Pressure			297	121.50
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	0	0	0	0	0	
SIXTH STAGE							
16.50 - 19.50		148.50	Gauge Pressure			264	148.50
Time	(Minutes)	10	10	10	10	10	Av Flow
Flowmeter	Reading	870	870	870	870	870	q
Dipstick	(Litres)	870	870	870	870	870	(Litres/Minute)
Water Intake	(Litres)	0	0	0	0	0	



GEOMECHANICS
 Geomechanics cc
 Exploration & Geotechnical Contractor
 12 Broadacres Drive, Broadacres
 PO Box 68063, Bryanston, 2021
 Tel: +27 87 808-1501/2
 Fax: +27 11 467 9221
 e-mail: info@geomechanics.co.za

FIELD DATA FROM LUGEON TESTS			
Drillhole No: <u>NM9</u>	Inclination: <u>90</u>	Test No: <u>1</u>	
Date of Test: <u>08/04/2013</u>	Test Section from: <u>2</u> m to: <u>5</u> m	Packer Pressure: <u>12</u> kPa	
Packer Type: <u>Single</u>	Water Level: _____ m	Hole Ø at test level: <u>NWD4</u> mm	
Bottom of Casing: _____ m	Pressure gauge height above collar: <u>2.8</u> m		
Base of Hole: <u>5.00</u> m	Details of test equipment: _____		
Calibration Curve No: _____			

FIRST STAGE		<u>2-5</u>	<u>12</u>	Gauge Pressure <u>28</u>			<u>20</u>	<u>12</u>
Time	(Minutes)	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	Av Flow
Flowmeter	Reading	<u>2013,5</u>	<u>2016,1</u>	<u>2016,4</u>	<u>2016,6</u>	<u>2016,9</u>	<u>2016,9</u>	q
Dipstick	(Litres)	<u>2016,1</u>	<u>2016,4</u>	<u>2016,6</u>	<u>2016,9</u>	<u>2016,9</u>	<u>2017,1</u>	(Litres/Minute)
Water Intake	(Litres)	<u>2.6</u>	<u>0.3</u>	<u>0.2</u>	<u>0.3</u>	<u>0.3</u>	<u>0.2</u>	
SECOND STAGE		<u>5-8</u>	<u>30</u>	Gauge Pressure <u>38</u>			<u>70</u>	<u>50</u>
Time	(Minutes)	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	Av Flow
Flowmeter	Reading	<u>2017,1</u>	<u>2017,7</u>	<u>2018,7</u>	<u>2020,1</u>	<u>2020,8</u>	<u>2020,8</u>	q
Dipstick	(Litres)	<u>2017,7</u>	<u>2018,7</u>	<u>2020,1</u>	<u>2020,8</u>	<u>2020,8</u>	<u>2020,8</u>	(Litres/Minute)
Water Intake	(Litres)	<u>0.6</u>	<u>1</u>	<u>1.4</u>	<u>0.7</u>	<u>0</u>	<u>0</u>	
THIRD STAGE		<u>8-11</u>	<u>48</u>	Gauge Pressure <u>80</u>			<u>112</u>	<u>80</u>
Time	(Minutes)	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	Av Flow
Flowmeter	Reading	<u>2020,8</u>	<u>2020,8</u>	<u>2020,8</u>	<u>2022,2</u>	<u>2023,2</u>	<u>2023,2</u>	q
Dipstick	(Litres)	<u>2020,8</u>	<u>2020,8</u>	<u>2022,2</u>	<u>2023,2</u>	<u>2023,2</u>	<u>2023,6</u>	(Litres/Minute)
Water Intake	(Litres)	<u>0</u>	<u>0</u>	<u>1.4</u>	<u>1</u>	<u>0.4</u>	<u>0.4</u>	
FOURTH STAGE		<u>11-14</u>	<u>99</u>	Gauge Pressure <u>176</u>			<u>242</u>	<u>176</u>
Time	(Minutes)	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	Av Flow
Flowmeter	Reading	<u>2023,6</u>	<u>2024,2</u>	<u>2027,3</u>	<u>2030,4</u>	<u>2033,4</u>	<u>2033,4</u>	q
Dipstick	(Litres)	<u>2024,2</u>	<u>2027,3</u>	<u>2030,4</u>	<u>2033,4</u>	<u>2033,4</u>	<u>2038,1</u>	(Litres/Minute)
Water Intake	(Litres)	<u>0.6</u>	<u>3.1</u>	<u>3.1</u>	<u>3</u>	<u>4.7</u>	<u>4.7</u>	
FIFTH STAGE		<u>14-17</u>	<u>176</u>	Gauge Pressure <u>308</u>			<u>224</u>	<u>176</u>
Time	(Minutes)	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	Av Flow
Flowmeter	Reading	<u>2038,1</u>	<u>2061,1</u>	TOTAL WATER LOSS			<u>2061,1</u>	q
Dipstick	(Litres)	<u>2061,1</u>		PRESSURE TEST CANNOT WORK				(Litres/Minute)
Water Intake	(Litres)							
SIXTH STAGE		<u>17-20</u>	<u>153</u>	Gauge Pressure <u>374</u>			<u>272</u>	<u>374</u>
Time	(Minutes)	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>	Av Flow
Flowmeter	Reading	<u>2072,6</u>	TOTAL WATER LOSS					q
Dipstick	(Litres)		PRESSURE TEST CANNOT WORK					(Litres/Minute)
Water Intake	(Litres)							

Borehole core logs

***Langa Dam site, left flank
(NM1, NM2, NM9)***

HOLE No: NM 1
Sheet 1 of 2

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR-hard rock
MHR-medium hard rock
SR-soft rock
VSR-very soft rock

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 1
Sheet 1 of 2

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)	DEPTH Scale 1:100
91	0	0		NXC		-	-	-	-	-	-	-	-	-	-	0.00
64	0	0		NXC		-	-	-	-	-	-	-	-	-	-	0.50
67	38	0		NWD4												1.57
95	95	21		NWD4	2	FG	LF	<1	B 1 2	0 45 90	10-20 >500 >500	SJ SJ SJ	silt silt silt	0-5 1 1	20 2 2	
86	86	0		NWD4												
100	100	17		NWD4												
74	74	9		NWD4	0											
92	92	54		NWD4		FG	LF	<1	B 1	0 45	10-150 >500	SJ SJ	silt stained	<1 stained	15 2	
64	64	17		NWD4												
84	84	0		NWD4	1											
96	96	0		NWD4												
100	100	0		NWD4		FG	LF	<1	B 1	0 85-90	10-300 -	SJ SJ	stained stained	stained stained	12 -	
97	97	8		NWD4	1											
89	89	34		NWD4												
82	82	32		NWD4												
99	99	56		TNW	0	FG-MG	MF	-	1 2	0 80-90	<300 -	RJ RJ	stained stained	stained stained	8 -	
100	100	72		TNW	1											
99	99	51		TNW	2											



HOLE No: NM 1
Sheet 2 of 2

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock





Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 1
Sheet 2 of 2

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
97	97	84		TNW		FG	LF	<1	B 1	0 85-90	10-300 -	SJ SJ	stained stained	stained stained	12 -
99	99	85		TNW											



25.16

NOTES

- 1) Water table at 14.2m.
- 2) Poor material recovery is attributed to washing out of fines.

CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Jan Kiri
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/03/23
DATE : 2013/04/08
DATE : 11/10/2013 15:54
TEXT : ..HOLES\Notepads\NM110.txt

ELEVATION :
X-COORD : X3296840
Y-COORD : 31 Y0067796

HOLE No: NM 1

HOLE No: NM 2
Sheet 1 of 1

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 2
Sheet 1 of 1

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
56	0	0		NXC		-	-	-	-	-	-	-	-	-	-
60	0	0		NWD4		-	-	-	-	-	-	-	-	-	-
87	83	0		NWD4	3	FG	LF	<1	B 1	0	<40	SJ	silt	<1	30
64	64	0		NWD4											
45	32	0		NWD4											
85	85	13		NWD4	1	FG	LF	<1	B 1	0	<40	SJ	silt	<1	30
77	77	35		NWD4		FG-MG	MF	-	-	-	-	-	-	-	-
89	89	31		NWD4	0										
90	90	60		TNW	2	FG-MG	MF	-	1	0	<100	RJ	-	-	10
98	98	61		TNW	1										
98	98	45		TNW	0	FG	LF	<1	B 1	0	10-200	SJ	-	-	15



HOLE No: NM 9
Sheet 1 of 1

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 9
Sheet 1 of 1

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
98	0	0		NXC		-	-	-	-	-	-	-	-	-	-
87	0	0		NXC		-	-	-	-	-	-	-	-	-	-
100	0	0		NWD4		-	-	-	-	-	-	-	-	-	-
95	75	29		NWD4	1										
46	38	0		NWD4											
100	95	16		NWD4		FG	LF	<1	B	0	<100	SJ	silt	0-2	20
51	51	0		NWD4	0										
68	52	0		NWD4											
100	100	19		NWD4											
100	100	7		NWD4	0	FG	LF	<1	B 1	0	<100 -	SJ SJ	silt silt	<1 <0.5	25 -
75	75	0		NWD4											
100	100	33		NWD4											
99	99	23		NWD4	1										
87	87	17		NWD4											
93	93	31		TNW	Total water loss	FG	LF	<1	B	0	10-150	SJ	stained	stained	15
76	76	50		TNW											
100	100	58		TNW	Total water loss										
92	92	55		TNW											




CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Jan Kiri
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/04/06
DATE : 2013/04/11
DATE : 11/10/2013 15:54
TEXT : ..HOLES\Notepads\NM110.txt

ELEVATION :
X-COORD : X3296887
Y-COORD : 31 Y0068039

HOLE No: NM 9



CONTRACTOR :
MACHINE :
DRILLED BY :
PROFILED BY :
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION :
DIAM :
DATE :
DATE :
DATE : 11/10/2013 15:54
TEXT : ..HOLES\Notepads\NM110.txt

ELEVATION :
X-COORD :
Y-COORD :
LEGEND
SUMMARY OF SYMBOLS

***Langa Dam site, river section
(NM3)***

HOLE No: NM 3
Sheet 1 of 1

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 3
Sheet 1 of 1

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
59	0	0		NXC											
10	0	0		NXC		-	-	-	-	-	-	-	-	-	-
57	53	53		NWD4	0	MG	MF	-	1	80-90	-	RJ	sand	<1	-
88	88	27		NWD4		MG	MF	-	1	0	>20	RJ	stained	stained	8
100	100	0		NWD4		FG	LF	<1	B	0	<10	SJ	stained	stained	40
89	89	0		NWD4	0										
96	96	49		NWD4	0										
100	100	31		NWD4	0										
97	97	11		NWD4	0										
99	99	35		NWD4	0	FG	LF	<1	B	0	>20	SJ	stained	stained	10
96	96	35		NWD4	0				1	45	>500	SJ	stained	stained	2
				NWD4	0				2	70	>400	SJ	stained	stained	2-3
97	97	7		NWD4	0										
98	98	37		NWD4	0										
100	100	49		NWD4	0										
100	100	23		NWD4	0										



CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Polite
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/03/25
DATE : 2013/04/08
DATE : 11/10/2013 15:54
TEXT : ..HOLES\Notepads\NM110.txt

ELEVATION :
X-COORD : X3296829
Y-COORD : 31 Y0067717

HOLE No: NM 3

Langa Dam site, right flank
(NM4 – NM7)

HOLE No: NM 4
Sheet 1 of 1

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR-hard rock
MHR-medium hard rock
SR-soft rock
VSR-very soft rock

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 4
Sheet 1 of 1

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
0	0	0		NXC		-	-	-	-	-	-	-	-	-	-
0	0	0		NXC		-	-	-	-	-	-	-	-	-	-
64	23	0		NWD4	0	FG	LF	<1	B	0	<10	SJ	silt	<1	40
85	85	0		NWD4	0	FG	LF	<1	B	0	10-80	SJ	silt	<0.5	30
85	85	7		NWD4	0	FG	LF	<1	B	1	80	SJ	silt	<0.5	-
96	96	41		NWD4	0										
100	100	12		NWD4	0										
98	98	17		NWD4	0										
100	100	9		NWD4	0										
99	99	36		NWD4	0	FG	LF	<1	B	0	60-180	SJ	stained	stained	15
95	95	37		NWD4	0				1	30	>1000	SJ	stained	stained	1
95	95	11		NWD4	0				2	70	>500	SJ	stained	stained	2
100	100	26		NWD4	0										
95	95	43		NWD4	0										
100	100	28		NWD4	0										



CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Polite
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/03/21
DATE : 2013/03/25
DATE : 11/10/2013 15:54
TEXT : ..HOLES\Notepads\NM110.txt

ELEVATION :
X-COORD : X3296879
Y-COORD : 31 Y0067686

HOLE No: NM 4

HOLE No: NM 5
Sheet 2 of 2

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular





Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 5
Sheet 2 of 2

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
99	99	15		TNW											
73	73	29		TNW											
100	100	65		TNW											



25.27

NOTES

- 1) Water table measured at 9.85m.
- 2) Poor material recovery is attributed to washing out of fines.

CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Wilson
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/03/21
DATE : 2013/04/08
DATE : 11/10/2013 15:54
TEXT : ..HOLES\Notepads\NM110.txt

ELEVATION :
X-COORD : X3296866
Y-COORD : 31 Y0067658

HOLE No: NM 5

HOLE No: NM 6
Sheet 1 of 2

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR-hard rock
MHR-medium hard rock
SR-soft rock
VSR-very soft rock

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 6
Sheet 1 of 2

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
92	0	0		NXC		-	-	-	-	-	-	-	-	-	-
94	0	0		NXC		-	-	-	-	-	-	-	-	-	-
82	18	0		NWD4		-	-	-	-	-	-	-	-	-	-
79	49	0		NWD4	17	FG	LF	<1	B	0	<10	SJ	silt	>1	>50
95	76	0		NWD4		-	-	-	-	-	-	-	-	-	-
86	86	0		NWD4		-	-	-	-	-	-	-	-	-	-
90	90	9		NWD4	10	-	-	-	-	-	-	-	-	-	-
100	100	0		NWD4		FG	LF	<1	B	0	<20	SJ	silt	1	40
49	23	0		NWD4		-	-	-	-	-	-	-	-	-	-
94	48	0		NWD4	6	-	-	-	-	-	-	-	-	-	-
100	0	0		NWD4		-	-	-	-	-	-	-	-	-	-
93	0	0		NWD4		-	-	-	-	-	-	-	-	-	-
88	0	0		NWD4	1	-	-	-	-	-	-	-	-	-	-
92	0	0		NWD4		-	-	-	-	-	-	-	-	-	-
66	0	0		NWD4		-	-	-	-	-	-	-	-	-	-
100	0	0		NWD4		-	-	-	-	-	-	-	-	-	-
67	0	0		NWD4	1	-	-	-	-	-	-	-	-	-	-
53	0	0		NWD4		-	-	-	-	-	-	-	-	-	-
48	0	0		NWD4		-	-	-	-	-	-	-	-	-	-
100	91	21		NWD4	1	FG-MG	MF	-	-	-	-	-	-	-	-
86	86	0		NWD4		FG-MG	MF	-	-	-	-	-	-	-	-
86	86	0		NWD4		FG	MF	-	B	0	<80	SJ	silt	>1	30
100	100	0		NWD4		-	-	-	-	-	-	-	-	-	-
69	69	0		NWD4	1	-	-	-	-	-	-	-	-	-	-
									1	0	<100	SJ	stained	stained	15



HOLE No: NM 6
Sheet 2 of 2

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock





Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 6
Sheet 2 of 2

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
100	100	0		NWD4		FG	MF	<1	2		60	300	SJ	stained	3
84	84	29		NWD4					3		45	100	SJ	stained	10
95	97	43		NWD4											



19.60 Moderately weathered highly fractured dark grey fine grained laminated soft rock SHALE.

25.06 Slightly weathered highly fractured dark grey fine grained laminated hard rock SHALE with a very highly fractured zone between 22.00m and 22.23m.

NOTES

- 1) Water table at 13.20m.
- 2) Poor material recovery is attributed to washing out of fines.

CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Jan Kiri
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/03/20
DATE : 2013/03/23
DATE : 11/10/2013 15:54
TEXT : ..HOLESNotepadsNM110.txt

ELEVATION :
X-COORD : X3296909
Y-COORD : 31 Y0067563

HOLE No: NM 6

HOLE No: NM 7
Sheet 1 of 2

JOB NUMBER: J01763

ROCK FABRIC MF -massive BF -bedded FF -foliated CF -cleaved SF -schistose GF -gneissose LF -laminated	GRAIN SIZE FG -fine grained MG -medium grain CG -coarse grain	JOINT ROUGHNESS SLJ-slickensided SJ -smooth RJ -rough	ROCK HARDNESS EHR-extremely hard rock VHR-very hard rock HR-hard rock MHR-medium hard rock SR -soft rock VSR-very soft rock
	JOINT SPACING VCJ-very close spacg CJ -close spacing MJ -medium spacing WJ -wide spacing VWJ-very wide spacng	JOINT SHAPE CUR-curvilinear PLA-planar UND-undulating STE-stepped IRR-irregular	




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 7
Sheet 1 of 2

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
				NXC		-	-	-	-	-	-	-	-	-	-
				NWD4		-	-	-	-	-	-	-	-	-	-
				NWD4	6										
				NWD4											
				NWD4		FG	LF	<1	B	0	<20	SJ	silt	<1	30
				NWD4	1										
				NWD4											
				NWD4		FG	LF	<1	B	0	<20	SJ	silt	<0.5	30
				NWD4	0										
				NWD4		FG	LF	<1	B	0	<20	SJ	silt	<1	30
				NWD4		FG	LF	<1	B	0	<20	SJ	silt	<0.5	30
				NWD4	0										
				NWD4		FG	LF	<1	B	0	<20	SJ	silt	<1	30
				NWD4	2										
				NWD4		FG	LF	<1	B	0	<20	SJ	silt	<0.5	30
				NWD4		-	-	-	-	-	-	-	-	-	-
				NWD4											
				NWD4	1										
				NWD4											
				NWD4											
				NWD4	1										
				NWD4											
				NWD4		FG-MG	MF	-	-	-	-	-	-	-	-
				NWD4	1										



HOLE No: NM 7
Sheet 2 of 2

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 7
Sheet 2 of 2

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
91	91	0		NWD4											
100	100	44		NWD4		FG	LF	<1	B 1	0 90	<200 -	SJ SJ	stained stained	stained stained	20 -
80	80	0		NWD4											



Slightly weathered highly fractured light grey fine grained laminated hard rock SHALE.

- NOTES
- 1) Water table at 10.78m.
 - 2) Poor material recovery is attributed to washing out of fines.

CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Jacson
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/03/20
DATE : 2013/03/25
DATE : 11/10/2013 15:54
TEXT : ..HOLESNotepadsNM110.txt

ELEVATION :
X-COORD : X3296926
Y-COORD : 31 Y0067530

HOLE No: NM 7

Langa Dam, left spillway
(NM10)

HOLE No: NM 10
Sheet 1 of 1

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 10
Sheet 1 of 1

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
33	9	0		NXC										
53	0	0		NXC	-	-	-	-	-	-	-	-	-	-
99	0	0		NWD4										
92	92	0		NWD4										
47	47	0		NWD4	FG	LF	<1	B	0	<50	SJ	silt	<2	30
73	73	15		NWD4	-	-	-	-	-	-	-	-	-	-
95	95	9		NWD4										
88	88	32		TNW										
85	85	0		TNW	FG	LF	<1	B 1	0 80-90	20-150 0	SJ SJ	stained stained	stained stained	20 -
87	87	19		TNW										
100	100	22		TNW										
100	100	0		NWD4										
90	90	24		NWD4										



CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Polite
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/04/06
DATE : 2013/04/11
DATE : 11/10/2013 15:54
TEXT : ..HOLES\Notepads\NM110.txt

ELEVATION :
X-COORD : X3296672
Y-COORD : 31 Y0068163

HOLE No: NM 10

Langa Dam, right spillway
(NM8)

HOLE No: NM 8
Sheet 1 of 1

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NM 8
Sheet 1 of 1

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	LUGEON VALUES	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)		
			90	0	0		NXC										
			73	0	0	12	SPT										
			90	0	0		NWD4		0								
			64	0	0	17	SPT										
			81	0	0		NWD4										
			89	0	0	30	SPT										
			100	0	0		NWD4		0								
			80	0	0	20	SPT										
			95	0	0		NWD4										
			100	0	0	REFUSAL	SPT										
			96	89	42		NWD4		0								
			99	99	7		NWD4	FG	LF	<1	B 1 2	0 45 45	10-150 >500 >500	SJ SJ SJ	silt silt silt	0-3 1 1	20 1 1
			67	53	10		NWD4		0								
			71	71	11		NWD4	FG	LF	<1	B 1	0 70	30-150 >500	SJ SJ	silt silt	<1 <1	18 1
			83	83	0		NWD4	FG	LF	<1	B 1 2	0 45 45	10-150 >500 >500	SJ SJ SJ	silt silt silt	0-3 1 1	20 1 1
			100	100	0		NWD4										
			95	95	0		NWD4	FG	LF	<1	B 1	0 70	30-150 >500	SJ SJ	silt silt	<1 <1	18 1
			98	98	11		NWD4										
			100	22	0		NWD4										



NOTES

1) Water table at 10.8m.

2) Poor material recovery is attributed to washing out of fines.

10.8m

CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Polite
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/04/11
DATE : 2013/04/16
DATE : 11/10/2013 15:54
TEXT : ..HOLESNotepadsNM110.txt

ELEVATION :
X-COORD : X3296906
Y-COORD : 31 Y0067415

HOLE No: NM 8

***Langa quarry site
(NQ1 – NQ3)***

HOLE No: NQ 1
Sheet 1 of 1

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NQ 1
Sheet 1 of 1

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
96	0	0		NXC	-	-	-	-	-	-	-	-	-	-
100	0	0		NXC	-	-	-	-	-	-	-	-	-	-
84	0	0		NWD4	-	-	-	-	-	-	-	-	-	-
88	82	9		NWD4	FG	LF	<1	B	0	<100	SJ	silt	0-3	17
77	65	40		NWD4										
79	79	0		NWD4										
75	75	0		NWD4	FG	LF	<1	B 1	0 80-90	20-150 -	SJ SJ	silt silt silt	<1 <1	15 -
89	89	15		NWD4										
84	84	9		NWD4										
91	91	62		NWD4										
100	100	61		NWD4										
89	89	35		NWD4	FG	LF	<1	B 1 2	0 70 80-90	<200 >1000 -	SJ SJ SJ	stained stained stained	10 - -	
90	90	0		TNW										
97	97	81		NWD4										
99	99	73		NWD4										
100	100	57		NWD4										



CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Jan Kiri
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/04/13
DATE : 2013/04/16
DATE : 11/10/2013 15:55
TEXT : ..OLESNotepadsWQ12&3.txt

ELEVATION :
X-COORD : X3297827
Y-COORD : 31 Y0068121

HOLE No: NQ 1

HOLE No: NQ 2
Sheet 1 of 1

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NQ 2
Sheet 1 of 1

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
				NXC										
33	10	0		NXC	-	-	-	-	-	-	-	-	-	-
72	35	0		NXC										
61	18	0		NXC										
94	94	0		NWD4										
				NWD4	FG	LF	<1	B	0	<100	SJ	silt	0-2	23
99	99	0		NWD4										
100	100	53		NWD4	FG	LF	<1	B	0	<150	SJ	silt	<2	14
59	59	0		NWD4	FG	LF	<1	B	0	<50	SJ	silt	0.5	40
77	77	0		NWD4										
83	83	83		NWD4	FG	LF	<1	B 1	0 80-90	<20 -	SJ SJ	silt silt	<1 <1	>50 -
97	97	22		NWD4										
98	98	69		NWD4										
100	100	71		NWD4										
				NWD4	FG	LF	<1	B 1	0 70	>50 >1000	SJ SJ	stained stained	stained stained	8 1
98	98	49		NWD4				2	80-90	-	SJ	stained	stained	-
84	84	36		NWD4										
100	100	53		NWD4										



CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Polite
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/04/15
DATE : 2013/04/17

ELEVATION :
X-COORD : X3297649
Y-COORD : 31 Y0068037

DATE : 11/10/2013 15:55
TEXT : ..OLESNotepadsWQ12&3.txt

HOLE No: NQ 2

HOLE No: NQ 3
Sheet 1 of 1

JOB NUMBER: J01763

ROCK FABRIC
MF -massive
BF -bedded
FF -foliated
CF -cleaved
SF -schistose
GF -gneissose
LF -laminated

GRAIN SIZE
FG -fine grained
MG -medium grain
CG -coarse grain

JOINT SPACING
VCJ-very close spacg
CJ -close spacing
MJ -medium spacing
WJ -wide spacing
VWJ-very wide spacng

JOINT ROUGHNESS
SLJ-slickensided
SJ -smooth
RJ -rough

JOINT SHAPE
CUR-curvilinear
PLA-planar
UND-undulating
STE-stepped
IRR-irregular

ROCK HARDNESS
EHR-extremely hard rock
VHR-very hard rock
HR -hard rock
MHR-medium hard rock
SR -soft rock
VSR-very soft rock




Department of Water Affairs
uMkhomazi Water Project

HOLE No: NQ 3
Sheet 1 of 1

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing (mm)	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
82	0	0		NXC	-	-	-	-	-	-	-	-	-	-
100	0	0		NXC	-	-	-	-	-	-	-	-	-	-
88	81	34		NWD4	FG	LF	<1	B	0	<100	SJ	silt	0-2	30
87	87	7		NWD4	FG	LF	<1	B	0	<100	SJ	silt	0-2	25
80	80	7		NWD4										
100	100	34		NWD4										
90	90	0		NWD4	FG	LF	<1	B 1 2	0 70 80-90	10-400 >1000 -	SJ SJ SJ	stained stained stained	stained stained stained	20 1 -
99	99	25		NWD4										
100	94	19		NWD4										
100	100	96		TNW	FG-MG	MF	-	1	0-10	10-500	RJ	stained	stained	8
100	100	77		TNW										
100	100	55		TNW	FG	LF	<1	B 1 2	0 70 80-90	10-400 >1000 -	SJ SJ SJ	stained stained stained	stained stained stained	20 1 -









CONTRACTOR : Geomech
MACHINE : YWE
DRILLED BY : Jan Kiri
PROFILED BY : JJ Ehlers
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
DIAM :
DATE : 2013/04/11
DATE : 2013/04/15

ELEVATION :
X-COORD : X3297477
Y-COORD : 31 Y0067933

DATE : 11/10/2013 15:55
TEXT : ..OLESNotepadsWQ12&3.txt

HOLE No: NQ 3

	GRAVEL	{SA02}
	SILT	{SA06}
	CLAY	{SA08}
	SHALE	{SA12}
	DOLERITE	{SA18}{SA42}
5.5 ▼	PERMANENT WATER TABLE	{SA35}
	ROOTS	{SA40}

CONTRACTOR :
MACHINE :
DRILLED BY :
PROFILED BY :
TYPE SET BY : JJ Ehlers
SETUP FILE : Borehole.SET

INCLINATION :
DIAM :
DATE :
DATE :
DATE : 11/10/2013 15:55
TEXT : ..OLESNotepadsWQ12&3.txt

ELEVATION :
X-COORD :
Y-COORD :
LEGEND
SUMMARY OF SYMBOLS

Tunnel outlet
(BH8)

HOLE No: BH 8

Sheet 1 of 1

JOB NUMBER: J01763

ROCK FABRIC
 MF -massive
 BF -bedded
 FF -foliated
 CF -cleaved
 SF -schistose
 GF -gneissose
 LF -laminated

GRAIN SIZE
 FG -fine grained
 MG -medium grain
 CG -coarse grain

JOINT SPACING
 VCJ-very close spacg
 CJ -close spacing
 MJ -medium spacing
 WJ -wide spacing
 VWJ-very wide spacng

JOINT ROUGHNESS
 SLJ-slickensided
 SJ -smooth
 RJ -rough

JOINT SHAPE
 CUR-curvilinear
 PLA-planar
 UND-undulating
 STE-stepped
 IRR-irregular

ROCK HARDNESS
 EHR-extremely hard rock
 VHR-very hard rock
 HR-hard rock
 MHR-medium hard rock
 SR-soft rock
 VSR-very soft rock




Department of Water Affairs
 uMkhomazi Water Project

HOLE No: BH 8

Sheet 1 of 1

JOB NUMBER: J01763

%Mater recov	%Core recov	%RQD	SPT	DRILLING METHOD	Grain Size	Rock Fabric	Fabric Spacing (mm)	No. of Joints sets	Joints incl (deg)	Joints spacing	Joints rough & Shape	Fill type	Fill thick (mm)	Frac Freq (m)
				NXC										
				NXC										
		8		SPT										
				NWD4										
43	23	0		NWD4										
100	0	0		NWD4										
51	0	0	15	SPT										
100	0	0		NWD4										
92	0	0		NWD4										
89	0	0	35	SPT										
93	0	0		NWD4										
49	0	0	55	SPT										
54	0	0		NWD4										
100	100	0		NWD4										
100	100	60		NWD4	FG	LF	<1	B 1	0	10-150	SJ	silt	<0.5	11
100	100	22		NWD4										
96	96	14		NWD4										
100	100	45		NWD4	FG	LF	<1	B 1	0	<100 >200	SJ	stained	stained	13
100	100	45		NWD4										
87	87	0		NWD4										
78	78	0		NWD4	FG	LF	<1	B 1	0	<100 <200	SJ	stained	stained	30
78	78	0		NWD4										
95	95	0		NWD4										
81	81	21		NWD4	FG	LF	<1	B 1	0	<100 >200	SJ	stained	stained	13
81	81	21		NWD4										
67	67	60		NWD4										
67	67	60		NWD4										



CONTRACTOR : Geomech
 MACHINE : YWE
 DRILLED BY : Wilson
 PROFILED BY : JJ Ehlers
 TYPE SET BY : JJ Ehlers
 SETUP FILE : Borehole.SET

INCLINATION : VERTICAL
 DIAM :
 DATE : 2013/03/16
 DATE : 2013/03/22
 DATE : 06/11/2013 15:16
 TEXT : ..REHOLES\Notepad\BH8.txt

ELEVATION :
 X-COORD : X3295219
 Y-COORD : 31 Y 067426

HOLE No: BH 8

Borehole core photographs

***Langa Dam site, left flank
(NM1, NM2, NM9)***

BOREHOLE: NM 1 LENGTH: 25.16m INCLINATION: VERTICAL

0 0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8 0.9 1 1.1 1.2 1.3 1.4 1.5



Box 1 of 4
0.00m to 7.61m


Box 2 of 4
7.61m to 15.08m

Box 3 of 4
15.08m to 22.08m

UMkhomasi Water Project
GEOTECHNICAL INVESTIGATIONS

BOREHOLE: NM 2 LENGTH: 20.00m INCLINATION: VERTICAL

0 0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8 0.9 1 1.1 1.2 1.3 1.4 1.5




Box 1 of 3
0.00m to 9.50m

Box 2 of 3
9.50m to 17.00m

Box 3 of 3
17.00m to 20.00m

UMkhomasi Water Project
GEOTECHNICAL INVESTIGATIONS

BOREHOLE: NM 9 LENGTH: 20.11m INCLINATION: VERTICAL



Box 1 of 3
0.00m to 8.00m

Box 2 of 3
8.00m to 14.80m

Box 3 of 3
14.80m to 20.11m

GEOTECHNICAL INVESTIGATIONS

UMkhomasi Water Project

***Langa Dam site, river section
(NM3)***

BOREHOLE: NM 3 LENGTH: 20.00m INCLINATION: VERTICAL



Box 1 of 3
0.00m to 8.00m

Box 2 of 3
8.00m to 14.90m

Box 3 of 3
14.90m to 20.00m

UMkhomasi Water Project
GEOTECHNICAL INVESTIGATIONS

Langa Dam site, right flank
(NM4 – NM7)

BOREHOLE: NM 4 LENGTH: 20.00m INCLINATION: VERTICAL

0 0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8 0.9 1 1.1 1.2 1.3 1.4 1.5



Box 1 of 3
0.00m to 7.80m


Box 2 of 3
7.80m to 14.35m

Box 3 of 3
14.35m to 20m

UMkhomasi Water Project
GEOTECHNICAL INVESTIGATIONS

BOREHOLE: NM 5 LENGTH: 25.27m INCLINATION: VERTICAL

0 0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8 0.9 1 1.1 1.2 1.3 1.4 1.5



Box 1 of 4
0.00m to 7.17m

Box 2 of 4
7.17m to 14.60m


Box 3 of 4
14.60m to 21.20m

NM 5

Page 1 of 2

uMkhomasi Water Project
GEOTECHNICAL INVESTIGATIONS

BOREHOLE: NM 6 LENGTH: 25.11m INCLINATION: VERTICAL



Box 1 of 4
0.00m to 7.69m

Box 2 of 4
7.69m to 15.50m

Box 3 of 4
15.50m to 23.70m

NM 6

Page 1 of 2

UMkhomasi Water Project

GEOTECHNICAL INVESTIGATIONS

BOREHOLE: NM 7 LENGTH: 25.00m INCLINATION: VERTICAL

0 0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8 0.9 1 1.1 1.2 1.3 1.4 1.5



Box 1 of 3
0.00m to 7.50m



Box 2 of 3
7.50m to 17.00m



Box 3 of 3
17.00m to 25.00m

uMkhomasi Water Project
GEOTECHNICAL INVESTIGATIONS

Langa Dam, left spillway
(NM10)

BOREHOLE: NM 10 LENGTH: 20.02m INCLINATION: VERTICAL



Box 1 of 3
0.00m to 8.62m

Box 2 of 3
8.62m to 16.37m

Box 3 of 3
16.37m to 20.02m

UMkhomasi Water Project
GEOTECHNICAL INVESTIGATIONS

Langa Dam, right spillway
(NM8)

BOREHOLE: NM 8 LENGTH: 20.00m INCLINATION: VERTICAL

0 0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8 0.9 1 1.1 1.2 1.3 1.4 1.5



Box 1 of 3
0.00m to 7.05m



Box 2 of 3
7.05m to 15.00m



Box 3 of 3
15.00m to 20.00m

uMkhomasi Water Project
GEOTECHNICAL INVESTIGATIONS

Langa quarry site
(NQ1 – NQ3)

BOREHOLE: NQ 1 LENGTH: 20.19m INCLINATION: VERTICAL

0 0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8 0.9 1 1.1 1.2 1.3 1.4 1.5



Box 1 of 3
0.00m to 7.77m

Box 2 of 3
7.77m to 15.52m

Box 3 of 3
15.52m to 20.19m

UMkhomasi Water Project
GEOTECHNICAL INVESTIGATIONS

BOREHOLE: NQ 2 LENGTH: 20.07m INCLINATION: VERTICAL

0 0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8 0.9 1 1.1 1.2 1.3 1.4 1.5



Box 1 of 3
0.00m to 0.07m

Box 2 of 3
0.07m to 0.157m

Box 3 of 3
0.157m to 0.2007m

UMkhomasi Water Project
GEOTECHNICAL INVESTIGATIONS

BOREHOLE: NQ 3 LENGTH: 20.18m INCLINATION: VERTICAL



Box 1 of 3
0.00m to 7.44m

Box 2 of 3
7.44m to 14.71m

Box 3 of 3
14.71m to 20.18m

UMkhomasi Water Project
GEOTECHNICAL INVESTIGATIONS

Tunnel outlet
(BH8)

BOREHOLE: BH 8 LENGTH: 20.10m INCLINATION: VERTICAL

0 0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8 0.9 1 1.1 1.2 1.3 1.4 1.5 metres



Box 1 of 3
0.00m to 7.27m

Box 2 of 3
7.27m to 14.17m

Box 3 of 3
14.17m to 20.17m

BH 8

Page 1 of 1